

# LIU Wire Scanner Project

Ray Veness, for the LIU WS Team

Slides from



JL Sirvent, D.Gudkov,

# Status of PSB prototype

- Installed in EYETS 16-17
  - 'Final' mechanics,
  - development control system,
  - development acquisition systems
- Tests with beam, more than 900 scans recorded in June 2017
  - Benchmarking with the operational scanner
  - Validated mechanical design (with exception - see next slide)
  - Testing of prototype acquisition systems
- Intervention in TS3 to swap the instrument with the spare
  - Instrument assembled and tested by VSC (awaiting final OK to install)
  - Now on the test bench for calibration and burn-in tests

# New fast wire scanner prototype in PS Booster (4L1)

*Prototype installed in PS Booster on 15.03.2017  
Ready for operation*



# New fast wire scanner. Kinematic Unit

- **Interchangeability**


- One design of kinematic unit for all machines
- Interchangeability of components

- **Design and Production Features**

- Both shaft supports located in the stepped chamber
- No drum
- Direct drive
- Cantilevered shaft
- Magnetic auto-return device (magnetic brake)
- Standard CF flange DN273
- Optimised design of forks (reduced deformation)
- Optimized design of optical encoder disc

- **Vacuum**

- Optical encoder focusers are outside vacuum
- Hybrid bearings (SS races, ceramic balls)
- Vacuum compatible motor supplied directly from subcontractor (CERN qualified)
- Increased stepped chamber wall thickness (0.4 mm vs. 0.3 mm)




*Designed in collaboration with EN-MME  
(N. Chritin, A. Demougeot)*






# Shaft Angular Position Measurements. Optical Position Sensor

- Optical encoder disk located inside vacuum
- Follows the shaft movement
- Lens system and optical fiber are located outside the vacuum volume
  - Trapped volumes avoided
  - Reduced outgassing load
- Focal distance adjustment possibility by means of fine pitch thread
  - Access from outside without venting
- Glass disk with chrome encoder pattern deposition (baseline)
  - So far better optical properties
  - Disk holder required (2 additional parts)
  - Higher inertia
- Metal disk with laser engraved encoder pattern (preferred upgrade)
  - Optical properties are comparable with glass disk (by recent tests)
  - Laser engraving in collaboration with Dundee University
  - Lower inertia due to optimised design
  - Installation directly on the shaft
- Bakable up to 200 °C (metal disk)



*roughness of optical track: Rt0.04*  
*Optical slits pitch 0.02 mm.*




*...Acquisition will be discussed by Federico...*

# PS Prototype

- On-schedule for installation in YETS 17-18
  - Mechanics arriving
  - ECR approved by IEFC
  - Control and acquisition will be available – deciding what to use
- Instruments and tanks will be used as spares for series
  - No significant changes to designs.

# PS Prototype Assembly and installation planning




# LIU Series production

- Control system
  - Prototype under production for installation in the PS
  - Series will be launched first Semester 2018, based on PS experience
- Mechanics
  - Specification committee for vacuum tanks passed on 17/8/17
  - Production of all components now in progress
  - Expect to be able to start assembly first quarter 2018
  - Still on schedule to be ready for early LS2
- Acquisition system
  - Final review to decide on baseline will be held xxx



# LIU Series: Installation planning




Recent results from PSB prototype testing

# 3. PSB Prototype Beam Tests:



## 3.1 Precision on beam width determination

- Beam Sigma spread comparison for prototype and operational (Ring 3 Horizontal)
- LHC25 and ISOLDE beams at different energies.
- Many points per sigma in both scanners : 200 – 500
- **Successful Prototype operation:**
  - Similar performance for LHC25ns (Dominated by amplitude statistics in both BWS?)
  - Beam sigma errors → **Prototype ± 0,7% , Operational ±1,3%** (ISOLDE).

Detectors detail



ICECAL\_V3 FE detail





Beam Type	Operational	Prototype
LHC25 1.4GeV	2559 ± 31, 1.2%	2569 ± 37, 1.4%
ISO 588 MeV/c	8021 ± 125, 1.6%	8245 ± 52, 0.6%
ISO 886 MeV/c	6354 ± 88, 1.4%	6571 ± 46, 0.7%
ISO 1.39 GeV/c	5302 ± 44, 0.8%	5538 ± 38, 0.7%
ISO 1.92 GeV/c	4880 ± 53, 1.1%	5025 ± 34, 0.7%

Beam sigma measurement (um) and spread during MD in um and %.


# 3. PSB Prototype Beam Tests:

## 3.1 HDR acquisition system evaluation

- **Aim:** Ease BWS operation and avoid tuneable parameters (HV+Filter selection).
- Prototype equipped with two secondary acquisition systems:
  - A) **Standard:** Single channel acquired on surface.
  - B) **HDR** Based on Q-PMT detector: 4 channels acquired on tunnel with ICECAL FE.



Detectors detail



ICECAL\_V3 FE detail


Scint. photon yield varied by  $1e3$ :

- **STD** → Required filter changes
- **HDR** → Static configuration  
→ PMT Saturation free

# 3. PSB Prototype Beam Tests:


## 3.1 Identified issues and actions

- **Issue:**
  - Not operated since then → Glass Disk was slipping into the BWS holder.
  - Initial calibration table not valid anymore. Incorrect beam projections.
  - Data shown was corrected by software (but potentially biased by this effect)



- **Actions:**
  - New BWS with improved disk holder is prepared to be installed on next TS (19/09/2017)
  - Scanner is under testing prior to installation → Calibration and performance assessment on optical bench.
  - Small Scintillators to be substituted by bigger ones → Expected Improved amplitude statistics.

Detectors detail



ICECAL\_V3 FE detail

end



