



COOLING & VENTILATION INFRASTRUCTURE

Mauro Nonis
Pedro Cabral



ENGINEERING
DEPARTMENT

CLIC CEIS Working Group Meeting 22/06/2018

Outline




1 – CV systems, air infrastructure

2 – Open questions

3 – Future work


Main Tunnel



Designing for:

- 28°C
- 0,188 kg/s water p/module



Site	Heat Loads		Flow Rate AHU/EXU	ΔT	System
Main tunnel, two beam	Updated + lighting	248 W/m	129888 m ³ /h	5°C	Transversal flow, AHUs in alcoves
Main tunnel, klystron side		250 W/m	130843 m ³ /h		Transversal flow, AHUs / DXUs in service compartment
Main tunnel, modules side		225 W/m	117858 m ³ /h		



$$\frac{HL_{BDS, cdr}}{HL_{tunnel, cdr}} = 35\%$$



Site	Heat Loads		Flow Rate AHU	ΔT	System
BDS	35% tech HL tunnel + lighting	177 W/m	100493 m ³ /h	5°C	Transversal flow, AHUs in alcoves

Caverns



Site	Heat Loads	Flow Rate AHU	ΔT	System
Service Cavern	Unknown HL	-	5°C	Dedicated AHU inside the caverns
UTRA, UTRC	CDR + lighting 99 kW, 104 kW	59081 m ³ /h, 61946 m ³ /h		
Cavern 1.3, 1.4, 2.1, 3.1	Unknown HL	-		
Cavern 2.2, 3.2 BC2 Cavern e ⁺ / e ⁻	CDR + lighting 158 kW, 158 kW 30 kW	94233 m ³ /h, 94233 m ³ /h 17910 m ³ /h		


Beam Dumps






- Beam dumps should be closed spaces
- Air recirculation + “fresh air” from the tunnel – flow rate?

Site	Heat Loads		Flow Rate AHU	ΔT	System
Drive beam dumps	CDR + lighting	6 kW	3684 m ³ /h	5°C	Dedicated AHU inside the beam dump caverns
Main beam dumps		143 kW	85493 m ³ /h		

Injectors, Booster, Damping Rings





- Many surface CV buildings
- Is recycling allowed? (RP)






Site	Heat Loads	System
Drive beam injector	Updated values (Alexej) + lighting	Longitudinal flow, AHUs at the surface
Main beam injector		
Booster		
Pre-damping ring e ⁺		
Damping ring e ⁺ and e ⁻		

Injectors, Booster, Damping Rings





Site	Heat Loads	System
Drive beam injector	Updated values (Alexej) + lighting	Longitudinal flow, AHUs at the surface
Main beam injector		
Booster		
Pre-damping ring e ⁺		
Damping ring e ⁺ and e ⁻		

Transfer Lines



Site	Heat Loads	System
Transfer Loop	CDR + lighting	Longitudinal flow, AHUs at the surface
Frequency Multiplication		
Transfer from CR2 to J.P.		
Transfer from Booster to J.P.		
Transfer from J.P. to S.P.	CDR + lighting	Transversal flow
Transfer e ⁺ slope		
Transfer e ⁻ slope		

Transfer Lines




2 x R500 e+ Injector

2 x R550 e- Injector

Site	Heat Loads	System
Transfer Loop	CDR + lighting	Longitudinal flow, AHUs at the surface
Frequency Multiplication		
Transfer from CR2 to J.P.		
Transfer from Booster to J.P.		
Transfer from J.P. to S.P.	CDR + lighting	Trasversal flow
Transfer e ⁺ slope		
Transfer e ⁻ slope		


Detectors Hall



- Gas extraction is foreseen
- 670 kW – 5 x 80'000 m³/h
- ❖ Review Heat Loads

Site	Heat Loads	System
Detectors Hall	CDR + Lighting	<u>High Heat Loads - Review</u>

DB and MB Turnarounds



- AHUs inside the UTRA/C or BC2 caverns
- Supply + extraction ducts

Site	Heat Loads		Flow Rate AHU	ΔT	System
	CDR + Lighting				
MB turnarounds e ⁺ and e ⁻		12 kW	6873 m ³ /h	5°C	Dedicated AHU inside the beam dump caverns
DB turnarounds	-	Unknown	-		

Surface Buildings



Site	Heat Loads	System
Drive Beam Injector	Updated values (Alexej) + 50W/m ²	15 x AHU 66988 m ³ /h
Main Beam Injector		5 x AHU 69364 m ³ /h
Booster		4 x AHU 69106 m ³ /h
Building - Damping Rings		2 x AHU 50042 m ³ /h
Building - CR1 and CR2	CDR + 50W/m ²	3 x AHU 76020 m ³ /h
Building - Injection Hall		2 x AHU 50746 m ³ /h

Dedicated AHUs for each surface building



Open questions

- Confirm heat load in the detectors hall
- Heat loads for service cavern and caverns 1.3, 1.4, 2.1 and 3.1
- Attribute heat loads to the surface buildings
- Determine the necessary “fresh air” for the beam dumps



Open questions

- Can we recycle air?
- Smoke extraction design and integration is still WIP
- Design for the 380 GeV or 3 TeV?

Future Work – short term



- Develop and detail the air infrastructures
- Design the water cooling plants and hydronic network



To be confirmed

Site	S/U	HL Water [kW]
Drive Beam Injector	U	5356
Drive Beam Injector	S	14191
Main Beam Injector	U	3886
Main Beam Injector	S	5126
Booster	U	1811
Booster	S	4239
Drive Beam Dumps	U	533
Drive Beam Turnaround	U	736
UTRA	U	869
UTRC	U	869
Equipment Passages for UTRC	U	0
Adittional Caverns 2.2 and 3.2	U	1000
Caverns 1.3 and 1.4	U	0
Survey Cavern 2.1 and 3.1	U	0
Main Beam Dump	U	13860
Detectors Hall - Underground	U	7500
BDS	U	14040
Main Tunnel - Two Beam	U	18563
Main Tunnel - Klystron, K side	U	12389
Main Tunnel - Klystron, LINAC side	U	13564

Tunnel BC2 e ⁺	U	1175
Main Beam Turn-Around e ⁺	U	0
Tunnel BC2 e ⁻	U	1175
Main Beam Turn-Around e ⁻	U	0
BC2 Caverns	U	0
Transfer Lines e ⁺ from Surface to Tunnel	U	108
Transfer Lines e ⁻ from Surface to Tunnel	U	120
Transfer Lines Loop	U	2101
Frequency Multiplication	U	12141
Tranfer from CR2 to J.P.	U	1028
Transfer from Booster to J.P.	U	1028
Transfer from J.P. to S.P.	U	2055
Pre Damping Ring	U	2733
Damping Ring e ⁺ / e ⁻	U	2681
Building - Damping Rings	S	1447
Building - CR1 and CR2	S	3440
Building - Injection Hall	S	1547

❖ Please confirm these values

Questions and Remarks



Thank You for Your Attention