



HO Corrector Magnets: decapole test and future plans




Marco Statera
on behalf of the LASA team
INFN Milano - LASA

CERN – 4 Octobre 2017

OUTLINE

- MCDXFP (decapole)
 - assembly
 - first cooldown results
- MCQSXFP (4pole) and MCTXFP(12pole) planning
- MgB₂ RCSM status and planning


HO CORRECTOR MAGNETS ZOO



MCDXFP

MCDXFP 10POLE





	nominal	simulation
length	172 mm	183 mm
integrated field @ lop @ r50 mm	25 Tmm	26 Tmm
magnetic length	95 mm	97 mm
harmonics		B15=11.6 B25=-0.7



- COILS
 - Updated BTS2 Arisawa design
 - Hybrid BTS2/DURATRON
- Improved electrical connection design

COILS

machined from bulk



machined from bulk


M. Statera- 2017/10/04

COILS' PRODUCTION

- 16 coils produced, 4 batches
- First batch
 - 3 BTS2 to be redesigned
 - 1 hybrid (spare)
- 6 BTS2 final design
- 6 hybrid


coils' assesment

- single coil I_{max}
- thermal cycle (2 batches)
- resistance
- HV insulation
- dimentions



RESISTANCE AND INSULATION

- resistance: we can detect one turn
- ground insulation
 - Al wrap
 - $> 36 \text{ G}\Omega @ 2.5 \text{ kV}$



DIMENTIONAL CHECK


- four moulds overall results
- comparable with sextupole

	NOMINAL	MEASURED	ST. DEV.
INNER SHORT	25.5 mm	25.52 mm	0.025 mm
OUTER SHORT	43.3 mm	43.63 mm	0.086 mm
INNER LONG	100.8 mm	100.79 mm	0.020 mm
OUTER LONG	118.6 mm	119.00 mm	0.111 mm


sextupole coils $\sigma = 0.13$ mm
octupole coils $\sigma = 0.4\text{-}0.5$ mm

ASSEMBLY

- same assembly procedure as sextupole MCSSXFP and octupole MCOXFP




5 coils BTS2
5 coils hybrid



M. Stalera - 2017/10/04


ASSEMBLY



M. Statera- 2017/10/04


ELECTRICAL CONNECTIONS

CERN
connection box



LASA
connection box


copper for
bus bar connection



upper PCB


lower PCB

PCBs fixing




bridge

CERN
connection box



M. Statera- 2017/10/04


INSTALLED COILS



GROUND INSULATION

- max voltage to ground in operation 36 V
- hot spot temperature in operation 122 K

by V. marinozzi




MCDXFP TEST

- Week 1
 - 4.2 K 1h @ I_{ult} , 121 A (115% I_{op})
 - 2.17 K 1h @ I_{ult} , 121 A
- Week 2 – starting on 9/10/2017
 - 4.2 K 1h @ I_{ult} , 121 A (115% I_{op})
 - no dump resistance quench
 - training


WEEK 1 PRELIMINARY

- one provoked
- one 98 A quench
- reached ultimate 114 A -1 hour test
- tested up to 121 A



SINGLE POINT MAGNETIC FIELD


- single Hall probe
- reference radius $r = 50$ mm



ROUND COIL MAGNET

demonstrator


- mechanics design ongoing
- Winding machine modification ongoing
- mould construction ongoing



- first batch of insulated MgB₂ wire delivered at LASA

schedule

- winding in 2017
- magnet assembly 1Q 2018



G. Volpini et al. Eletromagnetic Study of a Round Coil Superferric Magnet, IEEE Tr. App. Sup, 26, 4 (2016)

M. Statera- 2017/10/04

MCTXFP AND MCQSXFP

- tender approved by INFN
- contract sent to company
- (foreseen) start in October
- Tentative schedule
 - April 2018 MCTXFP delivered to LASA
 - Sept. 2018 MCQSXFP delivered to LASA

CONCLUSIONS

- MCDXFP
 - assembled
 - first cooldown preliminary results
- MCQSXFP and MCTXFP: 2018
- MgB₂ RCSM
 - assembly 1Q 2018