

Feasibility and implication of installation of the string test in SM18 with a slope

M. Bajko WP16

Open technical issues under discussions

Integartion

- **With SLOPE or not** (no request from CRG nor from magnets and Vac)
- Tooling : for Sc link and DFX installation
- Which set up point 1 or 5? Paolo Integration? The most complex one
- String should validate installation and dismounting procedures

Cryogenics:

- Need of a quench buffer, 10 g/s recovery line at warm, operational pressure 20 bars
- Which cooling (point 1 or point 5)
- Do we have spare DFX or we use a standard one?
- V_{He} in a cold mass = 25 l/ m? Herve?

Magnets

- Machine cycles...see with ABP
- Training till Inom? Iultimate?
- Provoked quenches with QHs to check propagation, QH delays
- Tracking test (measurements during ramp?)
- Thermal cycle?

Alignment

- Monitoring also during operation the position of the magnets (installation, cool down, warm up)

Vacuum

- Beam screen? With dedicated instrumentation? Chaufrettes?
- **De we have counted in the budget the beam screens? 700 kCHF extra cost?WP12?**we would need for Q1 proto (166mm) and D1(6mm dipole) proto , we have for the series but we need to instrument at least one (6 mm quad).



Integration slide1


Integration

- With SLOPE or not (no request from CRG nor from magnets and Vac)
- Tooling : for Sc link and DFX installation
- Which set up point 1 or 5? Paolo Integration? The most complex one
- String should validate installation and dismounting procedures


We have to choose between:

P1 or P5

Where P1L = P5R, and P1R= P5L




Using the argument of the SM18 set-up the choice is: P5L or P1L
Using the argument of complexity is : P5L



P5L is the most complicated and coherent set up with the Sm18 installations and the tunnel is the smallest .


We plan to reproduce the space allowed in that place of the tunnel for the interventions



Integration slide 2

Integartion

- With SLOPE or not (no request from CRG nor from magnets and Vac)
- Tooling : for Sc link and DFX installation
- Which set up point 1 or 5? Paolo Integration? The most complex one
- String should validate installation and dismounting procedures




There is no clear show stopper in SM18 to simulate the SLOPE but we did not get till today REQUEST for doing it.

P5L is the most complicated and coherent set up with the Sm18 installations and the tunnel is the smallest .

We plan to reproduce the space allowed in that place of the tunnel for the interventions

Consultation results



TODAY we do not consider to implement a SLOP for the IT STRING.


Integration slide 3

Integration

- With SLOPE or not (no request from CRG nor from magnets and Vac)
- Tooling : for Sc link and DFX installation
- Which set up point 1 or 5? Paolo Integration? The most complex one
- String should validate installation and dismounting procedures

Magnets ordered by arrival option 1

- Q2a prototype 1st-3rd Q 2019
- Q2b series 2nd Q 2020
- Q1 prototype 2nd Q 2020
- CP series 2nd Q 2020
- D1 prototype 1st Q 2021
- Q3 series 2nd Q 2021



In principle more difficult the installation and have more interest for the WP15 and for Vac as allows instrumenting the Beam screen of Q1 (the tick version)




Integration slide 4

Integration

- With SLOPE or not (no request from CRG nor from magnets and Vac)
- Tooling : for Sc link and DFX installation
- Which set up point 1 or 5? Paolo Integration? The most complex one
- String should validate installation and dismounting procedures

Magnets ordered by arrival option 2

- Q2a prototype 1st-3rd Q 2019
- Q2b series 2nd Q 2020
- Q3 prototype 2nd Q 2020
- CP series 2nd Q 2020
- D1 prototype 1st Q 2021
- Q1 series 2nd Q 2021



Cryogenics

Cryogenics:

- Need of a quench buffer, 10 g/s recovery line at warm, operational pressure 20 bars
- Which cooling (point 1 or point 5)
- Do we have spare DFX or we use a standard one?
- V_{He} in a cold mass = 25 l/ m? Herve?

P5L is the most complicated and coherent set up with the Sm18 installations and the tunnel is the smallest .

We plan to reproduce the space allowed in that place of the tunnel for the interventions

Antonio Perin is working on the cryogenics. Together with MSC-TF and P. Gayet we are evaluating the pumping capacity for SM18 . *The last conclusion made by L. Serio (with SM18 UPG) was that no need of additional pumping.*



Magnets

Magnets

- Machine cycles...see with ABP
- Training till I_{nom} ? Iultimate?
- Provoked quenches with QHs to check propagation, QH delays
- Tracking test (measurements during ramp?)
- Thermal cycle?

I_{nom} is what we have considered till now.
 In the phase of HWC of the STRING 120
 quenches were estimated to be done till I_{nom} .
 An other 50 quenches are planned to do with
 the goal of "special test" not done in the
 shadow of the HWC.

Hardware Commissioning Special Tests Hardware Commissioning Special Tests

magnet name	energy @ nominal [MJ]	nr of quenches aftre 1st cool down					nr of quenches aftre Thermal Cycle				
		LOW 10% I_{nom}	MEDIUM 40% I_{nom}	HIGH 75% I_{nom}	NOMINAL I_{nom}	NOMINAL STUDIES I_{nom}	LOW 10% I_{nom}	MEDIUM 40% I_{nom}	HIGH 75% I_{nom}	NOMINAL I_{nom}	NOMINAL STUDIES I_{nom}
2 xMQXFA (Q1)	9.82	10	8	8	4	8	10	2	2	2	4
MQXFB (Q2a)	8.37	10	4	4	2	4	10	2	2	1	2
MCBxFb(Q2a)	0.1	5	5	5	2	5	5	1	1	1	2
MQXFB (Q2b)	8.37	10	4	4	2	4	10	2	2	1	2
MCBxFb(Q2b)	0.12	5	5	5	2	5	5	1	1	1	2
2 xMQXFA (Q3)	9.82	10	8	8	4	8	10	2	2	2	4
D1	2.15	5	3	3	1	3	5	1	1	1	1
MCBXFb	0.22	5	5	5	2	5	5	1	1	1	2
HO	0.1	9	9	9	0	9	9	4	4	0	4
DSH		0	0	0	1	0	0	0	0	0	0
bus bar		0	0	0	0	0	0	0	0	0	0
DHL											
total in the string	39.07	69	51	51	20	51	69	16	16	10	23
total nr of quenches		173					65				

The Current level
 has a non-negligible
 consequence on the
 energy deposition into
 the cold mass +
 extraction and so on
 the pumping capacity
 affecting finally also the
 planning

1 TC is planned



Vacuum

Vacuum

- Beam screen? With dedicated instrumentation? Chauffrettes?
- **De we have counted in the budget the beam screens? 700 kCHF extra cost? WP12?** we would need for Q1 proto (166mm) and D1(6mm dipole) proto , we have for the series but we need to instrument at least one (6 mm quad).


Beam Screens will be installed

Following the magnets availability and the needs in testing all type of beam screens we have:

3 instrumented: Q1 proto, D1 proto and Q2a or Q2b proto



Planning (Draft version)



SUMMARY

Today we do **NOT** consider to implement a **SLOP** for the **IT STRING**.

P5L

*is the most complicated and coherent set up
with the Sm18 installations*

*We plan to make **1 TC** and approximately
200 quenches up to a
maximum of $I_{nominal}$*