



# Muon Phase I Upgrades - Summary

- **Summary of planned upgrades**
- **Schedule of talks**
- **For each muon detector:**
  - **A few details**
  - **Selected issues**



# Muon Phase I Upgrades - Summary

- **CSC Upgrades**

- ME4/2 build 72 new CSC chambers
- ME1/1 build 7x72 Digital CFEBs
  - and 72 each associated trigger (TMB), readout (DMB) boards

- **RPC Upgrades**

- Build another endcap station out to rapidity 1.6

- **DT Upgrades**

- (BTI replacement – really a maintenance issue)



# Muon Phase 1 Talks

- **Jay Hauser – Phase 1 Muon Upgrades Introduction**
- **Oleg Prokofiev - Update on ME4/2 Chambers and Tooling**
- **Ben Bylsma - Update on Digital CFEB**
- **Vadim Khotilovich – CSC efficiency studies**
- **Jason Gilmore - TMB Design Issues for ME1/1**
- **Piet Verwilligen - RPC Upgrade for Phase 1**
- **Pierluigi Zotto – Barrel DT Phase 1 Upgrades**





# Muon Phase 1: CSC



# ME4/2 and ME1/1 upgrades

## R-Z cross-section




**“Empty” YE3 disk ready for ME4/2**



# ME4/2 upgrade motivation

- **Triggering with & without the ME4/2 upgrade:**
  - The high-luminosity Level 1 trigger threshold is reduced from 48  $\rightarrow$  18 GeV/c



Ingo Bloch, Norbert Neumeister, Rick Wilkinson



# DCFEB Prototype

Build prototype with four options for preamp/ADC interface

Options include:

- Direct Coupling with scaling
- AC Coupling with scaling
- Single to Differential with Analog Devices ADA4950
- Single to Differential with TI THS4524

DAQ path:

- Virtex 5 or 6
- Data sent in MAC level ethernet packets

Trigger path:

- Three options (see slide 4) fiber or copper?
- Major concern is additional latency (seems unavoidable)
- Other concerns: additional components/power consumption
- On TMB end: compatibility with mezzanine board





# Muon Phase I: RPC





# Endcap System at Start Up

	RE 1/1	RE 1/2	RE 1/3	RE 2/1	RE 2/2	RE 2/3	RE 3/1	RE 3/2	RE 3/3	RE 4/1	RE 4/2	RE 4/3
No. of chambers	36*2	36*2	36*2	18*2	36*2	36*2	18*2	36*2	36*2	18*2	36*2	36*2






# The Double Chamber Approach

**Move act. station 2  
to station 4**

**Build a double  
station for station 2**




	RE 1/1	RE 1/2	RE 1/3	RE 2/1	RE 2/2	RE 2/3	RE 3/1	RE 3/2	RE 3/3	RE 4/1	RE 4/2	RE 4/3
No. of chambers	36*2	36*2	36*2	18*2	36*2	36*2	18*2	36*2	36*2	18*2	36*2	36*

4th station



# Validation

- RE2bis was implemented as a logical “AND” of 2 RPCs
  - $\epsilon = \epsilon^2$                       90%  $\rightarrow$  81 %
  - Rate?                                      Turned out to be negligible:  
2 x 100 Hz cm<sup>-2</sup>  $\rightarrow$  0.05 Hz cm<sup>-2</sup>
- This plot was made in TDR geometry with:
  - Rate:                      Neutron hits: Poisson Distribution for random noise
  - Efficiency:                Single Muons, 10 - 200 GeV/c , 1.04 <  $\eta$  < 2.1
  - $\rightarrow$  Pure Fake Rate,                      no rate due to MinBias and Signal




- Unable to reproduce exactly the same result as 8 years ago
- Major Changes in Software:
  - Patterns
    - Broad Patterns  $\rightarrow$  Narrow Patterns
  - Algorithm:                3/4  $\rightarrow$  4/6
  - Quality:
    - no preferred Layer
    - Q = # Planes hit - 3



# Preliminary Results

Full Endcap ( Towers 8 – 16 ==  $1.04 < \eta < 2.10$  )



Slightly better (lower) Trigger Rate for RE2bis, but not as high as expected w.r.t. the simulation of a fully independent 5<sup>th</sup> plane.

**Is this worth the effort?**



# (RPC) Conclusions

- **Simulation is ongoing:**
  - First results indicate that **TDR approach** will be adequate
  - Hopefully decision by beginning of next year
  
- **Funding & Responsibilities:**
  - Division of responsibilities between Europe and Asia is currently under discussion
  - Total cost of the project is in range 4 – 5 MCHF
  - Large part of the funds already ensured: Belgium, India, Pakistan, China, Korea
  - Involvement of CMS and Italy highly welcome
  
- **Ready to start:**
  - CMS RPC Collaboration is ready to start production in 2010
  - Milestone for completion could be 2013 - 2014
  
- **Infrastructure and integration issues to be discussed:**
  - Cooling in RE4
  - Integration with CSC



# Muon Phase I Upgrades – CSC Issues

- **“Shovel-ready” ME4/2 (5 prototypes)→**
- **Arranging for chamber factory at CERN**
  - Tooling to be shipped to CERN in few months
- **Can Digital CFEBs be ready for installation in ME1/1 during the 2011 shutdown?**
  - Results of prototype tests available ~Mar. 2010
  - Numerous technical details – can DCFEB be backward compatible?





# Muon Phase I Upgrades – RPC Issues

- **Detailed plans (e.g. double station in RE2) depend highly on simulation**
  - **First CMSSW simulation results now available**
  - **Only noise+neutron hits, other sources significant?**
    - **Low-Pt muons + neutrons?**
- **(Work plan: who builds what, schedule and financing)**



# Muon Phase I Upgrades – Simulation Issues

- **Crucial but severely limited by manpower**
- **E.g. neutron hits**
  - **Tricky to add in**
- **Significant tuning will be needed after we take first LHC data**







# Backup slides

# CSC Simulation result (May '09)

(Vadim Khotilovich, Alexei Safonov)


- Efficiency gaps for good quality TF tracks disappear with addition of ME4/2
- ME4/2 will be included by default in 31X
- Back-porting to 22X took a considerable amount of effort
  - Thanks to the experts: Rick Wilkinson, Tim Cox, Oana Boeriu and Slava Valuev!






# “Digital CFEB” cathode board

- **CSC principle: digitize cathode charges to ~1%, interpolate for fine position**
- **Current CFEB: the ADC is multiplexed 16:1**
  - Requires analog charge storage ASIC (SCA)
  - Serial digitization after L1A





- **Digital CFEB uses Flash ADCs:**
  - Continuous and deadtimeless digitization





# ME1/1 Restoration of $\eta$ 2.1-2.4

- **High- $\eta$  section of ME1/1**
  - Cathode strips are currently ganged 3:1



- **Plan:**
  - Install DCFEB boards on ME1/1
  - Move existing CFEBs from ME1/1 to ME4/2
  - Takes ~2.5 months per endcap
  - **72 new TMB and DMB boards needed to accommodate additional inputs, optolinks**



# Overall ME4/2 schedule (if 2011 start) - installation constraints not taken into account

WBS	Task Name	Duration	2011					2012				2013				2014		
			tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	tr	
1	Emu ME4/2 upgrade	796 days	[Gantt bar spanning from start of 2011 to end of 2013]															
1.1	ME4/2 Procure mechanical parts and panels	260 days	[Gantt bar from start of 2011 to mid-2011]															
1.2	ME4/2 Panel production	390 days	[Gantt bar from mid-2011 to end of 2011]															
1.3	ME4/2 Chamber assembly and shipping	455 days	[Gantt bar from mid-2011 to mid-2012]															
1.4	ME4/2 Procure electronics parts (non-CFEB)	325 days	[Gantt bar from start of 2011 to end of 2011]															
1.5	ME4/2 Produce electronics boards (non-CFEB)	325 days	[Gantt bar from mid-2011 to end of 2011]															
1.6	Pre-production DCFEB	260 days	[Gantt bar from start of 2011 to mid-2011]															
1.7	ME4/2 Final assembly and test (FAST) at CERN	390 days	[Gantt bar from mid-2012 to end of 2012]															
1.8	Procure DCFEB parts	260 days	[Gantt bar from mid-2011 to end of 2011]															
1.9	Produce DCFEB boards	325 days	[Gantt bar from mid-2012 to end of 2012]															
1.10	Ready for start of ME4/2 chamber installation	0 days	[Milestone diamond at end of 2012, labeled 3/29]															
1.11	Installation of ME4/2 chambers (earliest date)	15 days	[Gantt bar starting from milestone 1.10, in early 2013]															
1.12	Cabling and services for ME4/2 (earliest date)	65 days	[Gantt bar starting from milestone 1.10, in early 2013]															
1.13	(Upgrade of ME1/1 with DCFEB, earliest date)	130 days	[Gantt bar starting from milestone 1.10, in early 2013]															
1.14	Install CFEBs on ME4/2 chambers (earliest date)	15 days	[Gantt bar starting from milestone 1.10, in early 2013]															




# ME4/2 Upgrade Schedule

<b><math>t_0 + 0</math> months</b>	<b>CD2 approval, money flows, begin work on Bldg 904</b>
<b><math>t_0 + 3</math> months</b>	<b>orders sent out for all parts</b>
<b><math>t_0 + 6</math> months</b>	<b>production tooling shipped to CERN and assembled in Bldg 904</b>
<b><math>t_0 + 9</math> months</b>	<b>chamber parts delivered, shipped to CERN</b>
<b><math>t_0 + 12</math> months</b>	<b>production begins at Bldg 904 at 2 CSCs/month</b>
<b><math>t_0 + 15</math> months</b>	<b>production ramps to 4 CSCs/month</b>
<b><math>t_0 + 18</math> months</b>	<b>FAST site begins assembly &amp; testing at CERN (Bldg 904?), spare CFEB boards installed on ME4/2s</b>
<b><math>t_0 + 24</math> months</b>	<b>42 CSCs finished and tested -- ready for installation of 1st endcap, recover 200 CFEB boards from ME1/1s</b>
<b><math>t_0 + 33</math> months</b>	<b>all 76 CSCs finished</b>
<b><math>t_0 + 36</math> months</b>	<b>final 36 chambers ready for installation on 2nd endcap</b>



# Preliminary Results

Full Endcap ( Towers 8 – 16 ==  $1.04 < \eta < 2.10$  )



Slightly better (lower) Trigger Rate for RE2bis, but not as high as expected w.r.t. the simulation of a fully independent 5<sup>th</sup> plane.

**Is this worth the effort?**