


# Status of the LHC Machine



**Helmut Burkhardt, CERN**

RADCOR'09, 26 Oct. 2009, Ascona Switzerland



## Livingston plot

**Exponential** growth  
of  $E_{\text{cms}}$  in **time**

Starting in 60's  
with  $e^+e^-$  at about 1 GeV


**Factor 4 every 10 y**

$pp, p\bar{p}$  :  $E_{\text{cms}} / 6$   
still **5 x** above  $e^+e^-$  at  
same time


$pp, p\bar{p}$  : **discovery**

$e^+e^-$  : **precision** machines

both required



**The LHC is a big step forward; Excellent potential for major discoveries; according to RADCOR Higgs well within range**



28 y

**1982 : First studies for the LHC project**

**1983 : Z discovered at SPS proton antiproton collider**

**1989 : Start of LEP operation ~ 92 GeV, Z-factory**

**1994 : Approval of the LHC by the CERN Council**

**1996 : Final decision to start the LHC construction**

**1996 : LEP2 operation towards ~ 200 GeV, W+W-**

**2000 : End of LEP operation**

**2002 : LEP equipment removed**

**2003 : Start of the LHC installation - infrastructure**

**2005 : Start of Magnet installation in LHC tunnel**

**2007 : Installation complete, starting cooldown**



**2008 : Start of commissioning with beam**

**2010 : First physics results (?)**


16 y

9 y



# High Luminosity IR1, IR5 for the Large Multipurpose Detectors





**IR1 : ATLAS**




**IR5 : CMS**



# IR2, IR8 for $\mathcal{L} \sim 10^{30} - 10^{32} \text{ cm}^{-2} \text{ s}^{-1}$ with the more specialized Detectors




**IR2 : Alice – Heavy Ion -  $\Phi$**



**IR8 : LHCb – B -  $\Phi$**






## High design Centre-of-mass energy of 14 TeV in given (ex LEP) tunnel

- Magnetic field of 8.33 T with superconducting magnets
- Helium cooling at 1.9 K
- Large amount of energy stored in magnets
- “Two accelerators” in one tunnel with opposite magnetic dipole field and ambitious beam parameters pushed for very high of **luminosity of  $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$**
- **Many bunches with large amount of energy stored in beams**


## Complexity and Reliability

- Unprecedented complexity with 10000 magnets powered in 1700 electrical circuits, complex active and passive protection systems, ....
- 
- **Emittance conservation**  $\varepsilon_N = \beta \gamma \varepsilon$ , related to phase space density conservation, Liouville constant “intrinsic” normalized emittance  $\varepsilon_N$ , real space emittance  $\varepsilon$  decreases with energy
  - in absence of major energy exchange in synchrotron radiation / rf damping
  - clean, perfectly matched injection, ramp, squeeze, minimize any blow up from: rf,
  - kicking beam, frequent orbit changes, vibration, feedback, noise,..
  - dynamic effects - persistent current decay and snapback
  - non-linear fields (resonances, diffusion, dynamic aperture, non-linear dynamics )

# The total stored energy of the LHC beams




Nominal LHC design:  $3.2 \times 10^{14}$  protons accelerated to 7 TeV circulating at 11 kHz in a SC ring



**LHC: > 100 × higher stored energy and small beam size: ~ 3 orders of magnitude in energy density and damage potential. Active protection (beam loss monitors, interlocks) and collimation for machine and experiments essential. Only the specially designed beam dump can safely absorb this energy.**


# Damage potential : confirmed in controlled SPS experiment



controlled experiment with beam extracted from SPS at 450 GeV in a single turn, with perpendicular impact on Cu + stainless steel target


450 GeV protons →

r.m.s. beam sizes  $\sigma_{x/y} \approx 1$  mm



Cu and stainless steel sandwich  
108 plates

25 cm



6 cm

$2 \cdot 10^{12}$   $4 \cdot 10^{12}$   $8 \cdot 10^{12}$   $6 \cdot 10^{12}$

**SPS results confirmed :**

**$8 \times 10^{12}$  clear damage**

**$2 \times 10^{12}$  below damage limit**

for details see V. Kain et al., PAC 2005 [RPPE018](#)


**For comparison, the LHC nominal at 7 TeV :**

**$2808 \times 1.15 \times 10^{11} = 3.2 \times 10^{14}$  p/beam**

**at  $\langle \sigma_{x/y} \rangle \approx 0.2$  mm**

**over 3 orders of magnitude above damage level for perpendicular impact**







	LHC	LEP2
Momentum at collision, TeV/c	7	0.1
Nominal design Luminosity, cm <sup>-2</sup> s <sup>-1</sup>	1.0E+34	1.0E+32
Dipole field at top energy, T	8.33	0.11
Number of bunches, each beam	2808	4
Particles / bunch	1.15E+11	4.20E+11
Typical beam size in ring, μm	200 – 300	1800/140 (H/V)
Beam size at IP, μm	16	200/3 (H/V)

- **Energy stored in the magnet system:** **10 GJoule** Airbus A380, 560 t
- **Energy stored in one (of 8) dipole circuits:** **1.1 GJ (sector)** at 700 km/h
- **Energy stored in one beam:** **362 MJ** 20 t plane
- **Energy to heat and melt one kg of copper:** **0.7 MJ**

the LEP2 total stored beam energy was about 0.03 MJ



# The CERN accelerator complex : injectors and transfer




Beam size of protons decreases with energy : area  $\sigma^2 \propto 1 / E$   
 Beam size largest at injection, using the full aperture

simple rational fractions for **synchronization**  
 based on a single frequency generator at injection




# LHC Commissioning : injection tests in Aug'08 + Oct'09





1st Injection clockwise -  
beam 1 sector 2 - 3, 8-10  
Aug. 2008

1st Pb ions 23/10/2009

2nd Injection  
anti-clockwise beam 2  
sector 8 - 7  
22-24 Aug. 2008




again over week-end 24-25 Oct 2009, with LHCb spectrometer compensation





Local mini-quench  
“*quenchino*”

verification of quench limit in magnets  $\sim 2 \times 10^9$  protons  
@ 450 GeV and calibration of  $B_{\text{eamLossMon}}$  system



**10:30 beam 1 3 turns**  
**15:00 beam 2 3 turns**  
**22:00 beam 2 several 100 turns**








- First & Second Turn on screen
- First Turn on BPM system

Jörg Wenninger

Courtesy of Roger Bailey & O. Brüning




longitudinal position around the ring,  $s$  [m], here by monitor number



**H and V successfully scanned in the range  $\pm 12 - 18$  mm**


[LHC Perf. Note 1](#) Sep.2008




## $\beta$ -measurements and analysis

[LHC Perf. Note 8](#) Jan 2009


ABP and OP group



**A lot was learned from the cold-checkout, injection tests and the few days with beams in the LHC in 2008. Instrumentation and software and analysis worked very well and allowed many measurements, detailed analysis and adjustments. This also allowed to diagnose and later correct noisy channels and cabling error etc.**




one trace every 10 turns








# Simulation of injection with 170° injection phase offset






pt

turn 0



longitudinal phase space






**projection of previous plot : longitudinal charge density distribution**

# LHC beam 2 with well adjusted RF capture



**important : observation of good beam lifetime at injection energy**






## Past

- QRL cryo-line (He supply)
- DFB power connections, warm to cold transition
- Triplet quadrupoles - differential pressure

## More recent


- **PIM** plug in module with bellow, systematically checked / repaired after warm up using “ping-pong” ball with RF-emitter : polycarbonate shell,  $\varnothing$  34 mm, 15 g, 2h battery powered, 40 MHz emitter, signals recorded by LHC BPM
- Vacuum leaks, condensation - humidity sector 3/4
- Magnet powering check / correct : min/max, cabling - polarity
- Single event upset, radiation to electronics, shielding etc
- Magnet re-training magnets quenching below what was reached in SM18
- Magnet interconnects, splices →





Commissioning with beam interrupted by a series of hardware failures - **not related to beams**

- two large transformers ; 13 - 18 September 2008 '08
- 19 Sept. '08 at 11:18:36, incident during hardware commissioning of sector 3/4 towards 5.5 TeV/ 9.3 kA, at 8.7 kA or ~5.2 TeV, of the 600 MJ stored energy about 2/3 dissipated into the cold-mass                      1 MJ melts 2.4 kg Cu



bad splice 220 nΩ at electrical connection between dipole and quad Q23, ~ 6 t He or 1/2 of arc lost; pressure built up in adjacent each 107 m long, vacuum sub-sectors causing significant collateral damage.

details : LHC-PROJECT-REPORT-1168 March '09



some typical numbers and back of envelope estimates :

good splice ~ 0.3 nΩ, I = 12 kA, U = R I = 3.6 μV (now) possible to check

P = R I<sup>2</sup> = 0.043 W    quench would need locally > 10 W - depending on position - less critical in magnet

new QPS triggers at 0.3 mV for > 10 ms


LHC dipole L = 100 mH    stored energy in single dipole I<sup>2</sup> L / 2 = 7.2 MJ    × 154 = 1.1 GJ / sector





**BUS**  
 Cross-section Cu: 282 mm<sup>2</sup>  
 Cross section NbTi: 6.5 mm<sup>2</sup>  
 Kapton+isopreg insulation  
 RRR specification: >120  
 RRR experimental (D. Richter)  
 - RB bus: 223-276 (4 data)  
 - RQ bus: 237-299 (4 data)

**JOINT**  
 Joint length: 120 mm  
 Cu U-profile: 155 mm x 20 mm x 16 mm  
 Cu wedge: 120 mm x 15 mm x 6 mm  
 Insulation:  
 - 2 U-shaped layers of kapton  
 (240 mm x 0.125 mm thick)  
 - 2 U-shaped layers of G10  
 (190 mm x 1 mm)


# Busbar Splice



**normal conducting, soldered electrical connection between SC cables**  
 1684 units  $\times$  6  $\approx$  10 000 splices at magnet interconnects; 1/3 dipole, 2/3 quads



Courtesy:  
 Christian Scheuerlein



possible problems in soldering :

- overheating - SnAg loss
- too cold - SnAg unmelted, poor connection

A. Siemko et al. LMC 5/08/09

Now possible to diagnose : X-ray, ultrasound, resistance measurement.

Most reliable : resistance measured at room temperature

good : 10  $\mu\Omega$  dipole (RB) , 17  $\mu\Omega$  quadrupole (RQ).

Measured in 5 sectors which were warmed up. Fixed all above  $\sim$  40  $\mu\Omega$ . Other sectors measured at 80 K

# The LHC repairs in detail

14 quadrupole magnets replaced




39 dipole magnets replaced



54 electrical interconnections fully repaired. 150 more needing only partial repairs



Over 4 km of vacuum beam tube cleaned




5



A new longitudinal restraining system is being fitted to 50 quadrupole magnets

6





Nearly 900 new helium pressure release ports are being installed around the machine

7



6500 new detectors are being added to the magnet protection system, requiring 250 km of cables to be laid









**Preparation well advanced :**

**HW tests nearly completed, transfer lines tested ok inclusive ions !**

**Schedule from LPC  
26-10-2009**

**Dipole current limited to 2kA in 2009, or just over 2 TeV  $E_{cm}$**


- All dates approximate...
- Reasonable machine availability assumed
- Stop LHC with beam ~17<sup>th</sup> December 2009, restart ~ 7<sup>th</sup> January 2010




Technical Stop  
Re-commissioning with beam

SPS et al Physics Program


- 2009:
  - 1 month commissioning
- 2010:
  - 1 month pilot & commissioning
  - 3 month 3.5 TeV
  - 1 month step-up
  - 5 month 4 - 5 TeV
  - 1 month ions



this and next slide : as discussed in Commis. WG + LMC and summarized by S.M. in Sept. '09 LHCC




Energy	Safe	Very Safe
450	1 e12	1 e11
1 TeV	2.5 e11	2.5 e10
3.5 TeV	2.4 e10	probe




Month	OP scenario	Max number bunch	Protons per bunch	Min beta*	Peak Lumi	Integrate d	% nominal
1	Beam commissioning						
2	Pilot physics combined with commissioning	43	$3 \times 10^{10}$	4	$8.6 \times 10^{29}$	$\sim 200 \text{ nb}^{-1}$	
3		43	$5 \times 10^{10}$	4	$2.4 \times 10^{30}$	$\sim 1 \text{ pb}^{-1}$	
4		156	$5 \times 10^{10}$	2	$1.7 \times 10^{31}$	$\sim 9 \text{ pb}^{-1}$	2.5
5a	No crossing angle	156	$7 \times 10^{10}$	2	$3.4 \times 10^{31}$	$\sim 18 \text{ pb}^{-1}$	3.4
5b	No crossing angle – pushing bunch intensity	156	$1 \times 10^{11}$	2	$6.9 \times 10^{31}$	$\sim 36 \text{ pb}^{-1}$	4.8
6	Shift to higher energy: approx 4 weeks	Would aim for physics without crossing angle in the first instance with a gentle ramp back up in intensity					
7	4 – 5 TeV (5 TeV luminosity numbers quoted)	156	$7 \times 10^{10}$	2	$4.9 \times 10^{31}$	$\sim 26 \text{ pb}^{-1}$	3.4
8	50 ns – nominal Xing angle	144	$7 \times 10^{10}$	2	$4.4 \times 10^{31}$	$\sim 23 \text{ pb}^{-1}$	3.1
9	50 ns	288	$7 \times 10^{10}$	2	$8.8 \times 10^{31}$	$\sim 46 \text{ pb}^{-1}$	6.2
10	50 ns	432	$7 \times 10^{10}$	2	$1.3 \times 10^{32}$	$\sim 69 \text{ pb}^{-1}$	9.4
11	50 ns	432	$9 \times 10^{10}$	2	$2.1 \times 10^{32}$	$\sim 110 \text{ pb}^{-1}$	12

# Get LHC beams colliding : BPM resolution



adjust orbits such, that the beam 1 and 2 difference left/right of the IP is the same  
 beams must then collide. This is **independent of mechanical offsets and crossing angles**



nominal beam sizes at the IP			
	450 GeV	3.5 TeV	5 TeV
$\beta^*$ [m]	$\sigma^*$ [ $\mu\text{m}$ ]	$\sigma^*$ [ $\mu\text{m}$ ]	$\sigma^*$ [ $\mu\text{m}$ ]
11	293	105	88.0
3	153	54.9	45.9
2	125	44.8	37.5
1	88.4	31.7	26.5

$\delta x$	$\delta y$	$\mathcal{L}/\mathcal{L}_0$
$\sigma_x$	$\sigma_y$	
0	0	1.0000
0.1	0	0.9975
0.2	0	0.9901
0.3	0	0.9778
0.4	0	0.9608
0.5	0	0.9394
0.5	0.5	0.8825
1	0	0.7788
1	1	0.6065
2	0	0.3679
2	2	0.1353

measured with special (beam-) directional strip-line couplers BPMSW, at about  $L = 21$  m left and right of the IP in front of Q1 in each IR. Resolution each plane  $\delta_{IP} = \sigma_{BPM}$


**Expected resolution for small separation and 0 crossing angle ; in each plane.**

~ **50  $\mu\text{m}$**  using selected, paired electronics ; otherwise ~ 100 - 200  $\mu\text{m}$   
 beam 1 and beam 2 have separate electronics

~ **10  $\mu\text{m}$**  with extra BPMWF button pick-ups. Installed in 1&5, for large bunch spacing, [EDMS doc 976179](#)



# Luminosity scans and absolute luminosity




(pioneered by Van der Meer @ ISR)

**Orthogonal x, y scans  
to determine  $\sigma_{x,y}^*$**

$$\mathcal{L} = \frac{N_1 N_2 f}{4\pi \sigma_x \sigma_y}$$

$$\frac{\mathcal{L}}{\mathcal{L}_0} = \exp \left[ - \left( \frac{\delta x}{2\sigma_x} \right)^2 - \left( \frac{\delta y}{2\sigma_y} \right)^2 \right] \text{ gaussian beams}$$




Accuracy : better than **1%** at ISR

Aim for **early LHC ~ 10 %** ( done @ RHIC )


Contributions :

- Intensity  $N_{1,2}$  BCT ~1%
- Length scale - from BPM, bumps optics, few %
- Particles in tails
- Exact shape

extreme cases :




LEP example, V-plane, 3 bunches



studied by Simon White - as PhD thesis.

principle : H.B. and Per Grafstrom; LHC Report 1019 from 23 May 2007 <http://cdsweb.cern.ch/record/1056691>

and H.B., R. Schmidt, *Intensity and Luminosity after Beam Scraping*, [CERN-AB-2004-032](http://cdsweb.cern.ch/record/1056691)



The physics program is made by the physics community (you; not the machine)

To my knowledge the program is basically :

- **always run at highest possible energy**
- **get the maximum integrated luminosity**

with few exceptions :


- **heavy ion runs (Pb-Pb, maybe later also other ions)**
- **high  $\beta^*$  TOTEM and later ALFA operation - for forward (diffractive) physics,  $\sigma_{tot}$**

Any other ideas and requests ?

LHC constraints :  $E_{b1} = E_{b2}$ , same sign of charge, no polarisation

What about


- **Precision and knowledge of beam-parameters - energy and luminosity calibration, vertex precision and stability**
- **interest in UPCs,  $\gamma\gamma$  ? as discussed in [pAworkshop2](#) and [0706.3356](#)**



ultraperipheral p, Ion



## Concluding remark



**The LHC is the worlds largest and most energetic machine. We also all know that it is not an easy machine and already faced and solved many difficulties.**

**Interventions which require warmup / cool down of sectors imply month's without circulating beams.**



**We had an excellent start of the LHC with beams in 2008 getting quickly both beams around the ring and good lifetime in only 3 days !**

**The current repair and shutdown is also used to further improve the preparations for beams for physics.**



**The LHC is scheduled to restart in mid November'09. First collisions will be at injection energy and the first high energy physics run at 3.5 TeV beam energy. During 2010 the energy will be increased towards 5 TeV. A run with lead-ions is scheduled towards the end of the run later in 2010.**



# Backup Slides




by Katy Foraz, presented by M. Lamont LPC 26 Oct 2009



started :  
ready in  
2013-14



if approved could be  
ready by about 2018

2018 ?




- SPL:** Superconducting Proton Linac (4 GeV)
- PS2:** High Energy PS (~ 5 to 50 GeV – 0.3 Hz)
- SPS+:** Superconducting SPS (50 to 1000 GeV)
- SLHC:** “Superluminosity” LHC (up to  $10^{35} \text{ cm}^{-2}\text{s}^{-1}$ )
- DLHC:** “Double energy” LHC (1 to ~14 TeV)

**SLHC 1st step : replace current triplet by new larger aperture triplet, by ~ 2014**







# LHeC



CDR planned in 2010





$$f_{RF} = 400.7896 \text{ MHz}$$

$$\lambda_{RF} = 0.748 \text{ m or } 2.4951 \text{ ns}$$

35 640 RF buckets

Bunches spaced by **25 ns** or  
10 buckets

Inject batches of

2, 3 or 4 x 72 bunches


1 batch = 72 bunches

total  $39 \times 72 = 2808$  bunches

**Leave a 119 bunch**

**abort gap free  $\sim 3 \mu\text{s}$**

A full LHC turn is  $88.9244 \mu\text{s}$




Crossing angle needed for  $> 156$  bunches


to avoid encounters closer than  $\sim 6 \sigma$

Angle scales with  $\sigma$  or  $1/\sqrt{\beta^*}$  and  $1/\sqrt{E_b}$

Nominal angle at 0.55 m, 7 TeV is  $\pm 142.5 \mu\text{rad}$

$2 \times 15$  parasitic crossings  $\pm 58\text{m}$  from IP at 7.5 – 13  $\sigma$






two types of magnetic separation bumps :

parallel separation to avoid collisions in beam preparation, off in physics

crossing angle to avoid parasitic collisions, always required for > 156 bunches

IR1 : horizontal separation and vertical crossing angle

IR5 : vertical separation and horizontal crossing angle




orbit corrector magnets used in the IP bumps

MCBX in triplet - important for crossing angle and aperture at injection

collapse bump by combination of MCBC, MCBY and MCBX or ramp down MCBX first

Separation scans, optimization with MCBC, MCBY on one beam




**The LHC will run for the first part of the 2009-2010 run at 3.5 TeV per beam, with the energy rising later in the run. That's the conclusion that we've just arrived at in a meeting involving the experiments, the machine people and the CERN management. We've selected 3.5 TeV because it allows the LHC operators to gain experience of running the machine safely while opening up a new discovery region for the experiments.**

**The developments that have allowed us to get to this point are good progress in repairing the damage in sector 3-4 and the related consolidation work, and the conclusion of testing on the 10000 high-current electrical connections last week. With that milestone, every one of the connections has been tested and we now know exactly where we stand.**

**The latest tests looked at the resistance of the copper stabilizer that surrounds the superconducting cable and carries current away in case of a quench. Many copper splices showing anomalously high resistance have been repaired already, and the tests on the final two sectors revealed no more outliers. That means that no more repairs are necessary for safe running this year and next.**




**The procedure for the 2009 start-up will be to inject and capture beams in each direction, take collision data for a few shifts at the injection energy, and then commission the ramp to higher energy. The first high-energy data should be collected a few weeks after the first beam of 2009 is injected. The LHC will run at 3.5 TeV per beam until a significant data sample has been collected and the operations team has gained experience in running the machine. Thereafter, with the benefit of that experience, we'll take the energy up towards 5 TeV per beam. At the end of 2010, we'll run the LHC with lead-ions for the first time. After that, the LHC will shut down and we'll get to work on moving the machine towards 7 TeV per beam.**





Can be completely avoided up to 156 bunches  
 Then gradually becoming an issue  
 would be good to gain first experience on this  
 in the 2009 / 2010 run  
 Nominal, IP1/5 : each 30 parasitic collisions  $\sim 9\sigma$   
 Parasitic b.b. effects reduce with fewer bunches  
 or increased crossing angle

Simulation : IP5 colliding. IP1 going into collision  
 by ramping down the horizontal separation





close to head on beam-beam :  
 peaks in blow up at  $0.5$  and  $1.5 \sigma$

Some ref.

W. Herr, M. Zorzano LHC Project Report 462 ; Tatiana Pieloni thesis

Figures above from S. M. White, H. Burkhardt, S. Fartoukh, T. Pieloni, *Optimization of the LHC Separation Bumps Including Beam-Beam Effects WE6PFP018, PAC'09*



Many machine modes

Here concentrating on **STABLE BEAMS**. How to get the most for physics

Optimize conditions - based on direct feedback from experiment