

Status of CLIC and ILC

LHCP Bologna

Steinar.Stapnes@CERN.CH

on behalf of the CLIC and ILC accelerator communities

Key parameters ILC and CLIC

Parameter	Symbol [unit]	ILC	ILC	CLIC	CLIC
CMS energy	E _{cm} [GeV]	250	500	380	3000
Luminosity	L [10 ³⁴ cm ⁻² s ⁻¹]	1.35	1.8	1.5	6
Gradient	G [MV/m]	31.5	31.5	72	100
Repetition rate	f _r [Hz]	5	5	50	50
Bunches per train	n	1312	1312	352	312
Particles/bunch	N [10 ⁹]	20	20	5.2	3.72
Bunch length	σ _z [μm]	300	300	70	44
Energy spread	[%]	0.1-0.2	0.1-0.2	0.35	0.35
Emittances	ε _{x,y} [nm]	5x10 ³ /35	5x10 ³ /35	950/30	660/20
IP beam size	σ _{x,y} [nm/nm]	520/8	474/6	149/3	40/1
Beta-functions	b _{x,y} [mm]	13/0.41	22/0.48	8/0.1	6/0.07

Compiled by Daniel Schulte

Energy scales





ILC Candidate Location: Kitakami, Tohoku



LHCP Bologna, Steinar Stapnes

8 June 2018

ILC Layout





Parameters	Value
C.M. Energy	500 GeV
Peak luminosity	1.8 x10 ³⁴ cm ⁻² s ⁻¹
Beam Rep. rate	5 Hz
Pulse duration	0.73 ms
Average current	5.8 mA (in pulse)
E gradient in SCRF acc. cavity	31.5 MV/m +/-20% Q ₀ = 1E10



ILC: SCRF



Ultra-high Q_0 (10¹⁰)

Almost zero power (heat) in cavity walls (in SC RF the main efficiency issues related to fill factors and cryogenics) Standing wave cavities with low peak power requirements Long beam pulse (~1 ms) - favorable for feed-backs within the pulse train

Low impedance

Beam generates low "wakefields"

Relatively large structures (1.3 GHz)



Worldwide SRF Collaboration





The European X-FEL



Progress:

...

2013: Construction started

2016: E- XFEL Linac completion 2017: E-XFEL beam start

> 1.3 GHz / 23.6 MV/m 800+4 SRF acc. Cavities 100+3 Cryo-Modules (CM) : ~1/10 scale to ILC-ML







SRF Cavity Performance



ILC goal: 31.5 MV/m

FEL goal: 24 MV/m

Achieved: 29.8 MV/m



After Retreatment: E-usable: 29.8 ± 5.1 [MV/m]

(RI): E usable 31.2 ± 5.2 [MV/m]), w/ 2nd EP
(EZ): E usable 28.6 ± 4.8 [MV/m]), w/ BCP (instead of 2nd EP)

A. Yamamoto, 171106



14

Recent ILC Development



Cost saving studies, e.g.

L. Evans A. Yamamoto

- Coupler design 1-2%
 - Cavity material 2-3%
- No more hydrofluoric acid for chemical treatment 1-2%
- Higher gradient and more efficient cavities 4-5%

• ...

Modified exposure to nitrogen (from FNAL) Before: doping with few minutes at 800 °C Now: a day or so at 120 °C Nitrogen infusion appears very promising

- Increase in gradient
- Increase in Q₀



ILC since the TDR in 2012-13: Technical focus and changes





Site specific studies

Technical developments for most accelerator systems - high Q improvements for example

E-XFEL at DESY successfully constructed and put into operation – a key technology demonstration

ILC since the TDR in 2012-13: Technical focus and changes





8 June 2018

Site specific studies

Technical developments for most accelerator systems - high Q improvements for example

E-XFEL at DESY successfully constructed and put into operation – a key technology demonstration



	Collision E. [GeV]	Tunnel Space [GeV]	Value Total (MILCU in 2012)	Reductio n [%]	же жила стат лаа станасска лаа станасска лаа The International Linear Collider Machine Staging Report 2017
TDR	250/250	500	7,980	0	Addendum to the International Linear Collider Technical Design Report published in 2013
TDR update	250/250	500	7,950	-0.4	
Option A	125/125	250	5,260	-34	
Option A' (w/ R&D)	125/125	250	4,780 w/ R&D success	-40	Linear Collider Collaboration October 2017 Editors Lyn Eines aud Discolar Michaene

Recent proposal to start with an initial energy of 250 GeV (<u>physics impact report</u>) – key issues:

- Higgs precision depends significantly on HiLumi performance and theory assumptions (<u>link</u>)
- Below ttbar threshold
- Reduced search capabilities

Nevertheless, provides impressive precision, and remains upgradable.

TDR costs of ~8 BILCU for 500 GeV (ILCU = 2012 US\$ estimate used in the TDR) can be reduced by up to ~40%

Status and Prospect for ILC





Status and Prospect for ILC





 Physics WG, and TDR Validation WG re-organized to evaluate ILC-250GeV.



8 June 2018

CLIC layout, power generation





LHCP Bologna, Steinar Stapnes

Drive beam quality

• Produced high-current drive beam bunched at 12 GHz



Three challenges:

- High-current drive beam bunched at 12 GHz
- Power transfer + mainbeam acceleration
- ~100 MV/m gradient in main-beam cavities

Two beam acceleration

• Demonstrated two-beam acceleration



- High-current drive beam bunched at 12 GHz
- Power transfer + mainbeam acceleration
- ~100 MV/m gradient in main-beam cavities











8 June 2018

X-band performance

• Achieved 100 MV/m gradient in main-beam RF cavities

Three challenges:

- High-current drive beam bunched at 12 GHz
- Power transfer + mainbeam acceleration
- ~100 MV/m gradient in main-beam cavities











Nano-beams

The CLIC strategy:

- Align components (10µm over 200m)
- Control/damp vibrations (from ground to accelerator)
- Measure beams well allow to steer beam and optimize positions
- Algorithms for measurements, beam and component optimization, feedbacks
- Tests in small accelerators of equipment and algorithms (FACET at Stanford, ATF2 at KEK, CTF3, Light-sources)







LHCP Bologna, Steinar Stapnes

SwissFEL – C-band linac







- 104 x 2m-long C-band structures (beam → 6 GeV @ 100 Hz)
- Similar um-level tolerances
- Length ~ 800 CLIC structures
- Being commissioned



CLIC Technology and FELs





CLIC technology for different applications

- EU co-funded FEL design study
- SPARC at INFN-LNF
- ... many other small systems ...



INFN Frascati advanced acceleration facility EuPARXIA@SPARC_LAB





LHCP Bologna, Steinar Stapnes

Cost and Power



Year 🕨

Table 11: Value estimate of CLIC at 380 GeV centre-of-mass energy.

	Value [MCHF of December 2010]
Main beam production	1245
Drive beam production	974
Two-beam accelerators	2038
Interaction region	132
Civil engineering & services	2112
Accelerator control & operational infrastructure	216
Total	6690





A cost of ~6 BCHF and power ~200 MW are considered "reasonable" values → implementable

8 June 2018

LHCP Bologna, Steinar Stapnes

2013 - 2019 Development Phase

Development of a Project Plan for a staged CLIC implementation in line with LHC results; technical developments with industry, performance studies for accelerator parts and systems, detector technology demonstrators

2020 - 2025 Preparation Phase

Finalisation of implementation parameters, preparation for industrial procurement, Drive Beam Facility and other system verifications, Technical Proposal of the experiment, site authorisation

2026 - 2034 Construction Phase

Construction of the first CLIC accelerator stage compatible with implementation of further stages; construction of the experiment; hardware commissioning



2019 - 2020 Decisions

Update of the European Strategy for Particle Physics; decision towards a next CERN project at the energy frontier (e.g. CLIC, FCC)

2025 Construction Start

Ready for construction; start of excavations

2035 First Beams

Getting ready for data taking by the time the LHC programme reaches completion



8 June 2018

Conclusions

Important progress toward the EU strategy

ILC

250 GeV centre-of-mass being evaluated

SCRF: European XFEL is large-scale prototype

Political process ongoing

Hope for executive level statements this year

CLIC

380 GeV first energy stage

Normal conducting FELs are prototypes, e.g. Swiss FEL

Work on further stages to 3 TeV

Project Implementation Plan by end of 2018

Many thanks to D.Schulte, L. Evans, Y.Okada, S.Michizono, A.Yamamoto, W. Wuensch, Ph. Burrows ... the ILC and CLIC teams



