





### **Update on MQXF**

Paolo Ferracin on behalf of the MQXF collaboration

WP3 Meeting 05 December 2017 CERN

### **Acknowledgments**

#### CERN

 A. Ballarino, H. Bajas, M. Bajko, B. Bordini, J.C. Perez, S. Izquierdo Bermudez, J. Ferradas Troitino, P. Fessia, C. Fichera, L. Fiscarelli, L. Fleiter, P. Grosclaude, M. Guinchard, P. Hagen, O. Housiaux, F. Lackner, P. Moyret, H. Prin, E. Rochepault, S. Sequeira Tavares, E. Todesco, G. Vallone

#### BNL

M. Anerella, A. Ghosh, P. Joshi, J. Muratore, J. Schmalzle, P. Wanderer

#### FNAL

 G. Ambrosio, R. Bossert, G. Chlachidze, L. Cooley, E. Holik, S. Krave, F. Nobrega, I. Novitsky, C. Santini, S. Stoynev, T. Strauss, M. Yu

#### LBNL

D. Cheng, D.R. Dietderich, R. Hafalia, M. Marchevsky, H. Pan, I. Pong, S. Prestemon, E. Ravaioli, G. Sabbi, X. Wang

#### SLAC

- Y. Nosochkov
- CEA Saclay
  - H. Felice
- LASA
  - V. Marinozzi, M. Sorbi
- Tampere University of Technology
  - T. Salmi







### **Outline**

- Status of procurement of components
  - What and how much, when, where (storage)
- Status and plans for short models
  - Coil fabrication and tests
- Status and plans for prototype
  - Coil fabrication and tests
- AUP plans for the next 2 years







### **Outline**

- Status of procurement of components
  - What and how much, when, where (storage)
- Status and plans for short models
  - Coil fabrication and tests
- Status and plans for prototype
  - Coil fabrication and tests
- AUP plans for the next 2 years







### Some milestones (prototypes)

### MQXFBP1


Assembly:06/18

• Test: 05/19

### MQXFBP2

• Assembly: 04/19

• Test: 02/20










### Some milestones (series)



- First series coil
  - Fabrication begins in 04/19
- First series magnet
  - Assembly begins in 11/19







### **Procurement coil components**

Coil parts	MQXFBP1	MQXFBP2	Series	Comments
Cable insulation	On going	Order placed	Order placed	
End-parts (spacers, end-shoe)	Delivered	Delivered	All by 08/18	
Poles and end-shoe extensions	Delivered	Delivered	All by 08/18	
Coating for end-parts	Delivered	Order to be placed	Order to be placed	Company qualified found
Wedge	Delivered	Delivered	All by 08/18	
Traces	Delivered	Order to be placed	Order to be placed	IT completed
Mid-plane shim	Delivered	Delivered	All by 12/17	

- First MQXFBP1 coil (103)
  - Fabrication started in 05/17
- First MQXFBP2 coil (201)
  - Fabrication begins in 05/18
- First series coil
  - Fabrication begins in 04/19







### **Procurement magnet components**

- MQXFBP1: Assembly in 06/18;
- MQXFBP2: Assembly in 04/19
- First series magnet: assembly begins in 11/19

Magnet support structure	MQXFBP1	MQXFBP2	Series	Comments
Magnet support structure	·	•		comments
Nitronic material (no armco)	Delivered	Delivered	Delivered	
Thick ARMCO	Delivered	Delivered	All by 04/18	
Aluminum material	Delivered	Delivered	Starting in 03/18	
Aluminum shell	Delivered	Order by 02/18	Starting in 01/19	MQXFBP2 order after mech test
Thick yoke	Delivered	Order by 02/18	Starting in 04/19	MQXFBP2 order after mech test
Thick pad	Delivered	Order by 02/18	Starting in 04/19	MQXFBP2 order after mech test
Collars	Delivered	Order by 02/18	Starting in 04/19	MQXFBP2 order after mech test
Master	Delivered	Order by 02/18	Starting in 01/19	MQXFBP2 order after mech test
End-plate	Delivered	Order by 02/18	Starting in 01/19	MQXFBP2 order after mech test
Thin yoke	Delivered	Order by 02/18	MS to be (re)done	MQXFBP2 order after mech test
Thin pad	Delivered	Order by 02/18	MS to be (re)done	MQXFBP2 order after mech test
Keys	Delivered	Delivered	Delivered	
Bushings	Delivered	Delivered	All by 02/18	
Tie-rods	Delivered	Delivered	Delivered	
Rods	All by 01/18	All by 01/18	All by 01/18	
Pushers SS	All by 01/18	All by 01/18	All by 01/18	
Pushers G11	Delivered	Delivered	Delivered	
Bullets	All by 01/18	All by 01/18	All by 01/18	
Welding blocks	All by 01/18	All by 01/18	All by 01/18	
Backing strip	Delivered	All by 04/18	All by 04/18	
Pole key	Delivered	Delivered	All by 02/18	
Bladders	All by 01/18	Not ordered	Not ordered	







### **Procurement cold mass components**

- MQXFBP1 cold mass: Assembly in 10/18
- MQXFBP2 cold mass: Assembly in 07/19
- First series cold mass: Assembly in 03/20

Cold mass	MQXFBP1	MQXFBP2	Series	Comments
Stainless steel shells material	Delivered	Delivered	IT done, order soon	
Stainless steel shells fabrication	Starting in 04/18	Starting in 04/18	MS to be started in 12/18	
End covers	Not ordered	Not ordered	Not ordered	Design in progress
Heat exchanger tubes	All by 03/18	All by 03/18	Not ordered	







### **Outline**

- Status of procurement of components
  - What and how much, when, where (storage)
- Status and plans for short models
  - Coil fabrication and tests
- Status and plans for prototype
  - Coil fabrication and tests
- AUP plans for the next 2 years








# Short model program Coil fabrication

- 1st generation coils: 13
  - CERN: 7
    - 1 Cu and 1 low-grade
    - 3 RRP 132/169 and 2 PIT
  - LARP: 6
    - All RRP 108/127
- Available for test: 8
- 1 tested in MQXFSM1
  - Coil 2
- 4 tested in MQXFS1
  - 103,104,3,5
- 4 not tested (MQXFS2)
  - 102 (splice issue)
  - 201- 202 (low J<sub>c</sub> and RRR)
  - Coil 6










# Short model program Coil fabrication

- 2<sup>st</sup> generation coils: 21 planned
  - CERN: 18
    - RRP: 3 (132/169) and 5 (108/127)
    - PIT: 5 (no barrier) and 5 (barrier)
  - LARP: 3
    - RRP 1 (144/169) and 2 (108/127)
- 5 to be tested in MQXFS3
  - 105,106,107,7 (8)
- 5 to be tested in MQXFS5
  - 203,204,205,206 (207)
- 5 to be tested in MQXFS4
  - 108,109,110,111 (112)
- 5 to be tested in MQXFS6
  - 208,209,210,211 (212)
- 1 to be tested in MQXFS1e
  - 9









# Short model program Coil fabrication

- Summary
  - 27 coils fabricated from early 2014
    - **19** by CERN
    - 8 by LARP
  - 7 coils to be fabricated by mid 2018
    - 6 by CERN
    - 1 by LARP
  - Total: 34 coils
- Spare or not tested (without major NC)
  - 2<sup>nd</sup> generation: 207, 107, 212
  - 1<sup>st</sup> generation: 6








# Short model program Magnets

- MQXFS mirror
- MQXFS1
  - RRP coils, first generation cable (a)
    - azimuthal and axial increase (b and c)

 Stainless steel shell (d, in 01/18) and coil with smaller wedge gap (e, in 05/18)










# **Short model program Magnets**

#### MQXFS3

- RRP coils, second generation cable (a)
  - Axial increase (b), change of coil with azimuthal increase (c, in progress), stainless steel shell + beam screen (d, in 04/18)
- MQXFS5 (PIT)
  - RRP coils, second generation cable (a)
    - Replace 1 coil with coil 207: no inner layer quench heaters (b, in 03/18)










# Short model program Magnets

- MQXFS4
  - RRP (final) coils, second generation cable (a, in 06/18)
- MQXFS6 (PIT)
  - PIT (with bundle) coils, second generation cable (a, in 11/18)
- Test to be added: 2000 powering cycles









### **Outline**

- Status of procurement of components
  - What and how much, when, where (storage)
- Status and plans for short models
  - Coil fabrication and tests
- Status and plans for prototype
  - Coil fabrication and tests
- AUP plans for the next 2 years








# CERN prototype program Coil fabrication

 1 coil with Cu cable and 2 with low grade Nb<sub>3</sub>Sn completed

- 1st and 4th prototype coils (103 and 106) rejected for major NC
- New 1<sup>st</sup> and 2<sup>nd</sup> prototype coils (104 and 105) wound and ready for reaction
- The 3<sup>rd</sup> (107) wound
- The 4<sup>th</sup> (108) to be wound in 01/18
- In total, 5 RRP and 6 PIT coils to be produced










# CERN prototype program Prototype plans

Test FNAL
Test CERN
Test BNL
Shipment

- Assembly structure started
- 4 practice coils available
  - 001,101,102,103
- MQXFB mech. test
  - Goal: full loading
- MQXFBP1
  - Test in May 2019
- MQXFBP2
  - Test in Feb. 2020










# CERN prototype program Prototype plans

Test FNAL
Test CERN
Test BNL
Shipment

- To be discussed
  - Test of MQXFBP1b with beam screen?
  - Test of full cold mass with corrector?









### **CERN** prototype program











### **Outline**

- Status of procurement of components
  - What and how much, when, where (storage)
- Status and plans for short models
  - Coil fabrication and tests
- Status and plans for prototype
  - Coil fabrication and tests
- AUP plans for the next 2 years








# LARP prototype program Coil fabrication

- Coils for practice & mirror: 2 coil, 4-m long, completed
  - Coil 01 for mirror (1st generation cable)
  - Coil 01b practice (1st generation cable)
- Coils for MQXFAP1: 4 coils, 4-m long, completed
- Coils for MQXFAP2
  - 101 to 106 (FNAL and BNL)
- Coil for MQXFA3
  - From 107 (FNAL) and from 201 (BNL)










# LARP prototype program Prototype plans

- MQXFAP1 (4 m long)
  - Test in summer 2017 with coils 02,03,04,05
- MQXFAP2 (4.2 m long)
  - Test in by mid-2019 with 101,102,104,105 (106)
- LQXFAP (prototype cold mass)
  - Test in by early 2020 with MQXFAP1 and MQXFAP2
- MQXFA3 will be first series magnet









### LARP prototype program (MQXFAP1)










### **Overview of MQXF series**









### **Appendix**








### Overview of MQXF design


- OD: 630 m
- Stainless steel shell
  - 8 mm for LHe containment
- Aluminum shell
  - 29 mm thick
- Iron yoke
  - Gaps open
  - 4-fold symmetry
- Iron master plates
  - Bladder and keys
- Iron pad
- SS axial rods
- Aluminum collars
- G10 pole key
- Ti alloy poles






























- Aluminium collar
  - No coil pre-load











No coil pre-load










- Iron master
  - Half-length plates for bladders and keys























Coil-pack sub-assembly

