

Mechanical Issues SPL  
cavities/cryomodules  
Workshop CERN 30 Sep. 2009

Preparatory slides

W. Weingarten

# SPL cavities general parameters

Type of accelerating structure	$\beta = 1/0.65$	standing wave
Accelerating mode		TM <sub>010</sub> , $\pi$ -mode
Fundamental frequency	$f_{RF}$ [MHz]	704.4
Nominal gradient	$E_{acc}$ [MV/m]	25
Quality factor	$Q_0$	$1 \cdot 10^{10}$
Active length	$L$ [m]	1.065
Cell-to-cell coupling	$k_{cc}$ [%]	?
Iris diameter [mm]		$\sim 129$
$R/Q$ [ $\Omega$ ]		$\sim 570$
$E_{peak}/E_{acc}$		$\sim 2.2$
$B_{peak}/E_{acc}$	[mT/MV/m]	$\sim 4.4$
Tuning range	[kHz]	?
$\Delta f/\Delta L$	[kHz/mm]	$\sim 250$ <sup>1)</sup>
Lorentz-force detuning constant	$K_{Lor}$ [Hz/(MV/m) <sup>2</sup> ]	?
$Q_{ext}$ of input coupler		$1 \cdot 10^6$
Cavity bandwidth	$f/Q_{ext}$ [Hz] FWHM	704
Fill time	[ $\mu$ s]	460
HOM couplers	absorbing layer in between cavities	

***Parameters of the five-cell  $\beta = 1$  cavity (note:  $R = V^2/P$ , where  $P$  is the dissipated power and  $V$  the peak voltage in the equivalent LCR circuit).***

<sup>1)</sup> Adopted from H. Saugnac et al., Preliminary design of a stainless steel helium tank and its associated cold tuning system for 700 MHz SCRF cavities for proton

# SPL cavities general parameters - Nb <sup>1)</sup>

## Electrical and mechanical properties of Niobium

Residual Resistivity Ratio > 300

Thermal conductivity @ 4.2 K 10 - 100 W/(mK)

Grain size  $\approx 50 \mu\text{m}$

Yield strength > 50 N/mm<sup>2</sup>

Tensile strength > 140 N/mm<sup>2</sup>

Elongation at fracture > 30%

Vickers hardness HV 10  $\leq 60$

Linear expansion  $(L_{273} - L_{4.2})/L_{4.2}$  1.3 ‰

Melting point 2468 - 2497 °C

Recrystallisation temperature 830 - 1230 °C

Stress relieving temperature 780 °C (1 h)

## Content of the main impurities $\mu\text{g/g}$

Residual Resistivity Ratio > 300

Ta  $\leq 500$

H  $\leq 2$

W  $\leq 50$

O  $\leq 10$

Mo  $\leq 50$

N  $\leq 10$

Ti  $\leq 50$

C  $\leq 10$


Fe  $\leq 50$



Ni  $\leq 50$

<sup>1)</sup> adopted from XFEL Design Report


# DIMENSIONS DE LA CAVITE SPL $\beta = 1$

## DESIGN CEA-SACLAY






## POSITION ET DIMENSIONS DU COUPLEUR DE PUISSANCE



# Experience from DESY - Important production steps <sup>1)</sup>

- Deep drawing (die from anodized Al alloy)
- EB welding at iris and equator
- Annealing for re-crystallization under avoiding to grow large grains @ 750-800°C in a vacuum oven at a pressure of  $10^{-5}$ - $10^{-6}$  mbar for 1-2 h
- Full penetration EB welding (preferably from the inside) in good vacuum ( $p < 5 \cdot 10^{-5}$  mbar)
- Removal of roughness and defects by grinding
- Intermediate frequency checks and possibly trimming mandatory
- Flanges from NbTi alloy (about 50%Ti)



<sup>1)</sup> adopted from XFEL Design Report

## Important preparation steps for cavities <sup>1)</sup>

- electrochemical removal of a thick Niobium layer (so-called damage layer) of about 150  $\mu\text{m}$  from the inner cavity surface
- a rinse with particle free/ultra-pure water at high pressure ( $\sim 100$  bar) to remove residues from the electrochemical treatment
- outside etching of the cavities of about 20  $\mu\text{m}$
- ultra-high vacuum annealing at 800°C (out-gas possibly dissolved hydrogen / relieve mechanical stress)
- tuning of the cavity frequency and field profile
- removal of a thin and final layer of about 30  $\mu\text{m}$  by EP prior to the low power acceptance test done in a vertical dewar
- rinsing with particle free/ultra-pure water at high pressure (100 bar) to remove surface contaminants and drying in class 10 clean room
- assembly of auxiliaries (pick-up probe and HOM pick-up)
- baking at 120°C in an ultra-high vacuum
- additional six times rinse with high pressure ultra-pure water (100 bar)
- low power acceptance test at 2 K temperature


<sup>1)</sup> adopted from XFEL Design Report




# Important preparation steps for string assembly<sup>1)</sup>

- disassembling cavities in clean room from vertical test insert
- measurement of field profile and frequency in clean room
- tank welding in normal workshop area
- provisional input antenna replaced by the power coupler
- cavities are rinsed six times with ultra-pure high pressure water
- insertion of a bellows between the beam pipes of the individual components in a class 10 clean-room
- integral leak check


<sup>1)</sup> adopted from XFEL Design Report



**Figure 4.2.4** “Excitation curves” of the best cavities treated with 800°C furnace treatment and EP. The XFEL baseline gradient of 23.4 MV/m is exceeded by a significant margin.



**Figure 4.2.5** Comparison of the accelerating gradients at  $Q_0=10^{10}$  in the first performance test after the full preparation sequences using etching with post-purification at 1,400°C (blue) and EP with 800°C annealing (red).



**Figure 4.2.7** Performance of the TTF accelerator modules. The plot shows the average maximum gradient in the accelerator modules against the average gradient achieved in the acceptance tests at  $Q=10^{10}$  (open symbols). In addition, the operational gradient of the modules is plotted against the acceptance test gradient (closed symbols) which is based on equal RF power feeding.

## Experience from DESY - Cavity weld to He vessel issues

- keep  $E_a$ ,  $f$ , field flatness
- welding done after vertical test @ 2 K
- *Is welding possible before 120 °C baking and before vertical test?*
- *Yes, but under stepwise check of  $f$  and field flatness by field profile measurement system (automated system operational, J. Iversen, SRF2009, THPPO071)*




Figure 2: Layout of the FMS.




Figure 3: Average field flatness shift during welding



## Some engineering wisdom

### – Shaping

- Hydroforming avoids welds and hence is less time-consuming;  
Tubes are available at Plansee  
But: the larger the cavity the more difficult is the hydroforming

### – Joining

- Discouraging experience with Stainless Steel brazings at HERA (leaks)
- Welding Nb – SS possibly seems not possible (melting temperature different)
- Connection between cavity and He tank: Nb tube – Nb ring - NbTi flange - Ti tank

### – Flanges and gaskets

- Helicoflex not appreciated because it might emit particles
- Al diamond shaped gasket OK for NbTi flange; no leak problems
- But: 2 X higher etching rate for NbTi than for Nb (cover needed)

# Experience from CERN - Cavity weld to He vessel issues

J. P. Bacher , E. Chiaveri and  
B. Trincat, Brazing of  
niobium to stainless steel  
for UHV application in  
superconducting cavities,  
CERN/EF/RF 87-7, 5  
December 1987





Fig.3

The process shown in fig. 3 has been used to braze stainless steel flanges to niobium tubes which equip Nb superconducting cavities [3].

[3] G. Arnolds-Meyer et al., CERN/EF 87-9.