

# Plans for ProtoDUNE-SP Commissioning and Run

*Flavio Cavanna*

**DUNE Collaboration Meeting**

FERMILAB - 15 May 2018

---

# EHN1 extension -



two weeks ago...

04/25/2018 20:18:39


NPOVERVIEW1




# EHN1 extension - today



05/14/2018 22:49:11  
NPOVERVIEW1





# protoDUNE-SP Goals

Q1

- Prototyping production and installation procedures for DUNE far Detector Design *[task of the ongoing effort]*
- Validate design from perspective of basic detector performance
- Accumulate test-beam data to understand/calibrate response of detector to different ptcl. species
- Demonstrate long term operational stability of the detector

# and the Programme:

- 2018: (\*) Detector activation, **Test-Beam Run + Cosmics**
- 2019: (\*\*) endurance Run with Cosmics (long term stability)\*\*
- 2020: continuing Operation (Cosmics) if desired
- 2021: keep open the option of recording Test Beam data after CERN LS2
- 2022: *no Operation is foreseen in and beyond 2022.*

(\*) Detector commissioning and activation, data acquisition with Beams and the prompt execution of data processing and reconstruction have the highest priority in DUNE

# (\*\*) Note about the Long-Term Stability Run 2019


The long term stability Run with Cosmic  
- *6 to 12 months extending in 2019* -  
has been communicated/proposed to CERN SPSC on April 20

**The plan for the long term stability Run is not finalized yet**

- minimal goal: maintain detector active and  
acquire short Cosmic Run every day
- *dedicated tests at different cryogenic system and detector operating  
parameters presumably to be included in the plan*

*Allocation of Resources for Detector Operation and Computing in 2019  
under discussion*

# Installation, Commissioning and the 2018 Run



## Timeline

# ProtoDUNE-SP Operation Plan

The timeline for operations with beam is very limited  $\implies$  need to have a plan which insures the highest quality detector performance and data taking efficiency.

*The development of the plan is based on three main guidelines:*

- take advantage of the highly qualified expertise of system experts, in particular those based at CERN and directly involved in detector construction, test, integration, installation and in data acquisition, monitoring and controls.
- provide opportunity for DUNE collaborators who have not been intimately involved in the detector construction and integration to gain experience with the liquid argon detector technology (valuable for the DUNE far detector design and construction).
- plan is subdivided into two major phases (after manholes closed by End of June):
  - 🕒 Cryogenics Commissioning, BeamLine Commissioning, and **Detector Commissioning&Activation**
  - 🕒 Engineering Run  $\rightarrow$  **Physics Run w/ Beam** (and Cosmics)



- **Detector Commissioning/Activation** *“inside the Cryostat”* teams defined for:

- High Voltage
- Beam Plug
- APA Wire Bias
- Cold and Warm electronics
- Photon Detectors and R/O Electronics
  
- Temperature Monitoring
- Purity Monitoring
- Gas Analyzers
- Cameras
  
- Grounding and shielding
  
- Data Acquisition
- Detector Controls System

Requested :

- Contact person
- Expert list
- Tasks and procedures

Responses have started

*As well as for*

- **Commissioning operations “outside the Cryostat” and for start-up**

## **Data-taking:**

- Beam Instrumentation
- Muon Tagger
- Trigger
- Data Quality Monitor
- Computing
- Data Reconstruction and Analysis
  
- Beam Line
- Cryogenics

Responses  
on Plans and Procedures  
will enter into a ***master file***  
where a global sequence of  
events and activities will be  
coordinated so that  
prerequisites and exclusions  
can be met.

# Organizational Structure on the ground


**CERN Neutrino Platform**  
*M. Nessi (CERN)*

## ProtoDUNE-Single Phase

*Coordinators*

Liaison w/ CERN IT, FNAL SCD, DUNE Computing in matter of Computing Resources (*A. Dell'Acqua/CERN*)

Commissioning Leader, Run Coordinator (*F. Resnati/CERN, R. Acciarri/FNAL*) + Deputy (*A.Zani*)



# The CERN Experimental Programme

Grey Book database

Find in Greybook...

» NP04

Welcome

Experiments & Projects

Institutes

Participants

## RESEARCH PROGRAMME

LHC

SPS

PS

AD

ISOLDE Facility

Irradiation Facility

Neutrino Platform

GRADE

CTF3

R&D

Non-accelerator experiments

## RESEARCH ACTIVITIES

Experiments and Projects  
under Study

Recognized Experiments

Completed Experiments

## RELATED LINKS

EP Department

## NP04/ProtoDUNE-SP

Prototype of a Single-Phase Liquid Argon TPC for DUNE

**SYNONYM:**

ProtoDUNE-SP

**RESEARCH PROGRAMME:** Neutrino Platform

**APPROVED:**

28-09-2016

**BEAM:**

**STATUS:**

Preparation

Overview

Institutes

Participants



**SPOKESPERSON:** Christofas TOURAMANIS  
Flavio CAVANNA

**DEPUTY SPOKEPERSON(S):**

**CONTACT PERSON:** Simona KRIVA

**TECHNICAL COORDINATOR:**

**RESOURCES COORDINATOR:**

**GROUP LEADER IN MATTERS OF**

**SAFETY (GLIMOS):**

**DEPUTY GLIMOS:**

**DEPARTMENTAL FLAMMABLE GAS**

**SAFETY OFFICER (FGSO):**

**DEPARTMENTAL CRYOGENICS**

**OFFICER (CSO):**

**EXPERIMENT SECRETARIAT E-MAIL:** cenf.secretariat@cern.ch

**EXPERIMENT SECRETARIAT WEB SITE:**

**NUMBER OF INSTITUTES:** 42

**NUMBER OF AUTHORS:** 7

**NUMBER OF PARTICIPANTS:** 164

**NUMBER OF COUNTRIES:** 6

Status history

Status	Start date	End date
Preparation	22-02-2016	

TODAY

# Plan&Coordination of Commissioning/Activation

*ProtoDUNE-SP Detector Activation Preparatory Meeting:*

**Thurs. 9:00 am CDT (16:00 CET) - Weekly**

[org: F. Resnati/CERN, R. Acciarri/FNAL - Commissioning Leader, Run Coordinator]

Attendance: All ProtoDUNE Teams  $\oplus$  Neutrino Platform Team **and**  
CERN Specialized Groups

[Home](#) [Experiments](#) [DUNE](#) [Prototypes](#)  
[ProtoDUNE single phase \(NP04\)](#)


[Detector Commissioning and Activation Meeting](#)




The screenshot shows the INDI CO (Integrated Digital Conference) website interface. At the top, the INDI CO logo is displayed with the tagline "Integrated Digital Conference". Below the logo is a navigation bar with links for "Home", "Create event", "My profile", and "Help". A breadcrumb trail below the navigation bar reads: "Home » Experiments » DUNE » Prototypes » ProtoDUNE single phase (NP04) » Detector Commissioning and Activation Me...". The main content area of the page features the title "Detector Commissioning and Activation Meeting" in a large, bold, orange font.

# outside protoDUNE Cryostat

## External Beam Line, Beam Detectors and Muon Tagger



- many opportunities for fast trigger combinations from Beam instrumentation - Muon Tagger (and internal Photo-Detector)
- opportunity to trigger or veto TPC readout for beam halo muons





Trigger & ToF  
UpStream

BeamProfile X-Y  
BeamProfile X  
BeamProfile X  
Trigger Counter

BeamProfile X-Y  
Cherenkov Counter  
Cherenkov Counter

BeamProfile X-Y  
Trigger & ToF  
DwStream



Blue: quadrupoles.  
Red: bending magnets

Boxes: Beam detector supports  
Beam Profile X,Y = Scint. Fibre Tracker  
Trigger & Time-of-Flight detector =  
= Scint. Fibre paddle


Cherenkov counters

# NP04/H4 Beam Line & Beamline Detectors




# Muon Tagger

U of Chicago, Virginia Tech,  
U Minnesota, U Rochester, FNAL





Muon Tagger Modules





# Interfaces





# Cryogenic Commissioning Plan

CRYOGENICS					
Task	Duration	Specs	Tech Resp	Shift Resp	Monitoring
GAr Purging	1w + 1w (conting.)	- 20 Vol/day - leaks checks and repairs	CERN-NP	CERN-NP	
Safety Clearance	1d	All documentation ready	CERN-NP		
Cooling	1 w	- 1 K/hr, $\Delta T \approx 200$ K	CERN-NP CERN TE-CRG	CERN-NP	Temp
LAr Filling	3 w + 1 w (conting.)	- ~ <b>550 kL</b> - 2 trucks/day into 2x20000 L storage dewars - 40000L/day, 5 days/week	CERN-NP CERN TE-CRG	CERN-NP + ProtoDUNE-SP	Temp T-Gradient LAr Level
LAr Recirc. & Purific.	1w (conting.)	<i>Goals:</i> Stable Cryo Cond. $\tau_e \approx 2$ ms	CERN-NP pDUNE-SP	ProtoDUNE-SP + CERN-NP	T-Gradient LAr Purity

Start: last week of June  
End: last week of Aug.

3+ weeks built-in contingency

# Plan for ProtoDUNE-SP Operation

## Phase 1: Detector Commissioning and Activation

### System Experts on-site at CERN

[period of stay to be defined in the Commissioning Plan and Procedure,  
*Approved Support for travel and accommodations for non-resident provided by the DUNE project* ]

#### July 2018

**In parallel to (and within the limitations from) the concurrent Cryogenic Commissioning operations,** the focus of activity will be to:

- operate and run CryoInstrumentation (T-Profilers, PurMon, Cameras, GasAnalysers)
- commission as much of the detector elements as possible inside and outside the cryostat:
  - from cathode (moderate) HV ramp to bias V on the wire planes
  - from APA-CE performance tests and monitor noise levels
  - from systems local read-out to full DAQ r/o chain tests
  - from available Beam Detectors and Muon Tagger Modules tests to Trigger Logic setting and debugging
  - ...
- develop and exercise the tools for detector and beamline monitoring (DQM and DCS)

#### August 2018

The focus of activity will be :

- 1.complete cryogenic commissioning and LAr purification
- 2.Beamline and beamline instrumentation commissioning
- 3.LAr Detector Commissioning

LAr DETECTOR	Commissioning
Task	Duration
Cathode HV ramp	1 w +
Wire Planes	
V-bias	
CE activation	
PD activation	1 w (conting.)
DAQ activation	
On-Line Mon	
DQM	
Data Archiving	

**completed by Sept. 5 -  
possibly a week earlier**

• Beam operations:

August 29, 2018 (Start)

November 11, 2018 (End)

H4 Beam Time Allocation to NP04 by SPS-C:

7.5 weeks (including Beam Commissioning Time) in 4 blocks (2w + 2w + 2w + 1.5w)



schedule issue date: 26-Jan-2018


Version: 1.0

LHC Exp. PS/SPS Exp. Other Exp. INT Exp.

		Mar			Apr			Mai			Jun			Jul			Aug			Sep			Oct			Nov			Dec																																																																								
Week		11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50																																																												
Machine																										UA9 TS1 Coldex																									UA9 TS2 Coldex																									Coldex																									RP
North Area	T2 - H2	SPS & TT20 Setup 18			NA Setup 8	HERD FIT 7	NA62 GTK 7	NA61 SHINE 14						TIC 7	Calice (Alcal) 7	ATLAS ZDC 7	Calice (Alcal) 7	NA61 K 60GeV/c 7	NA61 SHINE 21			AXIAL 7	KLEVER 7	EMMA 7	CMS HGCAL 7	CMS HCAL 14			Calice (Sdhcal) 14			HERD 7	NA61 SHINE 7	CMS HGCAL 7	NP02 26			NA61 SHINE 28																																																															
	T2 - H4	SPS & TT20 Setup 18			NA Setup 8	NA63 9	CMS ECAL 7	GIF RD51 14			NA64 setup 7	NA64 35			CMS ECAL 7	AIDA WP14 7	SHIP installation 7	SHiP Muon 14	SHIP Charm 7	GIF 7	GIF RD51 14			DiTau 7	NP04 setup 7	NP04 7	CMS MTD 7	NP04 14			CMS ECAL 7	NP04 14			GIF RD51 7	NP04 12	RE29 DAMPE 7	HERD 7	ATLAS ZDC 7	CaloCube 7																																																													
	T4 - H6	SPS & TT20 Setup 18			NA Setup 8	Clic pix 7	CMS Outer Tracker 9	ATLAS HGTD 7	ATLAS ITK 14			ATLAS ITK Kartel 7	RD42 7	ALICE muons 7	CERF 7	CMS Outer Tracker / AIDAwp7 7	Clic pix 7	ATLAS HGTD 7	ATLAS ITK 21			ATLAS AFP 14	ATLAS BCM 7	Clic pix 7	ATLAS ITK 14			ATLAS AFP 14	ALICE muons 7	RD42 7	AIDA WP7 7	ATLAS ITK Kartel 14			CMS Outer Tracker 7	ATLAS Strip Tk 7	Clic pix 7																																																																
	T4 - H8	SPS & TT20 Setup 18			NA Setup 8	TOTEM (+UA9) 9	ATLAS # 7	ATLAS HV-CMOS 14			LHCb 14	ATLAS Tilecal 14			ATLAS HV-CMOS 7	TOTEM (+UA9) 7	ATLAS TRT 7	LHCb 21			crysbear 7	CMS ITK 7	ALICE FOCAL 14			TOTEM (+UA9) 7	mu-e 7	ATLAS HV-CMOS 7	FCCee 7	TOTEM (+UA9) 7	ATLAS HV-CMOS 7	CMS ITK 7	LHCb 26			ATLAS Tilecal 14			R2E (+UA9) 7	HNX 14	NUCLEON 7																																																												
	T4 - K12	SPS & TT20 Setup 18			NA Setup 8																									NA62 217																																																																							
	T6 - M2	SPS & TT20 Setup 18			NA Setup 8																									NA58 COMPASS 217																																																																							
TT41					AWAKE 21									AWAKE 21									AWAKE 21									AWAKE 21																																																																					


For further information contact the PS/SPS-Coordinator. Email: Sps.Coordinator@cern.ch, Tel: +41 75 411 3845.

# Expected Rates (H4 beam line MC Calculation): normalized to $10^6$ pions on target per spill (4.8 s)



## Rates at 1 GeV/c

Rate with Collimator



**Engineering Run:**

- Beam-line detectors activation and DAQ sync,
- Beam Trigger activation/test/debug,
- Secondary (Pion) Beam Intensity Tuning (measure/mitigation Muon Halo in LArTPC) ⇨ StartUp Physics Run


Beam Setting (Mom, Sign)	Beam Rate		Beam Time
2 GeV/c – Negative	27 Hz	50% $\pi^-$ , 50% $e^-$	<b>1 week</b>

**Physics Run**

**[expected 3000 spill/day]:**

- ➔ Hadron Beam - Goals:
  - ≥ 500 k Pion evt per momentum setting
  - ≥ 100 k Proton evt per momentum setting
- ➔ Electron Beam - Goal:
  - ≥ 75 k Electron evt per energy setting

Hadron Beam <i>Cu Target</i>			
Beam Setting (Mom, Sign)	Accumul. Stat. (goal)	Trig. Rate/Beam Rate	Beam Time
2 GeV/c - Positive	750 k [500 k $\pi$ ]	25 Hz / 38 Hz	<b>1 week</b>
3 GeV/c - Positive	750 k [500 k $\pi$ ]	25 Hz / 56 Hz	
no beam	-	-	1 week
1 GeV/c - Positive	1 M [500 k $\pi$ ]	25 Hz / 27 Hz	<b>2 week</b>
no beam	-	-	1 week
4 GeV/c - Positive	600 k [500 k $\pi$ ]	25 Hz / 196 Hz	
5 GeV/c - Positive	600 k [500 k $\pi$ ]	25 Hz / 200 Hz	<b>2 week</b>
6 GeV/c - Positive	600 k [500 k $\pi$ ]	25 Hz / 226 Hz	
7 GeV/c - Positive	600 k [500 k $\pi$ ]	25 Hz / 252 Hz	
no beam	-	-	1 week
Electron Beam <i>Pb Target</i>			
Energy Ramp: 0.5, 0.6, 0.7, 0.8, 0.9, 1., 2., 3., 4., 5., 6., 7. GeV	75 k per En. setting  900 k Tot.	25 Hz / 60 Hz	<b>1.5 week</b>



**TPC DATA**



**DAQ**

Raw data decoding

**Raw Data**

Noise filtering, Stuck code mitigation, Deconvolution

**Deconvoluted Data**

Hit finding, Disambiguation  
 PMA, Pandora, WireCell, PD, CNN


**Reconstructed Data**

dQ/dx and dE/dx calibration

**Calibrated Data**

**Detector Performance and Physics Analysis**

**Path to inform the DUNE design**



**ProtoDUNE Analysis talk by Tingjun**



# Plan for ProtoDUNE-SP Operation

## Phase 2: Data Taking Run with Beam (and Cosmics)

### September - October - November 2018

2 shifters / 3x8hr shift / 24h/7d

Shift Team: Expert Shifter (ES) + basic shifter (S)

Shifts will be in the EHN1 Control Room.

Shifters (who are not System Experts) are expected to provide for their travel and daily expenses while at CERN through their home institution funding; however, the DUNE Operations Budget for ProtoDUNE will provide an apartment where temporary shifters may stay while on shift.


Availability and sign-up information will be managed by Maxine Hronek

# SUMMARY

- ProtoDUNE SP is transitioning from **Construction/Assembly** to **Operation** (Commissioning and Run).
- **The plan for Cryo-Commissioning is in place, the plan and procedures for detector commissioning&activation is being developed, SPS Beam Time is allocated, basic Run Plan defined** - fine tuning & swap w/ other SPS users or parasitic time under discussion
- *Highest priority:*
  - DAQ and Off-line SW readiness for timely exploitation of beam and cosmic data.
  - Careful and prompt evaluation of Detector Performance to inform DUNE design and TDR.
- Several Physics topics of interest for longer term studies and Analysis

BACKUP Slides




# ProtoDUNE Liquid Argon Flow Simulations



## Temperature, Impurities and Velocity @ Z = 2m


# H4 (Tertiary) Beam Line

CERN SPS - North Area




### -*Beam Instrumentation:*

- H4 beam line model including concrete shielding:** substantial reduction of background particle rate at TPC front




- Precise **field map calculation for H4 magnets**, important for the muon background calculations
- Exact **bending magnet geometry** completed.
- Optimization of **beam pipe geometry** and dimensions
- Final H4 **beam position** decision taken by ProtoDUNE-SP (NP04) Collaboration



# External Muon Tagger

Trigger logic using coincidence signals from upstream and downstream modules

A FAST NIM signal is generated when a coincidence is found btw the two layers of the hit paddle



- **during beam spill (BeamOn):**
  - ➔ Muon Tagger stand-alone trigger  $\Rightarrow$  **hor-muon halo trigger** for LAr TPC Calibration (e-lifetime, SCE)
  - ➔ in “anti-combination” w/ beam counter trigger  $\Rightarrow$  **veto** TPC readout in case of pile-up or halo/punch-through
- **out of beam spill (CosmicOn):**
  - ➔ Muon Tagger stand-alone trigger  $\Rightarrow$  **hor-muon cosmic trigger** for LAr TPC Calibration (e-lifetime, SCE)
  - ➔ in combination w/ internal PhDet trigger  $\Rightarrow$  **special cosmic event trigger** (cosmic ray induced muon bundles or electromagnetic cascades in atmosphere)

# Summary: (possibly available) Fast Trigger Inputs

Input	Source
BeamON	Spill beam gate
Trig1, Trig2	Bl: Trigger Counters
USTOF, DSTOF	Bl: Upstream, Downstream Time of Flight
BPXY1, BPXY2	Bl: BeamProfile X-Y (closer to Det)
C1, C2	Bl: Trigger Counters

Input	Source
CosmicON	Cosmic post-beam gate
USMTModJ1 Q1-4, USMTModJ2 Q1-4, USMTModS1 Q1-4, USMTModS2 Q1-4	CRT: Upstream, Jura Up/Dw Module Quadrant 1-4, Upstream, Saleve Up/Dw Module Quadrant 1-4
DSMTModJ1 Q1-4, DSMTModJ2 Q1-4, DSMTModS1 Q1-4, DSMTModS2 Q1-4	CRT: Downstream, Jura Up/Dw Module Quadrant 1-4, Downstream, Saleve Up/Dw Module Quadrant 1-4

Input	Source
PDAPAS1-3 PDAPAJ1-3	PD: APA Jura Side 1-3, APA Saleve 1-3 (m-majority out of 10 PD bars)
MichelAPAS1-3 MichelAPAJ1-3	PD: APA Jura Side 1-3, APA Saleve 1-3 (delayed Michel signal)

## examples of possible Trigger Outputs

Path	Trigger Requirements ON	Required OFF
1	BeamON+Trig1+Trig2+USTOF+DSTOF	- USMTModS1Q1
2	BeamON+Trig1+Trig2+USTOF+DSTOF+BPXY1+BPXY2	- USMTModS1Q1
3	BeamON+Trig1+Trig2+USTOF+DSTOF+BPXY1+BPXY2+C1	-C2 - USMTModS1Q1

4	BeamON+USMTModJ1Q1+DSMTModJ1Q1+PDAPAS1+PDAPAS2+PDAPAS3	
5	CosmicON+USMTModJ1Q1+DSMTModJ1Q4+PDAPAS1+PDAPAS2+PDAPAS3	-BEAMON
6	CosmicON+MichelAPAJ2	-BEAMON




# Detector Performance & Calibration

- **Core calibration:**  
convert  $dQ/dx$  (ADC/cm)  
to  $dE/dx$  (MeV/cm)

- ➔ Electronics calibration
- ➔ **Space charge effects**
- ➔ Electron lifetime
- ➔ Recombination effects
- ➔ Muon/Pion based calibrations

- **S/N characterization**
  - $S(\langle dE/dx \rangle) / N(\text{Ped-rms})$
  - all TPC-wire/CE-channels



**Figure 5.** Energy per unit track length deposited by the beam-induced through-going muons in ArgoNeuT, corrected for the contribution of  $\delta$ -rays. The error bars shown are statistical only. The results from a Landau-Gaussian fit (shown in red) are also reported.

## protoDUNE basic Detector performance fundamental to inform DUNE design:

- **e-lifetime** ➔ Cryogenic system stability and recirculation/purification efficiency
- $\langle dE/dx \rangle$  ➔ APA (TPC) design geometry
- $\langle dE/dx \rangle$  ➔ Field Cage (EF uniformity)
- **S/N** ➔ CE noise level and performance
- **SCE mapping** ➔ overall detector capability to provide high quality data for Physics analysis

DUNE-doc-7222-v1