



WP11: electron and proton beam testing


ARIES annual meeting, RIGA 22 - 25 May 2018

J. Schwindling / CEA Paris - Saclay

Thanks to R. Ruprecht (KIT), U. Dorda (DESY), A. Gleeson (STFC)


Goal of WP11

- Testing of instrumentation, beam optics, RF equipment, accelerator components with **low-medium energy proton and electron beams**
- 5 installations: **ANKA, FLUTE, IPHI, SINBAD, VELA**



Task	Installation	Location	Task leader	Beam periods	In operation
11.1	ANKA / KARA	KIT	marcel.schuh@kit.edu	8 periods x 2.5 days x 24 h	Since 15 years
11.2	FLUTE	KIT	marcel.schuh@kit.edu	8 periods x 5 days x 8 h	Mid 2018
11.3	IPHI	CEA Saclay	jerome.schwindling@cea.fr	12 periods x 5 days x 8 h	Since a few months
11.4	SINBAD	DESY	ulrich.dorda@desy.de	9 periods x 5 days x 14 h	Spring 2019
11.5	VELA	STFC Daresbury	anthony.gleeson@stfc.ac.uk	14 periods x 3 days x 8 h	Q4 2018

KARA, the Karlsruhe Research Accelerator of the KIT synchrotron (ANKA)



• Key parameters

- Energy range: 0.5 - 2.5 GeV
- Beam current up to 200 mA
- 500 MHz RF system
- Revolution frequency: 2.715 MHz
- Custom filling pattern
- Different optics, e.g. low- α_c (LOA)
- RMS bunch length: 50 down to few ps

• Synchrotron light users at 2.5 GeV


• R&D Topics

- Superconducting insertion devices
- Synchronized ps-fs diagnostics
- Beam dynamics and analysis

• Accelerator test facility



Beam dynamic measurements with CLIC damping ring wiggler prototype



IPAC18: THPAK029

FCC-hh vacuum chamber tests



IPAC18: MOZGBE5



Installed and commissioned SCU20



IPAC18: THPMF066




Synchronized single shot electron beam diagnostics

- Combine different detectors
- Towards time resolved phase space tomography



P. Schönfeldt et al.

SPONSORED BY THE
 Federal Ministry of Education and Research
 05K16VKA



J.L. Steinmann et al., IPAC17, MOPAB056


B. Kehrer et al., IPAC17, MOOCB1

- ARIES presentation 23/05/2018, 16:30
“Optics characterisation at ANKA including the high wiggler field”
Panagiotis Zisopoulos (CERN) present turn-by-turn data of tune and chromaticity at KARA / ANKA of July 2017
- Based on former experiments of Lille University at KARA / ANKA, Lille discuss possibilities with KIT for higher signals on EO Monitor
- Further experiments at KARA planned for the vacuum chamber of the future FCC above the plan and budget of the H2020-project EuroCirCol
- Proposals for TNA in discussion with CERN, Lille University and others

Test Facility FLUTE at KIT



- FLUTE (Ferninfrarot Linac- Und Test-Experiment)
 - Test facility for accelerator physics
 - Experiments with THz radiation
- R&D topics
 - Serve as a test bench for new beam diagnostic methods and tools
 - Develop single shot fs diagnostics
 - Synchronization on a femtosecond level
 - Systematic bunch compression and THz generation studies



Final electron energy	~ 41 MeV
Electron bunch charge	0.001 - 3 nC
Electron bunch length	1 - 300 fs
Pulse repetition rate	10 Hz
THz E-Field strength	up to 1.2 GV/m



M. Nasse et al.; Rev. Sci. Instrum. 84, 022705 (2013)

A. Malygin et al.; IPAC18, THPMF068


M. Yan et al.; IPAC18, WEPAL029

FLUTE commissioning status


- RF system operational with 5 MW
- Laser on cathode
- Gun and first diagnostics section in commissioning
- ARIES experiment chamber installed (see next slide)



First proposal in preparation: Split ring resonator experiment



- Linear mapping of the long. axis onto the transverse plane
- Temporal resolution $R_t \propto \frac{1}{fV}$
 - THz-range
⇒ high frequency f
 - Field enhancement in SRR gap
⇒ large streaking voltage V



International collaboration with the University of Bern and PSI ^{2) 3)}

²⁾ J. Fabiańska et. al., *Sci. Rep.* **4**, 5645 (2014)



³⁾ M. Yan et. al., *IPAC'16*, TUPG56 (2016)

• Status of Split Ring Resonator Experiment


- chamber installed and THz generation demonstrated
- preparing split ring resonator in progress at Bern

• Possible first TNA experiment at FLUTE


- The High Intensity Proton Injector was built and is being commissioned at CEA Saclay through a CEA – CERN – IN2P3 collaboration
- Design performances are 3 MeV – 100 mA – CW proton beam (300 kW)
- Beam restarted end 2017 after upgrade of the cooling system
- Two internal experiments at duty cycle 1E-4 beginning 2018 (see Claude Marchand's talk)



- RF conditioning will continue during summer: goal = 4% (ESS)
- Proton beam available in September for ~1 month, then installation of target / shielding for neutron production, neutron production early 2019
- Discussions with 2 potential users:
 - ESS Bilbao: tests of ESS MEBT BPMs + electronics → September
 - Jülich Forschungszentrum: tests of SoNDe detector → beg 2019




ESS Bilbao BPM



SoNDe detector

- A dedicated accelerator R&D facility currently under construction at DESY
- Reusing the old DORIS tunnel to set up multiple independent experiments
- $E = 100$ MeV, charge: 0.5 - 20 pC, bunch length: few fs, transverse norm. emittance < 0.5 mm*mrad, arrival time jitter stability < 10 fs RMS, rep-rate: < 50 Hz
- Outside TNA, SINBAD will be used to study compression methods, inject into advanced acceleration schemes, diagnostics development, ...

- Installation of gun region ongoing, linac stage installation fall 2018
- Starting detailed planning of experimental area (vacuum tank incl. movers, instrumentation, ...)
- Available for TNA: **spring 2019**
- Users
 - Advertised in talks, presentations...
 - So far only one first contact to potential interested user, hoping for more once running...




Experimental area 4.2 m

SINBAD: status



nd
2 may





nd
22 may



VELA at STFC Daresbury

- VELA = Versatile Electron Linear Accelerator
- S-Band photo-injector
- Up to 250 pC bunch charge
- 6 MeV beam energy (upgrade to 40 MeV in progress)
- 10 Hz repetition rate (upgrade to 100 Hz in progress)
- Copper photo-cathode driven by UV laser
- 1 mm profile FWHM at the cathode
- 10 MW klystron



VELA: status

- VELA has been unavailable to users, because of co-activity with the CLARA FEL testbed currently under development.
- Current Status, May 2018: **Recommissioning**
- Anticipated availability for ARIES TNA programme: September 2018
- Two groups are preparing requests submission (plasma wakefield acceleration, material testing)
- Further beamtime allocations will be available to the TNA programme in 2019.



Conclusion

- A lot of progress in installing / commissioning the facilities
 - KARA, IPHI: running
 - FLUTE, VELA: commissioning
 - SINBAD: Spring 2019
- Contacts with several groups for access within ARIES
- Hope to show ARIES results next year !

Please advertise these facilities within your institution !