

## Quality Control of the dismounting of MBHDP102 First results – De-collaring process

Ricardo de Paz Ludena




11T Dipole Task Force Meeting # - CERN – 21/02/2018

## **Programme of Disassembly of 11T DP102**

Magnet state	Step	Task	Personnel
	1	Transport from SM18 to 927.	
	2	Magnetic measurements at room temperature.	Lucio Fiscarelli
СМ	3	Strain gauges measurements.	Philippe
Civi	4	Electrical tests. Full assembly.	Francois-Olivier
	5	Removal of coils interconnection and instrumentation wires.	Hugues, Nicolas
	6	Transport to 180.	Gregory
	7	Shell cutting, disassembly of end plates, yoke and two collared coils.	Frederic's team
	8	Transport to 927 of 2 collared apertures.	Frederic's team
СС	9	Electrical tests. Collared coils.	Francois-Olivier
	10	Geometrical measurements of collared coils.	Salvador
	11	Strain gauges measurements.	Philippe
	12	Decollaring.	Nicolas, Ricardo and Philippe
	13	Visual inspection.	Hugues, Nicolas, Ricardo
	14	Geometrical measurements of the coils.	Salvador
Coils	15	Electrical tests. Coils.	Francois-Olivier
	16	Collars geometrical measurements on larger and smaller coil size contact areas.	Salvador
	17	Some coils will be cut to check the degraded areas (broken filaments).	



## Magnetic Measurements: Cold mass Before / After cold tests



No significant variations Before / After cold test.



Courtesy of L. Fiscarelli

## Magnetic Measurements: Cold mass Before / After cold tests

<b>SP104b</b> Average (- 520, 520 mm)							SP1	.05b	Ave	erage (- mm	520, 52 າ)	0		
	CM before	CT (units)	CM after	CT (units)	∆ (u	nits)			CM be	fore CT	CM af	ter CT	Δ (u	nits)
n	bn	an	bn	an	bn	an	I	n	bn	an	bn	an	bn	an
2	1.42	4.88	1.50	4.89	0.08	0.01	:	2	-1.38	4.20	-1.08	3.90	0.30	-0.30
3	7.60	-0.20	7.37	-0.26	-0.23	-0.06	:	3	3.49	-0.81	3.30	-0.73	-0.19	0.08
4	0.14	-0.58	0.07	-0.58	-0.07	0.00	4	4	-0.39	0.75	-0.29	0.68	0.10	-0.07
5	2.06	-0.01	1.97	-0.01	-0.09	0.00	!	5	0.89	-0.69	0.85	-0.64	-0.04	0.05
6	0.01	0.03	0.01	-0.03	0.00	-0.06		6	0.07	0.71	0.07	0.69	0.00	-0.03

#### No significant variations Before / After cold test.



Courtesy of L. Fiscarelli

## **Electrical Tests. VT and Insulation**

SP104b	Tes	st name	BC2	AC2	After Yoke Disassembl ed	After Decollaring	
Insulation resistance	U[test]	time	measured	measured	measured	measured	nominal
Insulation resistance	[V]	[s]	[GΩ]	[GΩ]	[GΩ]	[GΩ]	[GΩ]
coils + QHs> ground	1000	30	44.80	2.59	68.20	Х	>1
coils> all QHs	1000	30	6.86	4.66	4.44	Х	>1
coils> ground	1000	30	55.10	3.27	55.70	х	>1
coil109> QHs109	1000	30	18.00	8.46	7.73	20.80	>1
coil112> QHs112	1000	30	17.40	15.60	13.95	16.30	>1
coil109> coil112	1000	30	77.20	6.20	8.87	x	>1
coil109> Loading plate	1000	30	Х	Х	Х	0.73	>1
coil112> Loading plate	1000	30	Х	Х	Х	Brd 957V	>1

- Insulation test 1000 V

-

After-decollaring measurements being run today on SP105b coils.

- Insulation SP104b coils to Loading plate, NOT GOOD.
- CM to CC, we lost 4 VT in SP105b: EE11506, EE11505, EE11405, EE11406
- CC to Coils, RECOVERED. And we have lost EE115I4 and EE115O12

SP105b	Test name		BC2	AC2	After Yoke Disassembl ed	
Insulation resistance	U[test]	time	measured	measured	measured	nominal
Insulation resistance	[V]	[s]	[GΩ]	[GΩ]	[GΩ]	[GΩ]
coils + QHs> ground	1000	30	6.75	37.70	25.60	>1
coils> all QHs	1000	30	3.70	3.91	4.51	>1
coils> ground	1000	30	6.80	84.00	34.10	>1
coil114> QHs114	1000	30	11.80	8.20	9.28	>1
coil115> QHs115	1000	30	11.00	11.20	13.43	>1
coil114> coil115	1000	30	61.00	47.30	13.41	>1
coil114> Loading plate	1000	30	Х	Х	Х	>1
coil115> Loading plate	1000	30	Х	Х	х	>1

#### Courtesy of F.O Pincot

### **Electrical Tests. Coil discharge**

SP105b

#### SP104b


Test nan	ne	BC2	AC2	After Yoke Disassemble d	After Decollaring
Time const	<b>-</b> T	T Measured	T Measured	T Measured	T Measured
Time consta	Time constant T		[µs]	[µs]	[µs]
	0.5kV	ОК	ОК	ОК	ОК
coil 109	0.75k V	ОК	ОК	ОК	ОК
	1.0kV	ОК	ОК	ОК	ОК
	0.5kV	ОК	ОК	ОК	ОК
coil 112	0.75k V	ОК	ОК	ОК	ОК
	1.0kV	ОК	ОК	ОК	ОК

Test nam	e	BC2	AC2	After Yoke Disassembled
Time a second	at T	T Measured	T Measured	T Measured
Time constant T		[µs]	[µs]	[µs]
	0.5kV	ОК	ОК	ОК
coil 114	0.75kV	ОК	ОК	ОК
	1.0kV	ОК	ОК	ОК
	0.5kV	ОК	ОК	ОК
coil 115	0.75kV	ОК	ОК	ОК
	1.0kV	ОК	ОК	ОК


- Coil discharge up to 1000 V done, everything OK
- After-decollaring measurements still to be performed on SP105b coils



### **Geometrical measurements CC**



## **Strain Gauges measurements. Welding – Unwelding variations**





Courtesy of P. Grosclaude



### **Strain Gauges measurements. Decollaring**

- Shim between stoppers: 0.15 mm
- Removal of the keys ≈ 8 MN







## **Conclusions**

- Electrical, Mechanical, Geometrical and Magnetic measurements have been performed at the different disassembly states of DP102: CM → CC → Coils

- Magnetic measurements apparently ok.
- Electrical: insulation and discharge are ok. Some VT out of service.
- Geometrical: analysis and coil measurements ongoing.

- Decollaring: shim 0.15 mm between stoppers (enough clearance for keys insertion) with 8 MN.

- **Decollaring:** above ≈ 10 MN (it depends on the coils size), the tooling is already closed and the extra force **could POSSIBLY be** share half and half between CC and Tooling.

- Current state: electrical and geometrical measurements of the four coils 109, 112, 114 and 115.






# **THANKS FOR YOU ATTENTION**



## **Extra slides**





## **Extra slides**

