



CLIQ and Quench Heaters performance in MQXFAP1

Vittorio Marinozzi – Fermilab

With many contributions by E. Ravaioli - CERN


2nd International Magnet Test Stand Workshop – May 8-9, 2018, BNL




Outline

- MQXFAP1 quench protection system
- Heaters performance
- CLIQ performance
- Conclusions


MQXFAP1 Protection system




MQXFAP1 Protection system




- Dump resistor: 37.5 mΩ
- OL heaters: 16 strips (HF and LF per each half coil)
- IL heaters: 8 strips (one per half coil)
- CLIQ: 40 mF, 500 V



MQXFAP1 Protection system



MQXFAP1 Protection system




Assumptions for simulations:

- Simulation software: LEDET
- 2D thermal model for the quench heaters
- Disconnected heaters not fired
- Coil 3 OL heaters at 25 % of nominal power (no Heating Stations)
- Measured RRR for each coil
- Measured J_c for each coil
- Protection parameters as at BNL facility
 - Validation time: 4 ms
 - Voltage threshold: 150 mV (at high current >8000 A)
 - Switch opening time: <1 ms

Quench Heaters performance

MQXFAP1 - Quench 12 (~16.7 kA) – Current decay



- Detection time: ~6.5 ms
- Validation time: 4 ms
- Switch delay time: ~1 ms
- Voltage threshold: 150 mV
- MIITs: 29.5
- HST: **275 K**


CLIQ performance

CLIQ commissioning tests


Test #	Magnet current [kA]	CLIQ charging voltage [V]	OL-H	IL-H	EE	Trigger
1	0	50	No	No	Yes	Manual
2	0	50	No	No	Yes	Manual
3	0	100	No	No	Yes	Manual
4	0	100	No	No	Yes	Manual
5	2	100	No	No	Yes	Manual
6	2	500	No	No	Yes	Manual
7	5	500	No	No	Yes	Manual
8	~16.7	500	Yes	Yes	Yes	Quench

CLIQ performance

Clmq commisioning second test
100 V, 40 mF




Clmq commisioning second test
100 V, 40 mF




CLIQ performance

MQXFAP1 – CLIQ commissioning, 2 kA, 100 V




Good agreement

MQXFAP1 – CLIQ commissioning, 2 kA, 100 V




CLIQ performance

MQXFAP1 – CLIQ commissioning, 5 kA, 500 V




MQXFAP1 – CLIQ commissioning, 5 kA, 500 V



Good agreement


CLIQ performance



- Detection time: ~6.5 ms
- Validation time: 4 ms
- Switch delay time: ~1 ms
- Voltage threshold: 150 mV
- MIITs: 25.2
- HST: **220 K**

CLIQ performance


2018-02-15-1501 - Sim #2185



- Total voltage shows a nice agreement
- Coil 4 and coil 5 voltages show a general agreement
- Coil 2 and 3 show some disagreement
- Difficult to have more details due to voltage taps signal saturation

CLIQ performance


MQXFAP1 – Comparison quench 12 / Quench 14
(~16.7 kA) – Experimental measurement



- MIITs/T quench 12:
29.5 MA²s / 275 K
- MIITs quench 14:
25.1 MA²s / 220 K


Using CLIQ reduces MIITs of
~15 %

CLIQ performance




- MIITs/T quench 14:
25.1 MA²s / 220 K
- MIITs/T quench 15:
25.4 MA²s / 225 K

CLIQ performance



CLIQ performance




- Sim MIITs:
27.85 MA²s
- Exp MIITs:
25.4 MA²s

CLIQ performance

- Quench 15, 16, 17 and 18 were performed using CLIQ, dump resistor, OL quench heaters, and no IL quench heaters
- Results are similar to what shown before
 - Good agreement btw measured current decay and simulations
 - MIITs are almost independent on the presence of IL quench heaters
- After quench 18, due to a short to ground, the test campaign was stopped

CLIQ performance



CLIQ performance

- Comparison of experimental and measured MIITs in all quenches with CLIQ

Quench	Current [A]	MIITs (simulated)	MIITs (measured)
14	16693	27	25.1
15	17167	27.85	25.4
16	17262	27.9	25.45
17	17326	27.95	25.49
18	17426	28.0	25.55

Conclusions


- Since CLIQ was commissioned during the MQXFAP1 test campaign, IL quench heaters were used until CLIQ reliability was demonstrated in quench 14
- The 37.5 m Ω dump resistor always present to extract some energy
- Therefore the lay-outs were:
 - IL quench heaters + OL quench heaters + dump (first 13 quenches)
 - CLIQ + OL quench heaters + dump (last 4 quenches)
 - Quench 14 has been performed with dump, OL heaters, IL heaters and CLIQ for the commissioning of CLIQ
- The reliability of simulations has been validated on experimental measurements
- The protection with EE, CLIQ and OL heaters shows a decrease of the MIITs of ~15 % respect to EE, IL and OL heaters
- The presence of dump resistor increases the efficiency of the protection system (in particular of CLIQ).
 - EE extract ~20 % of the stored energy (LEDET simulation).
- Based on simulations validated during this test, the maximum temperature of the magnet in nominal scenario is: 250 K @ I_{op}

Backup slides




Backup slides

2018-02-15-1501 - Sim #2189



Backup slides

2018-02-13-2015 - Sim #2190



With QH on C003,
50% Jc degradation
in C003

Backup slides

