

## Objectives for LHC compatible BGC instrument (v3)

G. Schneider



## Content

2

- Framework of the project
- Performance objectives for v3
- Vacuum considerations
- Dimensions
- Planning
- Interfaces and Installation considerations
- Infrastructure
- Summary

#### BE Beams Department

## Framework of the project

3

- The CERN internal PLAN reservation made in 2015 as Activity 10834
- Engineering Change Request (ECR) for the installation of BGC demonstrator instrument is about to be send out for check
  - $\rightarrow$  Staged approach, further ECRs will follow until the installation
  - → Location of Hollow Electron Lens (HEL) vacuum sector, what is today B5L4.B, will be split
  - $\rightarrow$  Cable requests for BGC are made
- Our collaboration includes the design and production of a second gasjet monitor (v3) by Cockcroft/Liverpool for installation in the LHC, with the following milestones:

*"Design report for a final gas-jet for the LHC"* : Report, June 2018 *"Full prototype adapted for testing in the LHC"* : Hardware, June 2019



## Performance objectives for v3

4

- Fully operational optical system, adopted for both proton and electron beam
- Gas curtain traversing LHC beam in a defined way
  - Quantity and Density
  - Position
  - Shape
- LHC Beam compatible (Vacuum, Impedance, Aperture, Alignment, Safety ...)
- Useful integration time



## Vacuum Sectorisation to be made in LS2

5

Additional gate valve BGC **/AIHB** LIU Vacuum Sector today: B5L4.B

#### **Courtesy: Pablo Santos Diaz**

## Vacuum Considerations

6

Amount of gas injected, based on Cockcroft design:


Pressure in Nozzle chamber: 1x10<sup>-3</sup> mbar, using 100 l/s pump → gas flow of 1x10<sup>-1</sup> mbar.l/s Use for 1 year run assuming 200 days continuous: 1x10<sup>-1</sup> mbar.l/s x 3600 s x 24 h x 200 d = 1728 bar/l Consider 50 l gas bottle at 200 bars → 10000 bar/l → will last 5 years

 $\rightarrow$  Will need positive replacement pump on Nozzle chamber  $\rightarrow$  Turbo Pump

Pressure between skimmer  $1-2 \rightarrow 10^{-5}$  mbar using 100 l/s pump  $\rightarrow 10^{-3}$  mbar.l/s Pressure between skimmer  $2-3 \rightarrow 10^{-6}$  mbar using 100 l/s pump  $\rightarrow 10^{-4}$  mbar.l/s Pressure interaction chamber  $\rightarrow 10^{-8}$  mbar using 100 l/s pump  $\rightarrow 10^{-6}$  mbar.l/s



# BGC dimensions must be optimised from laboratory set-up to machine instrument



## Performance/Space optimisation

8


- Optimisation on high pressure side (Nozzle side)
- Optimisation on the skimmer side → where to place which skimmer?
- Optimisation on the pumping side → where to place the pumps and which type of pump?
- → The aim is to make the instrument more compact while reducing the integration time

## Planning: Machine installation 1

9

#### **Milestone Dates**

- 2018 October : Agreed design
  - Blackening and coatings
  - Impedance
  - Gas type
  - Pumps
  - Optics
  - Skimmer dimensions an locations
  - Mechanical design of chambers
  - Safety considerations for machine and personnel:
    - 10 bar gas, operation of pumps on beam vacuum system, injection of gas



## Planning: Machine installation 2

10

#### **Milestone Dates**


- 2019

February: All manufacturing drawings signed, start price inquiries April: Order all components and chambers October: All cables installed in tunnel, all parts received

#### - 2020

January: BGC set-up running in laboratory environment March: Installation in the tunnel finished June: Commission in tunnel done.

#### → Not much contingency!!!!!!



### BE Beams Department

## Interfaces and Installation Considerations


11

- Impedance: To be presented and accepted by the impedance working group
- Geometers: Assure that alignment of the interaction chamber is possible
- Vacuum: Agree on injection and pumping
- Blackening of the chamber: Agree on vacuum acceptable blackening with good light absorption.
- Safety: Assure no hazard to persons Assure for a save LHC operation

## Infrastructure

12

- Installation of 10 bar gas line from a gas bottle?
- Is a gas purification system needed?
- Operation of the vacuum system from the racks in UL44
- Installation of supports
- Pull cables
- Installation of Rack in UL44




**BE** Beams Department

19.03.2018



## BGC Vacuum Chamber

13



## **BGC Vacuum Chamber**

14

8-way cross vacuum chamber

**Beams Department** 

**Copper liner with:** 

- Pumping hole pattern and holes for gas jet and optical system, to be agreed with Impedance WG


- NEG coating
- Based on VAX design

19.03.2018

## Summary


15

- Preparations for installation of a BGC demonstrator instrument during LS2 have started
- Many issues on the technical side to be addressed in a short timeframe
  Further good collaboration essential for success
- **Production review foreseen in October 2018.**
- All parts should be available October 2019
- Assembled operational system in laboratory environment January 2020
- Installed in Point 4 LHC: March 2020



## **BGC** Demonstrator installed

17



**Beams Department** 

BE




# BGC Demonstrator installed, view from Beam 1.

18

3 UHV all metal gate valve with pinch-off will allow for extensions to the BGC without breaking the beam vacuum.

## **Racks-Location**


#### Option 1: UA43 & UL44 (P4L) / UA47 & UL46 (P4R)



Courtesy: Maria Amparo Gonzalez De La Aleja Cabana


## **Beam-Gas Curtain: Instrument Components**

Note: This shows an integration of a laboratory prototype (v2), NOT an instrument designed for the LHC





## BGC (laboratory, version 2) integrated in LSS4 with a candidate e-lens solenoid





Fluorescence Monitor Installation

22



Slide from T.Dodington shown in BGC project meeting of 20/12/17 https://indico.cern.ch/event/686987/ [see also presentation from S.Mazzoni in same meeting]