

Low Radioactivity Techniques 2019, Jaca, Spain

A New Low-Background Facility in China Jinping underground Lab

Zhi Zeng

Tsinghua University

2019-05-20

Outline

- I. CJPL Current status**
- II. DURF in CJPL-II**
- III. summary**




I. CJPL Current status

CJPL Location




Jinping-I
Hydroelectric
Power Plant

Jinping-II
Hydroelectric
Power Plant





~17km JinPing tunnel

Tunnel Layout



Layout of CJPL-I



- Total space: 4000 m³
- Main Lab Space: 6.5(W) x 6.5(H) x 42(L)

Current Status of CJPL-I



CDEX experiment



PandaX



Jinping neutrino



Low-background gamma spectrometer

☐ Physics experiments:

- 2 dark matter experiments: **CDEX, PandaX**
- 1 neutrino experiment: **Jinping Neutrino experiment**

☐ Low background counting facilities:

- 3 low-background gamma spectrometers

Low-background gamma spectrometer

GeTHU, low background gamma spectrometers in CJPL-I, designed for material screening for dark matter experiment..



CJPL-I low background facility



GeTHU-I




GeTHU-II



GeTHU-III

Layout of CJPL-II



CJPL-II construction and current status





II. DURF in CJPL-II

DURF introduction

- Deep Underground and ultra-low Radiation background Facility for frontier physics experiments(**DURF**) is one of the 10 prior projects of *National Major Science & Technology infrastructure*.
- CJPL-II was selected to build DURF, and the proposal approved in the Dec.13 , 2018, ~177 million euros.
- DURF would involve:
 - Three Shielding devices for different experiment
 - Low background counting facilities
 - Ultra pure copper production devices
 - Crystal growth and process




Hall






Service tunnel

DURF in CJPL-II



A large water shielding vessel




Prepare for LXe/LAr experiments shielding:

- Size: L27m*W15m*D13m
- Volume: 4500m³ pure water
- Gamma background: 10⁻⁵ cpkkd@2MeV

Large Water shielding vessel in B2 Hall


A large liquid nitrogen shielding vessel



Prepare for HPGe experiments in C1 hall:

- Vessel Size: ϕ 16.4m*H20m(outer), ϕ 13m*H13m(inner)
- Volume: 1725m³ liquid nitrogen
- Gamma background: 10⁻⁸ cpkkd@1-3keV.
- The Liquid Nitrogen tank is now constructing.




A Polythene Shielding Room



Prepare for demo/prototype experiment and Low background facility in C2 hall:

- Room size: L38m*W6m*H4m(inside),
- Radon reduction Air input
- Additional lead, OFHC copper could be used inside the PE room.

Low Background Facility




One HPGe Array:

- 5 ULB-HPGe detectors
- OFHC copper, lead shielding;
- MDA: $\sim 10\mu\text{Bq/kg}$

15 HPGe Spectrometer:

- 10 coaxial p-type
- 2 coaxial n-type
- 2 well-type
- 1 ultra-low energy
- OFHC copper, lead shielding;
- MDA: $\sim 1.0\text{ mBq/kg}$

Low Background Facility



Include some additional instruments:

- 2 alpha ultra-low background counting devices
 - Detection efficiency: >90%
 - Background counts rate: < 0.0001 alphas/cm²/h
- 2 liquid scintillator spectrometer
- 2 high resolution ICP-MS

Timetable

总进度计划表(一级)						十三五国家重大科技基础设施极深地下极低辐射本底建设项目																														
						2017年				2018年				2019年				2020年				2021年				2022年										
						一季	二季	三季	四季	一季	二季	三季	四季	一季	二季	三季	四季	一季	二季	三季	四季	一季	二季	三季	四季	一季	二季	三季	四季	一季	二季	三季	四季			
序号	项目名称	计划开始 年月	计划完成 年月	实际开始 年月	实际完成 年月	完成 %	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下	上	下		
1	项目意向	2017.2	2017.6	2017.2	2017.6	100	■	■																												
2	项目策划	2017.3	2017.5	2017.3	2017.5	100	■	■																												
3	委托咨询	2017.5	2017.6	2017.5	2017.6	100		■	■																											
4	初步可行性研究	2017.3	2017.6	2017.3	2017.6	100	■	■																												
5	建议书编制	2017.6	2017.9	2017.6	2017.9	100			■	■																										
6	建议书审批	2017.9	2017.10	2017.9	2017.10	100				■																										
7	可行性研究报告编制	2017.10	2018.4	2017.10	2018.4	100				■	■	■	■																							
8	可行性研究报告审批	2018.4	2018.6	2018.4						■	■																									
9	项目评估(消防、环评等)	2017.6	2018.4						■	■	■	■																								
10	委托设计	2018.6	2018.7								■																									
11	初步设计	2018.7	2018.10								■	■	■	■																						
12	地下部分施工图设计	2018.10	2019.6								■	■	■	■	■	■																				
13	地上部分施工图设计	2019.1	2019.6								■	■	■	■																						
14	建设准备	2018.7	2018.12								■	■	■	■																						
15	委托监理	2018.7	2018.10								■	■	■	■																						
16	施工招标、签订合同	2018.10	2019.6								■	■	■	■	■	■																				
17	设备、物资采购招标	2019.1	2019.12								■	■	■	■	■	■																				
18	建筑公用工程施工(详见工程施工进度表)	2019.1	2021.6								■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■	■
19	实验设备设计、安装、调试	2019.7	2022.9																																	
20	各系统调试、联合调试	2021.6	2022.10																																	
21	具备竣工验收条件	2022.6	2022.12																																	
22	资料归档	2022.6	2022.12																																	

Aug. 2019, preliminary design completed;
 Dec. 2019, engineering project bidding;
 Jun. 2021, civil engineering completed;
 Sep. 2022. Shielding projects completed;
 Dec. 2022, Project completed.

III. Summary

- A new low-background facility, DURF, would be constructed in CJPL-II since 2019.
- DURF can provide three different shielding conditions for DM/0vbb experiments.
- Some ultra-low background counting devices would be equipped in DURF project and could be used for material screening, sample measurements.

严禁携带易燃易爆、有毒有害
禁止行人、非机动车通行

锦屏山水电
JINPING HYDRO

中国锦屏地下实验室
CJPL

锦屏山隧道

锦屏山水电
JINPING HYDRO

锦屏山隧道

锦屏山隧道
长17.5km

请勿疲劳
驾驶!

预防为主 综合治理
锦屏水力发电厂宣

30

禁止行人、非机动车、牲畜、摩托车进入

限速30KM、严禁超车、禁止行人、牲畜、摩托车进入

辅助洞施工交通管制公告牌

开始时间	2017年6月12日	结束时间	2017年7月21日
材料名称	全洞封闭		
管制时间	每日上午 8:00-12:00		
管制地点	锦屏山隧道		
管制原因	因施工需要，进行全洞封闭施工		
其他说明	1. 施工期间，隧道内禁止通行。 2. 施工期间，隧道内禁止停放车辆。 3. 施工期间，隧道内禁止堆放材料。 4. 施工期间，隧道内禁止进行其他任何作业。		

江苏南工科技集团有限公司

Welcome to Jinping!