



Tellurium Purification and Deployment in SNO+

Szymon Manecki, SNOLAB Research Scientist,
LRT, May 20th, 2019

Introduction




Introduction



SNO+ Collaboration, Phys. Rev. D 99, 012012 (2019)
SNO+ Collaboration, Phys. Rev. D 99, 032008 (2019)

SNO+ Physics Goals

- Neutrinoless Double Beta Decay




- Low Energy Solar Neutrinos



- Reactor Antineutrinos




- Geo-Neutrinos



- Supernova- ν




Introduction




$\nu\bar{\nu}\beta\beta$ Search Requirements

- Low backgrounds
- Good energy resolution
- Large amounts of isotope




Introduction






$0\nu\beta\beta$ Search Requirements

- Low backgrounds
- Good energy resolution
- Large amounts of isotope




Te Scintillator

- 780 T Linear Alkylbenzene (LAB)
+ 2 g/L PPO (Primary Fluor)
+ 15 mg/L bisMSB (WS)
- Tellurium Butanediol (TeDiol)
0.5% Te in LAB
- DDA (stabilizing amine)
0.4% in LAB



Te Scintillator


- LAB-soluble TeDiol complexes are formed in condensation and further oligomerization reactions of Telluric Acid with 1,2-Butanediol



- TeA purification
 - In the next slides
- 1,2-Butanediol distillation
 - Ref. LRT 2017 (Sz.Manecki)
- DDA purification
 - U/Th target at $\sim 10^{-15}$ g/g (expected reduction factor of 1000 from the assayed level has been easily reached with spiked distillation)
 - Expected reduction factors for Co/Na have been achieved, but clean handling post-distillation is going to be important

Te Scintillator

- LAB-soluble TeDiol complexes are formed in condensation and further oligomerization reactions of Telluric Acid with 1,2-Butanediol



- TeA purification

- The target 8 tonnes of TeA have already been cooling down underground (50% for > 2 years and 50% for < 2 years)



TeA Purification


- The purification technique relies on solubility of TeA in water based on pH
 - $\text{Te(OH)}_6 \rightleftharpoons \text{Te(OH)}_5\text{O}^- + \text{H}^+$

in-soluble
soluble
- Insoluble contamination
 - Dissolve in water, and filter
- Soluble contamination
 - Force TeA to recrystallize by adding Nitric Acid, let it precipitate out, and drain the “dirty” liquid

Isotope	$t_{exp}=1$ yr
²² Na	15309
²⁶ Al	0.048
⁴² K	565
⁴⁴ Sc	102
⁴⁶ Sc	43568
⁵⁶ Co	2629
⁵⁸ Co	25194
⁶⁰ Co	6906
⁶⁸ Ga	37343
⁸² Rb	18047
⁸⁴ Rb	11850
⁸⁸ Y	390620
⁹⁰ Y	823
¹⁰² Rh	276189
^{102m} Rh	133848
¹⁰⁶ Rh	1534
^{110m} Ag	69643
¹¹⁰ Ag	939
¹²⁴ Sb	3101138
^{126m} Sb	240
¹²⁶ Sb	358996




10kg pilot-scale




Target (r.f. 10³):
²³⁸U: 1.3x10⁻¹⁵ g/g
²³²Th: 5x10⁻¹⁶g/g

Needed reduction for cosmogenics by:
 10⁵-10⁶


TeA Plant Isometric Layout



Target 200 kg TeA / batch
~50 "working" days to purify 8 tonnes




TeA Plant Flow Diagram



TeA Fabrication & Cleaning

- All wet process lines and vessels constructed with plastic to suppress metals leaching
 - Polypropylene vessels designed and delivered by SeaStar
 - On-site contractors trained in clean PFA piping installation



TeA Fabrication & Cleaning

- SeaStar process vessel leaching (with warm acid solution)



Results from ICP-MS assay of leachate (ppt)

	Soak 1 (2 days)		Soak 2 (4 days)		Soak 3 (4 days)	
	RXT	TRXT	RXT	TRXT	RXT	TRXT
U	1	0.2	<0.05	<0.05	<0.05	<0.05
Th	5	1	1.1	<0.1	<0.1	<0.1
Ca	2700	2000	380	180	<20	<20
Fe	5600	5000	220	170	17	37

Compare: goal of 0.1 ppt U and <0.05ppt Th in purified TeA.
Other measured metals (relevant for cosmogenics) lower than Ca and Fe, <0.1 ppb goal.

Vessels meet our purity requirements!

Further cleaning/leaching with nitric acid after installation will provide additional safety factor.

TeA Plant Construction

Dec-2016



2017



2018



Jan-2019


COMPLETED




TeA Plant Outlook & Schedule

- The most critical components of the plant have been commissioned
 - Vacuum and process pumps, blowers, fans agitators and instrumentation
 - Process controls and operations programming is in an advanced stage
- Commissioning/cleaning with Nitric Acid
 - Summer, 2019
- Plant ready for Operation
 - Fall, 2019

TeDiol Plant Isometric Layout





TeDiol Plant Flow Diagram



TeDiol Fabrication & Cleaning

- PFA (PerFluoroAlkoxy) lined FRP (fiberglass-reinforced polymer) tanks for main process vessels
 - Flash chamber, batch tank & product tank
- PFA in-line heater
- PFA condenser
- PFA Centrifugal Pumps
- Nitrogen sparging system
- Stainless steel condensate tank



TeDiol Plant Construction

Feb-2018



May-2019





TeDiol Outlook & Schedule

- The construction of the plant has been completed
 - Only minor tasks remain (heat insulation, labeling, filters etc)
 - Commissioning of the equipment has been initiated
- Acid cleaning & commissioning
 - Summer, 2019
- Plant ready for Operation
 - Fall, 2019



SNO+ Te Phase

- With 0.5% Te loading
 - $T_{1/2}^{0\nu} > 2.1 \times 10^{26}$ yrs
 - $m_{\beta\beta} > 45$ meV_(IBM-2)



SNO+ Te Phase

- With 0.5% Te loading
 - $T_{1/2}^{0\nu} > 2.1 \times 10^{26}$ yrs
 - $m_{\beta\beta} > 45$ meV_(IBM-2)



Thank You

