

AD Machine and Experimental Areas – Operation and major problems in 2006, outlook for 2007



Contents

- AD restart and related problems
- The 2006 physics run
- What's in store for 2007?
- Consolidation



AD startup after 18 months....

Extremely difficult startup:

- PS-complex schedule delayed 6 weeks due to PS rotor (©)
- 3 weeks planned for AD startup needed 8 weeks!! 🙁
 - Problems in setting up electron cooler (19 days) ☺
 - PS injection septum failure (6 days) 😕
 - CERN general power distribution failure (4 days) 🙈
 - Difficulties in finding correct trajectory for ALPHA line (8 days) 🙈
- Physics finally started 22/8 instead of 18/7(all beamlines ok)
- ...but with lower rep. rate and somewhat lower intensity 🙈




Startup: Electron cooling difficulties

- Many,many problems during the PS repair (power converters, ctrls etc.)
- First beam on target 28/6 1 week to decelerate to low energies and discover e-cooling problems
- 50% of the 19 "cooling days" spent on cooler itself. 50% on other issues (ctrls, network, OASIS, supplies etc.) inefficient!
- Problems w. unstable residual collector voltage (cooling circuit?)
- Cathode stability verified after improvements in voltage divider
- When stable, momentum cooling rate much reduced in spite of much work on alignment, coupling compensation etc.
- Limited cooler diagnostics
- Problem "fixed" by drastically increasing cooling duration (+10s @ 300 MeV/c, +5s @ 100 MeV/c)



H and V beam profiles at 100 MeV/c




ATC/ABOC 2007

T. Eriksson CERN AB/OP



• "2006 cycle":

- Now 100s (86s in 2004)
- Final emittances ok for reasonable deceleration and xfer efficiency
- Rep.ratesuffers alsofrom longerPS-supercycles




ATC/ABOC 2007

T. Eriksson CERN AB/OP



Beam passes through strayfields of both ATRAP solenoids

Startup: ALPHA beamline



ATC/ABOC 2007

T. Eriksson CERN AB/OP



Startup: ALPHA beamline

- New DE0.DHZ87 successfully commissioned with ATRAP2 solenoid @ 3T.
- Shortly after, transmission = 0.....??!! (solenoid off)
- Found (much later...) that despite normal beam on 5 downstream MWPC:s, a trajectory change through the septum caused the losses
- New MWPC will be installed in the sensitive region during this shutdown



The 2006 run

•All beamlines operational as of 22/8 (5weeks late): Run extended until 20/11 to compensate

Run time (h)	2000	2001	2002	2003	2004	2006
Total	3600	3050	2800	2800	3400	2925
Physics	1550	2250	2100	2300	3090	2765
md	2050	800	700	500	310	160
uptime	86%	89%	90%	90%	71%	65%


ATC/ABOC 2007



The 2006 run

• Typical performance

Np (3.5 GeV/c)	3.31 e7 100 %
Np (2 GeV/c)	3.26 e7 98 %
Np (300 MeV/c)	2.8 e7 84 %
Np (100 MeV/c ramp)	2.92 e7 88 %
Np (100 MeV/c end)	2.72 e7 82 %
DETFA7049	2.39 e7 72 %
dp/p (3.5 GeV/c)	33.113 0.976
dp/p(2GeV/c)	1.317 0.231
dp/p (300MeV/c)	1.33 0.048
dp/p (100 MeV/c)	0.433 0



ATC/ABOC 2007



The 2006 run

- Increased losses
 PS AD target
- Increased deceleration losses
- Slower beam cooling at low energies
- Higher long. emittance


S	Parameter (at extraction)	Design	Achieved 2004				Achieved 2006		
		100 MeV/c	100 MeV/c	300 MeV/c	100MeV/c, multiej.		100 MeV/c	500 MeV/c	100MeV/c multiej.
•	Total energy spread [4s] [10 ⁻³]	1 – 0.1	0.8 – 0.4	0.15			>1	2	>1
	Bunch length [ns]	200- 500	90-200	300			120- 500	500	50
•	Number of antiprotons [107]	1.2	3.0/4.2	3.3/4.0	1.0*3	0.4*6	2.5	3.0	0.4*6
	Cycle time [s]	60	84	84	89	96	100	95	112

ATC/ABOC 2007



The 2006 run: ASACUSA

• Several subgroups including RFQD and multiejection (ej. at 2.4s interval on h=6)





The 2006 run: ATRAP

- Commissioning of new zone (ATRAP2); new e+ source →
- New trap with large-bore 3T superconducting solenoid (several quenches)
- Some handling problems with the new source
- New dipole corrects well for strayfield disturbance, but complications can arise when coupled with AD orbit trajectory drift





The 2006 run: ALPHA

• Commissioning of new trap ultimately aimed at trapping Hbars



The 2006 run: ACE

- Cell irradiation with 500MeV/c beam:
- Plans for AD cycle w. ecooling at 300MeV/c and then acceleration for ejection at 500MeV/c abandoned.....
- Extended s-cooling at 2GeV/c
- Eh,Ev = 8pi, lbunch = 500ns
- Some modifications to ej. line supplies
- 1 week exclusive run (including final setting-up)



ATC/ABOC 2007

T. Eriksson CERN AB/OP



2007 - shutdown work

• E-cooler:

- Renovation of collector cooling system: improve water quality (conductivity); attempt to solve stability problems
- Verification of all collector HW
- 2005 NEG improvement was successful, BUT we are running with one less Ion pump (feedthrough broken)

• "New" MWPC in DE0-line:

- To simplify ALPHA line setup
- Mech. design done w. upstream move of 2 quadrupoles
- Optics consequences checked: hope for improvements...



2007 - shutdown work

- Shielding of DE1.STP26/DE1.MWPC42: under study
- New experimental area access system
- ACE: Alignment of DEM-line
- ASACUSA:
 - 1 New Ion pump + refurbish 1 existing
 - Turbo pumps: last spare used, no longer supported (CERN-wide problem). To be discussed
 - RF buncher removal (end March?)
- ALPHA: Re-arrangement of zone. (+ general alignment/vacuum, not yet defined)
- ATRAP: (General services only, not yet defined)



2007 - shutdown work

- Safety issues:
 - Modification of platform near D305 (after crane accident)
 - New ATRAP e+ source: much overhead work
 - Condition of catwalks
 - Barracks/workshops...



2007 (and beyond) requests

- ACE: awaiting request
- ASACUSA: awaiting subgroup schedule (for support planning)
- PAX: Initial feasibility study for proposed experiment underway.Internal target tests soon?



2007 startup

- Extra HW-test time requested by AB/PO: 4 weeks in total
- Start with production beam 7/5
- 4 weeks for startup/md
 - Thorough study of e- vs. Pbar alignment for e-cooling
 - Set-up of new optics in DE0, DE3/4, DE2
- No plans for tst protons, but it might be needed
- And:
 - Study of PS to AD line optics desirable
 - − 5-bunch production beam − is it far away?????

ATC/ABOC 2007



2007 startup

- Physics run: 4/6 22/10
- Plan to continue running during weekends
- AD operation:
 - 2 shifts/day during startup, then:
 - 1 specialist on-call/week
 - 1 backup/week
 - ccc looks after AD during nights/weekends
- The same team also runs LEIR

ATC/ABOC 2007



CCC

- Running AD from ccc reinforces the need for:
- *Improved machine stability =*
 - Electron cooler stability/performance
 - Need improved correction of ecool trajectories
- Better tools for ejection beamline tuning =
 - Need new monitors for fast, non-destructive measurements and corrections



AD Consolidation

- AD is now included in the general consolidation program....
-at the bottom of the list....
- Let's look at only RS...and see what can be done

Item	RS	Material budget 2007-2010 kCHF	Staff requirements 2007-2010 MY
C10/C02 Cavity upgrade	12	380	3.3
Stochastic cooling Pickup/kicker movement	12	150	1.0
Horn pulser ignitron phaseout	9	230	0.35
Stochastic cooling controls/instrumentation	8	200	2.0
Horn pulser electronics	6	175	1.30
Ej.line trajectory instrumentation		300	0.6
(RF low level migration to DSP)		150	1.0

ATC/ABOC 2007



Conclusion General remarks

- AD downtime is increasing
- e-cooler is getting more and more difficult to set-up correctly
- Some equipment (eg. target area) has been operational for a very long time without intervention: know-how is disappearing
- Keen interest from users