First Cool-down in SPS

- First frequency measurements (in-situ)
 - @300 K: Cav1: 399.959 MHz, Cav2: 399.992 MHz
 - @4.5 K: Cav1: 400.638 MHz, Cav2: 400.689 MHz
- Cool-down start: 11/04 → 24/04 stable 4.5K with small interruption of 2 days
- RF conditioning (voltage calibration yet to be done)
 - Cavity 1 up to 5 kW-CW (~2 MV)
 - Cavity 2 up to 1 kW CW (~0.8 MV) degraded vacuum





May 2, MD#0 for Equipment Check





- Cavities moved with 60% LHe
- Test of interlocks: vacuum valves, access, liquid level
- Safe position table for beam confirmed by position switches (Parking, experiment)
- Absolute positions measured on line by EN Survey with FSI system, well within requirements (repeatable to within few μm)



RF Conditioning, Vacuum Evolution, May 2018

Fimeseries Chart between 2018-05-01 08:59:00.000 and 2018-05-30 21:02:36.442 (UTC_TIME)





MD #1 – Protons meet Crabs



First injection – 12:55, May 23

Worked w/o RF feedback $0.2 - 0.8 \times 10^{11}$ p/b





Crab-RF Sychronization

- Crab cavity rf set point from BA6 to BA3
- CC ~400 MHz, SPS RF ~200 MHz
- Rephasing of SPS RF to become synchronous with crab signal.





Reconstruction of Crabbing using HT



of turns for ref position along the bunch ~ 2k turns RF re-synchronization ~ 1s after injection



MD #2: Nominal Bunches 26 & 270 GeV



1 MV in cavity 1 (up to 2MV in some cases) ~50 kV in cavity 2, limited by cavity vacuum





RF Feedback & Beam Induced Signal



Input drive and voltage spikes at F_{rev} , due to direct beam coupling

Need to filter antenna signals better to suppress the direct beam induced signals

In parallel looking at alteration to cavity antenna to minimize effect





Orbit Scan for Electrical Center

- $\pm 5 \text{ mm}$ orbit bumps around the crab location
- Electrical center measurements were tried for fundamental mode and HOM
- Geometrical center from DOROS +1.25 mm, cavity measurements not conclusive (need higher current)





Emittance Measurements



Tune Crossing for a3 Measurements

- First attempt using closest tune approach to determine the *a*3 multipolar of the crab
- Better setup required for future MDs





Slow Losses at 26 GeV

 Cav 1 tuner loop setup and crossed the vertical tune







270 GeV Ramp

Cav1 ~1MV (400.787 MHZ), Cav2 off (400.528 MHz)





- Checked with and w/o transverse feedback beyond nominal bunch
- Longitudinally unstable w/o 800 MHz



Ramp to 270 GeV

Vertical tune: $Q_{\gamma} = 0.18$

RF Freq: Cavity 1: 400.787 MHz (~1 MV) Cavity 2: 400.528 MHz (almost zero)

Resonant excitation observed as we cross the vertical tune (black dotted lines).

Kicking the beam at 270 GeV equivalent frequency , while sweeping the beam frequency from 26-270 GeV

After setting the correct cycle start voltage to 270 GeV equivalent, beam circulated w/o any issue





HOMs

Peak HOM power estimated < 100 mW (analysis **ongoing** to account frequency dependent cable losses)



Nest Steps

- May: 2 MDs with beam
 - 23 May: Operated in RF open loop at 26 GeV low intensities (cav1 ~200 300 kV, cav2 ~50 kV), tried up to nominal
 - 30 May: RF feedback on. 26 GeV & 270 GeV nominal bunches (cav1 ~ 1 MV, cav2 ~ 50 kV)
- June: No MDs planned
 - Warm up done immediately after MD#2
 - TS1: Commissioning of the warm pumping units + some other interventions on instrumentation.
 - Validated 2K in manual mode (up to 25 mbar) producing superfluid helium
 - Continue operation of the module at 4.5 K for next days to adapt control logic to have automatic 2 K operation within next 2 weeks
- July: LLRF fully deployed \rightarrow >2 MV/cavity
 - RF Feedback + tuner loop for both cavities for transparency tests
 - Higher intensities (up to train of 60 nominal @ 26 GeV & 2 nominal bunches at 270 GeV)



Since MD#2





MD slot allocation for 2018



Beam to NA Close LEIR Start NA phy Start ISOLDE P Start AWA		hysics physics Bea	End LN4 RR End AWAKE#1 Start AD physics Beam to ADT									Start AWAKE#2	
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Мо	Easter Mon 2	DSO test LEIR 9	Beam to ¥ LEIR 16	5 23	Pb beam to PS 30	7	14	Whitsun 21	28	Pb beam to SPS 4	11	UA9 18	¥ 25
Tu	DSO test ADT, AD+Sec, ELENA				1st May	Par. SPS MD 10 hrs 8 to 18					Par. SPS MD 10 hrs 8 to 18	Technical stop	
We			Ded. Inj. MD 10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18	40	Ded. Inj. MD 10 hrs 8 to 18	¥	ITS1 30 hrs Restart	Ded. Inj. MD 10 hrs 8 to 18			
Th	Beam to LHC		Par. SP5 MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18	Par. SPS MD 10 hr to 18	Ascension	Par. SPS MD 10 hrs 8 to 18		COLDEX 24 hrs	Par. SPS MD 10 hrs 8 to 18			
Fr					T			•	•				
Sa				CC	table	test							
Su				& C	ycle se	etup		MD 1	& 2				

	July	End A	WAKE#2	LHC MD2 Aug				Start	AWAKE#3	Sep и	MD3 End AWAKE#3		AKE#3
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39
Мо	2	9	¥ 16	23	30	6	13	20	¥ 27	3	10	UA9 17	24
Tu										Par. SPS MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18	Technical stop	
We	Ded. It . MD 10 hrs to 18	Ded. Inj. MD 10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18		Ded. Inj. MD 10 hrs 8 to 18	*	Restart	Ded. Inj. MD 10 hrs 8 to 18					
Th	Par. SPS MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18		Par. SPS MD 10 hrs 8 to 18	Jeune G.		COLDEX 24 hrs	Par. SPS MD 10 hrs 8 to 18				
Fr													
Sa													
Su													

	_	Oct Start A	AWAKE#4 LHC	CMD4 lons	to LHC	End all pr ISO, EA, A HiRadM NOV	roton physics ND, nTOF, NA, 1at, AWAKE Ions to NA	& EA LHC ME	Enc (0) 05	End injectors, nd LHC NA, EA (06:00) 6:00 End Clear Dec				
Wk	40	41	42	43	44	45	46	47	48	49	50	51	52	
Мо	1	8	V 15	22	29	5	RP cooldonw & survey	2 🗭 19	26	¥ 3	¥ 10	17	Xmas 24	
Tu							PSB/PS/SPS 30hrs + 4	*						
We	13h	Ded. Inj. MD 10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18	13h	COLDEX 24 hrs	Ded. Inj. MD 10 hrs 8 to 18		Ded. Inj. MD 10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18		Long Shi	utdown 2		
Th	10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18	10 hrs 8 to 18	Ded. Inj. MD 10 hrs 8 to 18	Par. SPS MD 10 hrs 8 to 18						I		
Fr				*	-		LHC Pb-Pb io	n physics 4 wks	5					
Sa		no flex	<i>vibility</i>				Nort	h & East Area	Pb ion Physics 4	wks				
Su			,		*									



