

# Operation experience with the LHC RF system





Prepared by O. Brunner and L. Arnaudon/ CERN  
on behalf on the RF group  
CW RF Workshop / Alba, Mai 4-8 2010.

# Summary

- Presentation of the LHC RF system
- First results with beam
- Reliability and performances

# Layout (1)

- Two independent rings
- 8 RF cavities per ring all installed at point 4
- Klystrons and Cavity Controllers in a cavern ~150 m underground



# Layout (2)




- 100kV, 40A (ex-LEP) power converters located at the surface
- Klystron modulators, fast protection systems in four HV bunkers
- Sixteen 330 kW klystrons + circulators + RF ferrite loads in UX45
- Power control system based on industrial PLCs, plus a fast Interlock protection system
- WR2300 HH WG distribution system to individual cavities
- LLRF for Cavity Controllers in two Faraday Cages
- Beam Control equipment in a surface building in SR4



=> Most of RF equipment is not accessible during operation


# HV power converters

- 100kV, 40A (ex-LEP) power converters located at the surface
- Each power converter feeds 4 klystrons
- Nominal klystron working point: 58 kV, 8.8A (now 50 kV, 8A, see below)
- Main concern: RF noise in cavities due to HV ripple
  - Klystron HV is produced by 12 poles => HV contains ripples at 50, 100, ... and 600Hz producing phase modulation of the RF output
  - Up to 10% HV ripple measured on power converters @ 58kV, 36A
  - Could be reduced to  $\approx 0.5 - 1\%$  by fine tuning the phase advance of 12 phases to minimize HV ripple
  - HV ripples: **1 % variation of HV still induces  $\approx 8$  degrees** @ 400.8MHz and 58kV
    - Still an issue since 50Hz close to LHC synchrotron frequency
    - Klystron Polar Loop => down to  **$\sim 0.2$  dg pkpk**



P. Baudrenghien, The LHC Low Level RF, LLRF07, Knoxville TN, Oct 23,2007

# Klystron CW (1)



Klystron power sweep CW @ 400.8 MHz




- 1 klystron per cavity
  - 330 kW max (58 kV, 8.4 A)
  - 130 ns group delay (~ 10 MHz BW)
  - CW gain 39 dB @ 200 kW, 36 dB @ 300 kW
  - In operation ≈ 200 kW CW

# Klystron CW (2)



Klystron low signal sweep  $f_0 \pm 6$  MHz



Klystron peak output power  $\approx 200$  kW @  $f_0$  plus a  $\approx 20$  dB lower superimposed sweep signals between  $f_0 \pm 6$  MHz


## – LLRF constraints:

- Systems typically operated at a peak output power  $\approx -1.5$  dB below saturation (@ $f_0$ ) plus a  $\approx 20$  dB lower superimposed correction signals between  $f_0 \pm 6$  MHz.  
 => sets the maximum admissible gain for the klystron's bunching cavities as a function of frequency
- LHC: Notch filter integrated in the LLRF to cope with the second bunching cavities
  - all klystrons second bunching cavities tuned in same frequency range ( $\pm 0.4$  MHz)
  - resulted in quite poor klystron efficiency in some cases..

# Klystron CW (3)

- 21 klystrons @ CERN

- 16 in LHC
- 2 on test stands
- 3 spares



- Problems so far:

- 1 klystron developed a short circuit in gun (repaired)
- 1 klystron with sudden overheating of the output coaxial transition (multipactor)
- 1 klystron died due to a **vacuum leak after 16 khrs**
  - **Bad water cooling** of the hypervapotron collector was found culprit
  - Water cooling jacket modified and successfully tested (>48hr full DC power test)
  - At the time, all klystrons were equipped with modified water cooling jacket
  - Post inspection of at least one LHC collector was planned (>1000hrs)



- Inspection in LHC took place in January '10

- **Reveal that the new boilers did not solved the problem!**
- Collectors are still overheating
- Simulation from Thales showed that the collectors are suffering from a deficiency in water speed in this region
- Campaign launched with THALES to find a definitive solution...

- In the mean time...as LHC had to be restarted in February

- **DC power limited to 400kW max (50kV, 8A)** (instead of 58kV , 8.5 A)
- Water flows inverted on all collectors, to get better water speed homogeneity




# Circulator, RF load, WG

- 1 circulator per cavity
  - 330 kW max
  - 60 ns group delay
  - Circulator equipped with temperature control system
    - ⇒ Affects the  $Q_{\text{ext}}$  of the cavity

(=> see N. Schwerg's presentation)

- 1 RF ferrite load per circulator
  - 330 kW CW
  - RF loads reflection < -28 dB
- Wave guide system
  - WR2300 HH
  - Length: 15 to 30 meters




# Cavities




- 8 RF cavities per ring at 400.790 MHz:
  - Super Conducting Standing Wave Cavities, single-cell,  $R/Q = 45$  ohms, 6 MV/m nominal
  - Equipped with movable Main Coupler ( $20000 < Q_L < 180000$ )
  - Mechanical Tuner range = 100 kHz
- 4 spare cavities assembled in a cryomodule + 1 spare cavity
- new spare cavities shall be built in the next years

# Low Level RF System



Ph. Baudrenghien

- **Cavity controller:**
- Fast loops using cavity or waveguide measurements
- Individual control:
  - the field in each cavity
  - the cavity tune
  - the klystron gain/phase shift



RF Feedback	Open (@Q=60k)	Closed (for all Qs)
2-sided Bw	~7 kHz	~700kHz
Impedance	2.7 MΩ per cav.	45kΩ per cav.

L. Arnaudon

- **The Klystron Polar Loop** compensates for the klystron gain/phase changes
- The RF Feedback Loop reduces the cavity impedance at the fundamental.
- The Tuner Loop minimizes the klystron current.

- **Beam Control**

- the average energy of the beam (via the RF frequency)
- the phase of the average voltage (vector sum of 8 cavities).

**The Frequency Program:**


- Generates an RF which is set to the injection frequency and then follows a function through the acceleration ramp

**Phase loop:**

- Locks the Cav Sum (RF sum of the Antenna of 8 cavities) onto the beam (Wide-Band PU signal thru 400.8 MHz BPF) at injection.
- Very fast loop. Reacts in ~ 10 turns (~ 1ms). Must be fast compared to synchrotron period (Ts around 20 ms) to avoid filamentation at injection.

**Synchro loop:**

- Locks the RF on the Frequency Program.
- The Freq Program reference is sent to the SPS (ref for injection) and is the common ref for both rings (ref for cogging).
- Slow loop. Reacts in tens of ms





L. Arnaudon

# RF Synchronization:

- Pilots the bunch into bucket transfer from SPS to LHC

- A very flexible system allows operation to inject in any bucket using the bucket selector application.
- The collision point is set and kept very precisely within specification, 2mm in an optimal range of 30mm.
- No correction of the setting since 2 month and no difference related to energy change.




J. Noirjean

27.04.2009/J.Noirjean


92 fiber optic link are used to distribute frequencies and synchronization pulses between LHC, experiments and the CERN accelerator complex.

...with beam...


# Capture (1)



RF ON, wrong phase...



RF ON, good phase  
Phase loop OFF...



RF ON, good phase  
Phase loop ON...

T. Bohl / U. Wehrle

Mountain range displays



# Couplers gymnastic


- **At injection:**
  - **8 MV** to match the 0.8 eVs bunch from the SPS
  - Low  $Q_L$  favorable for fast damping of momentum/phase errors
- **During physics:**
  - Emittance must be blown up to 2.5 eVs (lifetime issues) => **16 MV needed**
  - High  $Q_L$  required (2 MV/cavity)

	<b>Injection</b>	<b>Start Ramp</b>	<b>Ramp &amp; Physics</b>
<b>Q</b>	20k	60k	60k
<b>Eacc</b>	5MV	5MV	8MV
<b>Ig</b>	~95kW	~33kW	~100kW


 First move Q to 60k  then raise voltage

# Reliability and performance (1)

- Beam intensity:
  - Pilot beam with low intensity ( $2E10$ ) and low emittance ( $0.2-0.4eV$ )
  - Successful tests made with one bunch at nominal intensity ( $1.1E11$ ) & emittance up to  $2.5eVs$
  - > some very long physics fills @ 3.5 TeV
  - Luminosity lifetime of up to 30h
- Limitation: 50kV, 8A
- Reliability:
  - 0 hrs of beam lost due to RF
  - Few trips per day/week
  - Some recurrent problems successfully treated
    - Thyatron auto triggering
    - Arc detectors
    - Main coupler blower glitches: still an issue under investigation



# Reliability and performance (2)



L. Arnaudon

- RF system consists of about 1000 interlocks
- Long periods (>>days), without RF trips.
- The RF system is very reliable with the present beam conditions, efforts will continue to prepare for the higher intensity runs...