

# Spallation Neutron Source RF Systems

Tom Hardek

Mark Crofford


Mark Middendorf

Maurice Piller

Yoon Kang

Sung-Woo Lee

Alexandre Vassioutchenko



# Outline

- SNS Operational Status
- Brief Accelerator Tour
- Current Performance
- Overview of RF Systems work
- A Look into the Future

# 1 Megawatt of Beam On Target


## Beam On Target (BCM25I)

Engineering Screen

*Auto Save:*  
*Ok*

<p><b>Q</b> <i>1.853e-05 C</i></p> <p><b>Energy Per Pulse</b> <i>17193 J</i></p> <p style="color: green; font-weight: bold; font-size: 1.2em;">Integrating</p> <p><b>Qint</b> <i>1.062e+04 C</i></p>	<p><b>PPP</b> <i>1.156e+14</i></p> <p><b>Power</b></p> <table style="width: 100%; border-collapse: collapse;"><tr><td style="width: 50%;"><i>1027377</i></td><td><b>1 Second Average</b></td></tr><tr><td><i>1025409</i></td><td><b>10 Second Average</b></td></tr><tr><td><i>1024000</i></td><td><b>1 Minute Average</b></td></tr></table> <p><b>Integrated power on target</b> <i>3.70939e+06 KWH</i></p>	<i>1027377</i>	<b>1 Second Average</b>	<i>1025409</i>	<b>10 Second Average</b>	<i>1024000</i>	<b>1 Minute Average</b>
<i>1027377</i>	<b>1 Second Average</b>						
<i>1025409</i>	<b>10 Second Average</b>						
<i>1024000</i>	<b>1 Minute Average</b>						

# Overall Operating Parameters




# Extended Operation at 1 MW

Energy and Power on Target

**1022.6 kW on Target**

**Beam to Target**



# Full Design Intensity Beam Pulse 1.4e14 PPP

**Diagnostics**  
RTBT\_Diag:BCM25

[Power Web Page](#)

BCM 25 I

Pulse	Integrated	
Charge <span style="background-color: #4b4b4b; color: green; padding: 2px;">2.48e-05</span>	Current (A) <span style="background-color: #4b4b4b; color: green; padding: 2px;">63.628</span>	Total kWh <span style="background-color: #4b4b4b; color: green; padding: 2px;">2974064.3</span>
Particles <span style="background-color: #4b4b4b; color: green; padding: 2px;">1.55e+14</span>	Power (W) <span style="background-color: #4b4b4b; color: green; padding: 2px;">6871.327</span>	Total Charge <span style="background-color: #4b4b4b; color: green; padding: 2px;">12158.164</span>

**Waveshape**

RTBT\_Diag:BCM25:currentTBT

Minipulse Integration Delay  
0.00e+00 2.43e-06

Ring Period  
0.00e+00 1.00e-06

Trigger Offset  
0.00e+00 0.00e+00

Threshold  
0.000 0.010

Range Method  
0.00 0.00

Period Method  
0.00 1.00

Analysis Method  
0.00 4.00

Minipulse Integration Width  
0.00e+00 1.00e-06

Turns  
0.00 0.00

Turns Method  
0.00e+00 0.00e+00

**Beam Delay**  
1.630 usec

**Beam Length**  
0.680 usec


Raw Data

Experts Only  
FPGA

# A Brief Photo Tour of the Various RF Systems

# Layout of Linac RF Modules

● 402.5 MHz, 2.5 MW klystron	3 Transmitter	3 Modulators
⊖ 805 MHz, 5 MW klystron	4 Transmitter	4 Modulators
⊖ 805 MHz, 0.55 MW klystron	14 Transmitter	7 Modulators






# Ion Source & RFQ

## Ion Source


- Currently using an Internal Antenna for production runs
- Have used an External Antenna ion source, a new development
- Pulsed 2 MHz at 50+ kW
- 13 MHz CW applied to the same antenna to maintain a low level plasma between pulses



## RFQ

- Recently modified to use only 2 Drive Couplers
- Accelerates H- Ions to 2.5 MeV
- Overcame difficulties in tuning at high duty cycle operations with LLRF improvement

# Medium Energy Beam Transport - MEBT



## MEBT

- Rebuncher system between RFQ and DTL with 4 cavities and other beam components
- Four 402.5 MHz amplifiers pulsed at 5 - 20+ kW


# Klystron Gallery Normal Conducting RF

- RFQ

- 1<sup>st</sup> klystron powers the RFQ structure.
- 800 kW, 402.5 MHz
- E2V klystrons
- The klystron can provide 2.5 MW so this klystron has excess power.
  - Actually installed first article klystron only producing 1.8 MW

- DTL

- 6 Klystrons power the DTL
- 2.5 MW, 402.5 MHz
- E2V klystrons
- Circulator Loads use a Water – Glycol mix.





# Klystron Gallery Normal Conducting RF

- CCL
  - 4 Klystrons power the CCL cavities
  - 5 MW, 805 MHz Thales Klystrons
  - Output window is gas insulated with SF<sub>6</sub>.
  - Circulator is gas insulated with SF<sub>6</sub>
  - Circulator load is conventional water load
  - Power is split to provide 2 structure inputs of 2.5 MW each



# Drift Tube Linac and Coupled Cavity Linac

## Los Alamos National Lab



**The 402.5 MHz DTL is composed of six sections.**



**The 805 MHz CCL is composed of four sections.**



# Klystron Gallery Superconducting Cavity RF

- SCL RF
  - 81 Klystrons each powering a separate cavity
  - 550 kW @ 75 kV
  - 805 MHz
  - CPI and Thales



# Superconducting Linac


## Jefferson Lab

- First and highest energy superconducting H- linac in the world
- 23 cryomodules
  - 11 medium-beta
  - 12 high-beta
- 33 medium-beta cavities
- 48 high-beta cavities
- One klystron per cavity



# Accumulator Ring RF


- Ring RF
  - 4 Bunching Cavity/Amplifier stations
    - Ferrite loaded (Phillips 4M2)
    - Cavity Bias provides dynamic tuning
    - Beam pipe and outer housing used for bias.
  - 2 bunching gaps per cavity
  - 3 Buncher Cavities operate at the revolution frequency 1.05 MHz
    - Maintain a gap to allow the extraction kickers adequate time to reach full field.
  - 1 Cavity operates at the 2<sup>nd</sup> harmonic 2.1 MHz
    - Reduce the peak beam current to minimize the possibility of exciting instabilities.
  - All cavities and amplifiers are the same.
    - Resonating capacity reduced for the 2<sup>nd</sup> harmonic cavity allowing use of the same structure.






# Accelerator Performance

# Klystron Operating Hours - High Voltage




# Perveance - Last 2 years - RFQ Klystron



- Red Trace = Cathode Current [Amperes]
- Blue Trace = Modulator Voltage [kV]
- Green Trace = Perveance [ $\mu\text{perv}$ ]

# Klystron Operational Efficiency

**Klystron Operational Efficiency**  
Power Delivered to Cavity With Beam Loading/DC Power



- Not Taken Into account
  - Modulator Droop
  - RF on longer than beam pulse

# Failed Klystrons – 4 Years of Full Operation

- DTL Klystrons (5 failures)
  - 1 klystron failed when we nearly burned through the body due to loss of focusing field
    - We were able to repair this klystron and it is fully functional
  - 1 klystron experienced magnet cooling loop piping damage due to Loss of cooling water
    - Repaired magnet
  - 3 klystrons experienced body cooling loop water leaks
    - Repaired cooling loop piping
- CCL Klystrons (2 failures)
  - 1 klystron suffered loss of emission
    - Thales is investigating
    - We may have had the cathode and filament leads reversed
  - 1 klystron lost vacuum while in storage
- SCL Klystrons (5 failures)
  - 1 klystron suffered water damage when it's magnet leaked and filled the space between the klystron and magnet with water
  - 1 klystron suffered gun damage when we miswired the gun magnet
  - 3 klystrons suffered from stability issues after we began operating them at 75 kV
    - Believe we can alter output matching to regain stable operation
  - 1 klystron replaced due to cathode arcing
    - Might be able to condition this klystron

# Overview of RF Systems Issues

# Ion Source RF

## Tomco Solid State 2 MHz Amplifier



- Original Tetrode amplifiers have served well but replacement parts are hard to acquire
- We wanted to purchase another power amplifier for a second test stand and decided on a solid state version
- We will ultimately replace all amplifiers with the solid state units operated at ground potential
  - Original amplifiers operate at -65kV
- 120 kW in 2 racks
- Two units are in our lab
  - Setting up for Site Acceptance Test
- Each amplifier rack can operate independently
- Each rack produces 60 kW

# RFQ Status

- Retuned RFQ after a major shift in frequency and field flatness last year (January 2009)
  - Seems to be the result of a vane shifting due to a water pressure surge during maintenance
  - Similar to shift that occurred several years ago
  - Concerned another shift could take place
  - May have field errors we do not observe
- Working on obtaining a spare
  - Prepared specification
  - Received bids from several possible vendors
  - Working on clarifying some items with vendors
- Had issues with loss of resonance control at high duty after several hours of operation
  - Limiting Ion Source gas flow
  - Upgraded water manifold to improve cooling
  - Added feedback loops to LLRF control page to regulate pulse width and chiller temperature
  - Added pressure relief valves
  - Changed pumps in chiller




# MEBT Rebuncher Amplifier System

Original system utilized 3CX5000's – Had reliability issues

First MEBT Solid State RF Amplifier – Now Operating Cavity 4



Tomco Solid State Amplifier




Switching Assembly, Circulators,  
Directional Couplers




Racks waiting for Amplifiers

# Warm Linac Issues



- Vacuum Leak on DTL-6 RF window
  - Originally thought to be braze joint but may have been O-Ring seal
  - May have a similar problem on several windows
  - RF conditioned 2 spare windows
  - Replaced DTL-6 window during maintenance period
  - Have 3 spare windows on order
  - Planning to build 3 more spare windows in-house



# SCL RF

- Now operating klystrons at design cathode voltage of 75 kV
- Replaced 9 Thales klystrons
  - 3 klystrons showed instability issues
  - All Thales klystrons have high gain
- Suffered arcing condition in SCL-5A coupler
  - We were able to recover this cavity
- Beam loss injured cavities SCL-5A and SCL 6C
  - Made some progress recovering SCL-5A
  - Hope to recover both cavities by careful conditioning

# A Look Into the Future

- Power Upgrade (PUP)
  - Add 36 more SCL Cavities, Klystrons and LLRF Systems
- Intensity upgrade
  - Requires more RF Power
  - Will replace some klystrons and upgrade HVCMs
  - Will need to Process some of our SCL Cryo-modules for higher accelerating field in cavities
- Second Target Station (Currently on-hold)
- Existing LLRF modules have obsolete components
  - Need to be working on next generation system
- Ring LLRF
  - Want to replace existing hardware and software with a version more compatible with our Linac systems

# Summary

- SNS reached 1 MW in mid September as promised to DOE
- Presently operate with 85% reliability
  - Ultimate goal is 95%
  - We have identified major sources of downtime and are addressing them
- There remains significant Ion Source RF System work
- MEBT RF Upgrade has a clear path to completion
- SCL RF Power limitation was resolved by adding an extra converter-modulator (running with 10 klystrons per modulator)
- We are beginning to acquire Klystron Perveance Data
  - Analyzing archive data