

High Power RF Processing of Couplers/Windows and Cavities for SNS Linac



Y. Kang
M. Crofford
T. Hardek
S. Kim
J. Mammosser
R. Peglow
C. Phibbs
A. Vassioutchenko

RAD/SNS/ORNL

6th CW and High Average Power RF Workshop
ALBA, Barcelona, Spain
May 4-7, 2010

Machine layout




Front-End:
Produce
a 1-msec long,
chopped, H-beam

Linac; 1 GeV acceleration


H- stripped to p

Accumulator Ring:
Compress
1 ms long pulse
to 700 ns


Liquid
lg
target



Chopper system makes gaps



SNS RF Systems




All SNS linac RF systems are pulsed at 8% duty cycle (1.3 msec, 60 Hz)

High Power Window/Couplers in SNS Linac

- RFQ powered by one 2.5 MW Klystrons
 - 2 windows for 402.5 MHz Radio-frequency Quadrupole (RFQ)
- 6 DTL tanks powered by 2.5 MW Klystrons
 - 6 windows for 402.5 MHz Drift tube linac (DTL) cavities
- 4 CCL structures powered by 5 MW Klystrons
 - Each CCL structure has 2 input ports
 - Klystron output is divided with a quadrature hybrid
 - 8 windows for 805.0 MHz Coupled cavity linac (CCL) cavities
- SCL cavities
 - 33 medium beta cavities in 11 cryomodules (with 0.55 MW Klystrons)
 - 48 high beta cavities in 12 cryomodules (with 0.55 MW Klystrons)
 - 81 windows for 805.0 MHz Superconducting linac (SCL) cavities
 - 36 high beta cavities will be added (9 cryomodules) in future power upgrade project

RF Processing in SNS RF Test Facility

- High power RF testing and processing can be performed at 8% duty (1.3 msec 60 Hz)
 - 805 MHz, up to 5 MW peak power
 - 402.5 MHz, 2.5 MW max. peak power
 - Complete low-level RF control and monitoring for reliable processing and operation in EPICS environment




- SCL cavities and cryomodules are prepared and processed
 - Cryomodules high power RF tested in test cave after repairs
 - New cryomodule is being assembled (Building a medium-beta cryomodule will start)
 - SRF cavities are plasma processed
- More than 60 windows/couplers including new spares have been conditioned for RFQ, DTL, CCL, and SCL
 - 42 of 81 power couplers of the SNS SRF cavities were RF processed in the RF Test Facility during construction of SNS cryomodules
 - Several cavity window/couplers for RF frequencies different from SNS frequencies were processed

SNS SCL Cryomodules


- Designed to operate at 2.1 K (superfluid helium)
- Total 81 cavities in 23 Cryomodules
 - med- β : 33 6-cell cavities in 11 cryomodules
 - high- β : 48 6-cell cavities in 12 cryomodules

Medium Beta Cryomodule
($\beta=0.61$)




SCL Present Status

- Careful high power testing delivered practical operational limits of cavities (not fundamental limits) but to set a safe operating gradient (Sang-ho Kim)
- SCL is providing a reliable operation for neutron production following SNS power ramp-up
- 930 MeV + 10 MeV (energy reserve)




SCL Considerations (J. Mammosser, S-H. Kim)

- For $> 1\text{GeV}$ operation with high system availability
 - high-beta gradients need to be improved
 - Collective system performance with other improvement
- In-situ plasma processing of cavities successfully tested with **possibility of 2 - 3 MV improvement per cavity**
 - More poorly performing **high-beta** cavities will be processed
- Production of spare cryomodules with better performing cavities
 - Building one high-beta cryomodule is under way and one medium-beta cryomodule will start
 - Completion of SRF Facility (**AIP Project**)
- Changes on the Cavities
 - couplers are interlocked with e-current measurement (interlock using degrading CCGs abandoned)
 - HOM feedthroughs will be taken out as needed
 - Will not have HOM couplers for new cavities



SCL Fundamental Power Coupler



- Present coupler specifications:
 - 550 kW peak
- 50 kW average
 - $Q_{ext} \sim 7 \times 10^5$
- Performance:
 - Conditioned up to 650 kW power in traveling wave and 2.4 MW power in standing wave
 - Over 500 kW peak power in linac cavity operation
- Consideration
 - Higher peak and average power capability for the future SNS power upgrade & more stable operation may require additional cooling at the antenna tip

Coupler RF Processing in EPICS

RF Conditioning System
Nov 09, 2009 16:18:50

Auto Process: **START** (Green), **STOP** (Red)

Auto Cycle: OFF, ON

Sequence State: **Hold**

Power State: Pwr: -4.138

After Fault Increment (dBm): 0.050

RF Increment (dBm): 0.002

Soak Time (Sec): 0.0

Pulse Width (us): 100.0

Vacuum Upper Limit (mbar): 3.00e-07

Vacuum Lower Limit (mbar): 1.00e-07

RF Upper Limit (dBm): -4.14

RF Lower Limit (dBm): -40.00

RF BOF Increment (dBm): 0.100

Step Interval (Sec): 1.0

Water Interlocks: Flow (0.83, 0.78), Temperature (31.53, 32.61, 29.77, 79.24), E-Current 2 (0.00e+00)

Vacuum Controller: CCG-2 Analog (2.1e-12), CCG-1 Analog (1.0e-07)


Power Meter (kW): Output FWD, Input FWD (2525.911), Output RFL (3.349), Input RFL (1.972)

RF Interlock SW 805: MPS Permit Out (404), RF Permit Inp. (5042), SAW RF Permit (F.O. Arc)

Signal Generator: RF Status (On), Frequency (805.0 MHz), Signal Power (-4.138 dBm)


RF Processing Control Screen

SCL Coupler Conditioning Setup




- Coupler conditioning processes:
 - Baked up to 200 °C with controlled slow ramp-up and cool down
 - 650 kW traveling wave to 6% duty cycle
 - 600 kW standing wave (2.4 MW peak) with variable waveguide short
 - Use of DC biasing during conditioning

RFQ Window/Coupler Construction





- RFQ system was upgraded with two coupler configuration (from 8 coupler configuration)
 - Use a magic-T hybrid power splitter with a water load on the isolation port
 - Operate at ~ 800 kW (400 kW / coupler)
 - Use coupler ports farther away from the H- ion-source for better vacuum condition
- New couplers designed using SCL coupler window routinely conditioned to 600 kW peak power @ 6% duty in traveling wave
 - 6 new couplers manufactured and RF conditioned at SNS/RFTF
 - RF conditioned up to 450 kW @ 1 msec, 30 Hz through bridge waveguide


RFQ Coupler RF Conditioning






- 402.5 MHz operating frequency
- Rectangular re-entrant cavity type (or ridge waveguide) is used as the bridge waveguide
- Used special vacuum ports to accommodate the coupler loop antenna tip design




Return and insertion losses through bridge waveguide and couplers





Upgraded RFQ Couplers





SNS CCL Window/Coupler Preparation



- Bridge waveguide is copper plated
- Pumping ports are equipped with RF screen
- Extra ports are for arc detectors and vacuum gauges
- Insertion loss of two windows with the bridge waveguide is < -0.03 dB
- Baked for 48 hrs at 150 °C with 12 hrs ramp-up and 12 hrs cool down





CCL Window RF Processing




SNS DTL Window/Coupler Conditioning

- Compact bridge waveguides have been built and copper plated
- Spare windows for 402.5 MHz, 2.5 MW cavities have been conditioned
- Conditioning setups for the DTL and CCL windows are similar except the waveguide dimensions




RF Distribution Setup for Cryomodule Test (up to 4 cavities)



Waveguide Feed Network for Four Cavity Conditioning

- Feed four SCL cavities with one klystron (available 5 MW tubes)
- Use waveguide vector modulator employing the mechanical phase shifters
- Adjust the power of four outputs connected to cavities to $\pm 40\%$ in amplitude and $\pm 30^\circ$ in phase



Summary

- LINAC RF structures and their high power components are performing reliably with continuous improvements
- RFTF completely equipped and operational:
 - Two klystron tanks with complete waveguides in WR2100 (402.5 MHz) and WR1150 (805 MHz)
 - One 11 MW peak power high voltage converter modulator (HVCM) for powering the klystrons up to 8% duty in 60 – 135 kV.
 - Test cave measures 3.6 m x 8 m
 - Clean room facility for SRF processing and other utilities for He cryo systems, vacuum, and water cooling
 - Complete low-level RF control and monitoring for operation in EPICS environment
 - Programmable bake out setup
- Performed RF processing tasks successfully during construction, commissioning, and post-commissioning operation
 - Conditioned new spare window/couplers have been conditioned for RFQ, DTL, CCL
 - Conditioned more than 50 couplers for SCL
- Ready for the upcoming power upgrade project (PUP) with assembling, testing, and conditioning of couplers and cavities