

Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science


Fundamental Couplers Activities in FNAL

Sergey Kazakov, June 5-6, 2018, CERN Worldwide Workshop on Fundamental Power Couplers

PIP-II couplers

PIP-II project:

Perfomance Parameter	Value	Unit
Paticle species	H	
Linac Beam Energy	800	MeV
Linac Beam Current	2	mA
Linac Pulse Length	0.55 - CW	ms
Linac Pulse Repetition Rate	20 - CW	Hz



PIP-II couplers

- Room temperature cavities:
 - RFQ.
 - Bunching cavities (4 pc).
- 5 types of superconductive cavities:
 - Half Wave Resonators, HWR (8 pc).
 - Superconductive Spoke Resonator 1, SSR1 (16 pc).
 - Superconductive Spoke Resonator 2, SSR2 (35 pc).
 - Low Beta 650 MHz Cavity, LB 650 (33 pc).
 - High Beta 650 MHz Cavity, HB 650 (24 pc).

Total number of couplers: 122.

PIP-II couplers

Requirements to couplers:

(Requirements meets <u>CW</u> version of PIP-II with <u>5 mA</u> current. Requirements are revised now for 2 mA version.)

RFQ coupler:

Frequency162.5 MHzPower75 kW, CW

Bunching coupler:

Frequency162.5 MHzPower3 kW, CW

HWR coupler:

Frequency 162.5 MHz Power 10 kW, CW

SSR1 & SSR2 coupler:

Frequency325 MHzPower30 kW, CW

LB & HB 650 coupler:


Frequency650 MHzPower110 kW, CW

All couplers were designed and all, except 650 MHz couplers, were built and tested.



🛟 Fermilab

162.5 MHz RFQ coupler




5 S. Kazakov | Fundamental Couplers Activities in FNAL

6/6/2018

‡ Fermilab

162.5 MHz RFQ coupler




Two coupler and four windows unit were produced.

Two windows failed after ~ 500 h work in CW mode.



6 S. Kazakov | Fundamental Couplers Activities in FNAL

Windows with replaceable ceramic and Viton O-rings were designed.



Diameter of ceramics was increased up to 6".

In case of broken window (broken ceramics), the ceramics can be replace easily (and one order less expensive).

We have 8 spare ceramic disk on the shelf.




S. Kazakov | Fundamental Couplers Activities in FNAL

7

162.5 MHz RFQ coupler











8 S. Kazakov | Fundamental Couplers Activities in FNAL

We hope we solved the problem with RFQ couplers. Ceramics is large, stresses are small. Multipactor is suppressed by HV bias.


Couplers works already more then 3 months. Total time > 350 hours in CW mode.



Design power: 30 kW, CW, full reflection

RF Window:

Single, room temperature, alumina, OD 73mm (2.87"), ID 12.7mm (0.5"), thick. 6mm (.236")



Antenna: Copper 0.5", air cooled, HV bias.

Outer conductor:

SS, ID 73mm (2.78"), 0.4mm wall thickness, no Cu coating.

Thermal properties of coupler (without thermal radiation of antenna):

P, kW	"2K ", W	"5K", W	"70K", W
0	0.07	0.35	1.9
10	0.20	0.62	4.6
20	0.33	0.89	5.7




10 S. Kazakov | Fundamental Couplers Activities in FNAL

Current status

- Couplers were successfully tested up to 30 kW, CW, full reflection, 90 dgr. step reflection phase.
- Couplers were tested up to failure. Window was destroyed at 47 KW, CW, full reflection.
- 5 couplers produced by CPI.
- 6 couplers are under production in CPI
- Three cavity were qualified with couplers (ready to be installed to cryomodule). Additional five cavity should be qualified before fall.




Each ceramic disk is measured before to be brazed.





CoorsTek ceramic measurements, F ~ 2.7 GHz





Some times ceramics is extremely good: loss tangent ~ 1.5E-5 at 2.7 GHZ




13 S. Kazakov | Fundamental Couplers Activities in FNAL

Antenna made by CPI










14 S. Kazakov | Fundamental Couplers Activities in FNAL

Coupler qualification:

Each couplers (each pair of couplers) is qualified at test stand.

Qualification: running coupler at full reflection mode, CW, at qualification power level for ~ 2 hours at each reflecting phase point. It is 4 phase point with 90 dgr. steps. Total time ~ 8 hours. Qualification power depends on operating power. It is still debated how much it shall be. Qualification is not conditioning. After qualification the couplers are re-cleaned and installed to cavity without conditioning. Really, the couplers do not require a conditioning. HV bias suppresses any activity.






15 S. Kazakov | Fundamental Couplers Activities in FNAL

Problem and issues with current design:

Wall thickness of vacuum outer conductor is rather small,
 0.4 mm. It is causes difficulties for handling. The wall thickness will be increased in next bunch of couplers.




LB & HB coupler, new design



Fermilab




LB & HB coupler, backup design





18 S. Kazakov | Fundamental Couplers Activities in FNAL

Vacuum part of coupler, new design



19 S. Kazakov | Fundamental Couplers Activities in FNAL

Thermal properties of 650 MHz couplers

	2K, W	5K, W	70K, W	293K, W
New, 0 kW	0.15	0.6	3.3	-2.7
New, 100 kW	0.55	0.93	6.2	21
Bckp, 0 kW	0.41	1.46	3.0	-3.1
Bckp, 100 kW	0.97	4.1	11.4	20

100 kW:

New = 0.55*960 + 0.93*220 + 6.2*20 = 857 W of cryo-plant Bckp = 0.97*960 + 4.1*220 + 11.4*20 = 2061 W of cryo-plant

New design requires ~ 2.4 times less power of cryo-plant.



20 S. Kazakov | Fundamental Couplers Activities in FNAL

Current status

- Two coupler prototypes with four vacuum parts are under production.
- Four vacuum parts are already made by CPI.
- Test infrastructure is under constriction.












Couplers test bench.





Couplers will be tested in resonance mode with full reflected power. It will allow to increase the level of testing power more then 100 kW using 30 kW RF source.






‡ Fermilab

6/6/2018

After the test couplers will be re-cleaned.



1.3 GHz prototype coupler was successfully tested in last week.



Design is similar to 650 MHz coupler design.



Coupler at test stand Matched load Waveguide to 30 kW, CW source. **RF vacuum window** Coupler

25 S. Kazakov | Fundamental Couplers Activities in FNAL

6/6/2018

‡Fermilab

Test results:

Coupler was tested in pulse and CW modes. + 3kV bias was applied in all tests.

- In pulse mode the coupler was tested up to 15 kW/ 10ms only.
 RF source (IOT) was not stable in pulse mode.
- There was no sign of any vacuum activity (no evidences of multipactor) during the pulse mode test. Vacuum level was ~ 2E-8 Torr.

Other test were in CW mode.

- Maximum power 27 kW, CW, TW was reached.
- Power level was limited by RF source (IOT).
- Time was limited by temperature (vacuum level) of waveguide RF window. Window became hot and vacuum level reached upper limit 1E-6 Torr.




Power	Time
27 kW	~ 14min
20 kW	~ 1 hour
15 kW	~ ∞

Conclusion:

New configuration works:

- No multipactor in slots, no multipactor in SS chambers.
- No other vacuum activities.





MP is suppressed by HV bias



6/6/2018

‡Fermilab