



# COOLING & VENTILATION INFRASTRUCTURE

Mauro Nonis  
Pedro Cabral



ENGINEERING  
DEPARTMENT

CLIC CEIS Working Group Meeting 31/08/2018

# Outline

---



1 – CV PiP Chapter

2 – Energetic Summary

3 – Future work

4 – Conclusions

# PiP Chapter

---



➤ Piped Utilities

➤ Ventilation Infrastructure

## ➤ Piped Utilities

- Industrial / Demineralized Water : Refrigeration
- Chilled Water : Air Handling Units
- Drinking Water : Make-Up Water
- Industrial Water : Fire-Fighting Systems
- Waste Water
- Compressed Air


# PIP Chapter



## ➤ Piped Utilities

- Water Cooling Sectors


- 1 – Drive Beam Injector Complex
- 2 – Main Tunnel
- 3 – Experimental Complex
- 4 – Main Beam Injector Complex



## ➤ Piped Utilities

- Primary Cooling Circuits


- Cooled by cooling towers
- Industrial water
- To refrigerate:
  - Secondary demineralized water circuits
  - Secondary industrial water circuits (exceptions)
  - Chillers
  - DX units



## ➤ Piped Utilities

- Secondary Cooling Circuits


- Cooled by a primary circuit
- Generally demineralized water
- To refrigerate:
  - Mainly equipment related to the accelerator



## ➤ Piped Utilities

- Chilled Water Circuits


- Cooled by chillers
- Industrial water
- To refrigerate:
  - AHUs





## ➤ Piped Utilities

- Piping Layout at Surface/ Shallow Underground (not included in the PiP)



# PIP Chapter



## ➤ Piped Utilities

Sector	Primary Circuits						
	Structure	Two Beam Machine			Klystron Machine		
		Cooling Power kW	Flow Rate m <sup>3</sup> /h	Cooling Towers no	Cooling Power kW	Flow Rate m <sup>3</sup> /h	Cooling Towers no
1	Drive Beam Injector U	5356	577	na			na
	Drive Beam Injector S	14191	1529				
	Frequency Multiplication Circuit a)	3238	349				
	Frequency Multiplication Circuit b), CR1 S, CR2 S and Transfer Line - CR2 to J.P.	16811	1811	6x10MW		na	na
	Chillers Refrigeration - Drive Beam Injector S/U, Frequency Multiplication Circuit 1	8106	873				
	Chillers Refrigeration - CR1 S, CR2 S, Frequency Multiplication Circuit 2, 3, 4 and Transfer Line - CR2 to J.P.	1811	195				
	Accelerator - Klystron	na			24778	2669	
	Accelerator - LINAC		2000		27128	2922	
	Main Tunnel (other equipment)		3809		24149	2601	
	Injection Hall and Transfer Lines - e <sup>-</sup> /e <sup>+</sup> , Loop, J.P. to S.P. (P&ID Circuit B)	5931	639		5931	639	
2/3	Detectors S	900	97	8x10MW	900	97	8x14MW
	Detectors U	2043	220		2043	220	
	Chillers Refrigeration - Drive Beam Injector S/U, Injection Hall, Transfer Lines - Loop, J.P. to S.P. (P&ID Circuit A)	5311	572		3757	405	
	Chillers Refrigeration - Pre Damping Ring S/U, Injection Hall, Transfer Lines - Loop, J.P. to S.P. (P&ID Circuit A)	1317	142		4516	486	
	Main Beam Injector U	3886	419		3886	419	
	Main Beam Injector S	5126	552		5126	552	
	Booster S/U, Damping Ring e <sup>-</sup> S/U, and Transfer Line - Booster to J.P.	11205	1207		11205	1207	
	Pre Damping Ring S/U, Damping Ring e <sup>-</sup> S/U	8307	895	5x10MW	8307	895	5x10MW
	Chillers Refrigeration - Main Beam Injector S/U	2136	230		2136	230	
	Chillers Refrigeration - Pre Damping Ring S/U, Damping Rings e <sup>-</sup> , e <sup>+</sup> S/U, Booster S/U and Transfer Line - Booster to J.P.	4719	508		4719	508	
Total Cooling [MW]	154			129			



Not updated tables

❖ N+1 Redundancy for Cooling Towers & Pumps

Secondary Circuits, Demineralized Water					
Sector	Structure	Two Beam Machine		Klystron Machine	
		Cooling Power	Flow Rate	Cooling Power	Flow Rate
		kW	m <sup>3</sup> /h	kW	m <sup>3</sup> /h
1	Drive Beam Injector U	5356	577	na	na
	Drive Beam Injector S	14191	1529	na	na
	Frequency Multiplication Circuit a)	3238	349	na	na
	Frequency Multiplication Circuit b), CR1 S, CR2 S and Transfer Line - CR2 to J.P.	16811	1811	na	na
2/3	Accelerator - Klystron	na	na	24778	2669
	Accelerator - LINAC	18563	2000	27128	2922
	Main Tunnel (other equipment)	35365	3809	24149	2601
	Injection Hall and Transfer Lines - e <sup>-</sup> /e <sup>+</sup> , Loop, J.P. to S.P.	5931	639	5931	639
	Detectors S	900	97	900	97
	Detectors U	2043	220	2043	220
	Main Beam Injector U	3886	419	3886	419
	Main Beam Injector S	5126	552	5126	552
	Pre Damping Ring S/U, Damping Ring e <sup>-</sup> S/U	8307	895	8307	895
	Booster S/U, Damping Ring e <sup>-</sup> S/U, and Transfer Line - Booster to J.P.	11205	1207	11205	1207
Total Cooling [MW]	131		113		

Chilled Water Circuits					
Sector	Structure	Two Beam Machine		Klystron Machine	
		Cooling Power	Flow Rate	Cooling Power	Flow Rate
		kW	m <sup>3</sup> /h	kW	m <sup>3</sup> /h
1	Drive Beam Circuit 1	1952	336		
	Drive Beam Circuit 2	1413	243		
	Drive Beam Circuit 3	1413	243		
	Drive Beam Injector S and Frequency Multiplication Circuit 1	1458	251	na	na
	CR2 S, Frequency Multiplication Circuit 4 and Transfer Line - CR2 to J.P.	824	142		
	CR1 S and Frequency Multiplication Circuits 2,3	569	98		
2/3	Injection Hall, Transfer Line - Loop Circuit 1, J.P. to S.P.	555	96	555	345
	Transfer Line - Loop Circuit 2	115	20	115	71
	Detectors Hall U	118	20	118	74
	Detectors Hall S	225	39	225	140
	Main Tunnel	4085	704	5351	922
	4	Main Beam S/U Circuit 1	820	141	820
Main Beam S/U Circuit 2		412	71	412	256
Main Beam S/U Circuit 3		412	71	412	256
Booster S/U and Transfer Line - Booster to J.P.		944	163	944	587
Damping Rings S/U and Pre Damping Rings S/U		2686	463	2686	1670
Total Cooling [MW]		18		12	

## ➤ Piped Utilities



- ❖ Simplified P&IDs for sector 2 and 3
- ❖ Ventilation P&ID will be present in the PiP

**P&IDs are not updated**

## ➤ Ventilation Infrastructure

- Design Indoor Conditions
  - Deep Underground: 28°C, Dew Point < 12°C
  - Shallow Underground: 22°C, Dew Point < 12°C
  - Surface Buildings: 18°C during winter, 25°C during summer
- Design Outdoor Conditions
  - Summer: 32°C, 40% RH
  - Winter: -12°C, 90% RH


## ➤ Ventilation Infrastructure

- Operational Modes

Mode	Conditions
Run	No access, machines running, maximum air recycling
Purge	Before access where it is necessary, accelerator stopped, only fresh air
Shutdown	Open access, accelerator stopped, fresh air supply for people


## ➤ Ventilation Infrastructure

- Accelerator Gallery, Two Beam Machine



## ➤ Ventilation Infrastructure

- Accelerator Gallery, Klystron Machine



## ➤ Ventilation Infrastructure

- Other Areas

- BDS, Caverns, Dumps and Turnarounds
- Detectors Hall
- Injectors

- AHUs & EXUs at the surface when possible / underground otherwise
- Air transport by ducts

- Injectors Complex
- Transfer Lines
- Damping and Combiner

- AHUs & EXUs at the surface
- Push & Pull ventilation

- Surface Buildings

- AHUs & EXUs at the surface
- Air transport by ducts



# PiP Chapter



## ➤ Ventilation Infrastructure

Ventilation Infrastructure							
Structure	Two Beam Machine				Klystron Machine		
	Air-Handling Units				Air-Handling Units		
Name	N <sup>o</sup>	N <sup>o</sup>	Cooling Power	Flow Rate	N <sup>o</sup>	Cooling Power	Flow Rate
	-	na	kW	m <sup>3</sup> /h	na	kW	m <sup>3</sup> /h
Accelerator Gallery - LINAC	1	6	185	100532	8	193	104541
		4	93	50266			
Accelerator Gallery - Klystron	1	na	na	na	16	84	45775

Ventilation Infrastructure							
Structure	Two Beam Machine				Klystron Machine		
	Air-Handling Units				Air-Handling Units		
Name	N <sup>o</sup>	N <sup>o</sup>	Cooling Power	Flow Rate	N <sup>o</sup>	Cooling Power	Flow Rate
	-	na	kW	m <sup>3</sup> /h	na	kW	m <sup>3</sup> /h
Drive Beam Injector S	1	40	126	75270	na	na	na
CR1 S and CR2 S	2	4	107	63731			
Detectors Hall S	1	2	113	67164	2	113	67164
Injection Hall	1	2	108	64179	2	108	64179
Main Beam Injector S	1	9	99	58967	9	99	58967
Booster S	1	6	98	58509	6	98	58509
Damping Rings e <sup>-</sup> /e <sup>+</sup> S and Pre-Damping Ring S	3	2	106	63475	2	106	63475

Ventilation Infrastructure												
Sector	Structure	Two Beam Machine				Klystron Machine						
		Air-Handling Units				Air-Handling Units						
		N <sup>o</sup>	N <sup>o</sup>	Cooling Power	Flow Rate	N <sup>o</sup>	N <sup>o</sup>	Cooling Power	Flow Rate			
-	na	kW	m <sup>3</sup> /h	na	m <sup>3</sup> /h	na	kW	m <sup>3</sup> /h	na	m <sup>3</sup> /h		
1	Drive Beam Injector U	1	1	691	90730	3	90730	na	na	na	na	
		2	152	90730								
	Frequency Multiplication U	1	1	198	96716	1	96716	na	na	na	na	
		1	81	48358	1	48358	na	na	na	na	na	
		1	61	36269	1	36269	na	na	na	na	na	
		1	245	60448	1	60448	na	na	na	na	na	
	Transfer Line - CR2 to J.P.	1	1	152	67164	1	67164	na	na	na	na	
	2/3	Transfer Line - J.P. to S.P.	1	1	225	134328	1	134328	1	134328	1	134328
		Transfer Line - Loop	1	2	115	68657	2	68657	2	68657	2	68657
		Transfer Line - e <sup>+</sup>	1	1	0	16433	0	0	0	16433	0	0
Transfer Line - e <sup>-</sup>		1	1	0	24905	0	0	0	24905	0	0	
Detectors Hall U		1	1	118	64179	na	na	118	64179	na	na	
Main Beam Dumps		2	1	31	16561	na	na	1	31	16561	na	
Drive Beam Dumps		10	1	6	298	na	na	na	na	na	na	
Drive Beam Turnaround		8	1	11	597	na	na	na	na	na	na	
UTRA		8	1	104	56693	na	na	1	104	56693	na	
UTRC		2	1	104	56693	na	na	1	104	56693	na	
Caverns 1.3 and 1.4		2	1	104	56693	na	na	1	104	56693	na	
Survey Cavern 2.1 and 3.1		2	1	0	3000	na	na	1	0	3000	na	
Additional Caverns 2.2 and 3.2		2	1	165	89552	na	na	1	165	89552	na	
Service Cavern		2	1	104	56693	na	na	2	104	56693	na	
BDS		1	4	121	65923	na	na	4	121	65923	na	
Main Beam Turnaround e <sup>-</sup> /e <sup>+</sup> and Tunnel BC2 e <sup>-</sup> /e <sup>+</sup>		2	1	39	20896	na	na	1	39	20896	na	
BC2 Caverns		2	1	22	11940	na	na	1	22	11940	na	
LIT Pressurized Area	1	1	0	12000	na	na	1	0	12000	na		
4	Main Beam Injector U	1	1	524	68780	4	68780	1	524	68780	4	
		2	115	68780			2	115	68780			
	Booster U	1	2	101	60062	3	60062	2	101	60062	3	
	Transfer Line - Booster to J.P.	1	1	155	67164	1	67164	1	155	67164	1	
	Pre Damping Ring U	1	1	833	159185	1	159185	1	833	159185	1	
Damping Rings e <sup>-</sup> /e <sup>+</sup> U	2	1	607	203951	1	203951	1	607	203951	1		



Tables are not updated

- ❖ Redundancy is considered in the tables within the PiP and is generally required for AHUs & EXUs
- ❖ In the UTRAs/UTRCs there might not be redundant AHUs due to space constraints. Hence, in the table, they have not been considered




## ➤ Ventilation Infrastructure

- Safety
  - Smoke extraction where required
  - The ventilation system can be operated by the fire brigade
  - Smoke sensors will be placed before the supply fans in every AHU
  - Air monitoring equipment will be placed at the exhaust for radiation protection
  - The lift and stairs are pressurized
  - A pressure cascade will probably be implemented to avoid the migration of activated air from areas of high levels to areas with low levels of activation


## ➤ Cooling Power



## ➤ Cooling Power



## ➤ Cooling Power





# Future Work

---

- Cost estimate
- Numbers checking for consistency between teams
- CV detailed report
- Integration of CV infrastructures in the tunnels
- Further technical detailing

# Conclusions

---

- PiP is ready for delivery
- Solid technical solutions for both cooling and ventilation
- There is important work ahead that is relevant to validate and test the technical solutions
  - Integration exercises with CE and all the utilities
  - Temperature stability tests
  - ...

## Questions and Remarks



## Thank You for Your Attention