



<http://cern.ch/SLHC-PP>

## 1<sup>st</sup> Annual Meeting of



STFC-RAL, Didcot-UK, (13th) 14th - 16th April 2010

# Status of LHC upgrade plans and the SLHC-PP

Roland Garoby


15 April, 2010



This project has received funding from the European Community's Seventh Framework Programme (FP7/2007-2013) under the Grant Agreement n°212114




## Outline



1. LHC status
2. Projected LHC progress
3. LHC upgrade after 2020
4. SLHC-PP
  - Description
  - Status
  - Plans
5. Summary


# 1. LHC status



Turning-on the LHC is not trivial...




## The culprit (Sept. 2008)...





## Dipoles current supply scheme




**154 dipoles in series**

**Interconnection**

$L = 15 \text{ Henrys} \rightarrow \text{Time constant} \sim 100 \text{ s}$




## The result in sector 3-4





# Repair and consolidation work




15/04/2010

R.G.

7



# Repair planning in 2009




15/04/2010

R.G.





8




# First collisions at 7 TeV c.m. (30<sup>th</sup> March, 2010)



# First collisions at 7 TeV c.m. (30<sup>th</sup> March, 2010)



## 2. Projected LHC progress



Based on talks at the Chamonix 2010

“LHC Performance workshop”

<http://indico.cern.ch/conferenceDisplay.py?confId=67839>



## Near future: 2010

from M. Lamont

Step	E [TeV]	Fill scheme	N	$\beta^*$ [m] IP1 / 2 / 5 / 8	Run time (indicative)
1	0.45	2x2	$5 \times 10^{10}$	11 / 10 / 11 / 10	Weeks
2	3.5	2x2	2 - $5 \times 10^{10}$	11 / 10 / 11 / 10	
3	3.5	2x2*	2 - $5 \times 10^{10}$	2 / 10 / 2 / 2	
4	3.5	43x43	$5 \times 10^{10}$	2 / 10 / 2 / 2	Weeks/Months
5	3.5	156x156	$5 \times 10^{10}$	2 / 10 / 2 / 2	
6	3.5	156x156	$9 \times 10^{10}$	2 / 10 / 2 / 2	Months
7	3.5	50 ns - 144**	$7 \times 10^{10}$	2.5 / 3 / 2.5 / 3	
8	3.5	50 ns - 288	$7 \times 10^{10}$	2.5 / 3 / 2.5 / 3	Months
9	3.5	50 ns - 720	$7 \times 10^{10}$	2.5 / 3 / 2.5 / 3	

\* Turn on crossing angle at IP1.

\*\*Turn on crossing angle at all IPs.

One month: 720 bunches of  $7 \times 10^{10}$  at  $\beta^* = 2.5$  m gives a peak luminosity of  $1.2 \times 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  and an integrated of about  $105 \text{ pb}^{-1}$  per month  
[15% nominal – 28 MJ]



## Near future: 2011

from M. Lamont

3.5 TeV: run flat out at up to  $\sim 100 \text{ pb}^{-1}$  per month

	No. bunches	ppb	Total Intensity	$\beta^*$	Peak Lumi	Integrated Lumi [ $\text{pb}^{-1}$ ]
50 ns	432	7 e10	3 e13	2	1.3 e32	$\sim 85$
Pushing intensity limit	720	7 e10	5.1 e13	2	2.2 e32	$\sim 140$
Pushing bunch current limit	432	11 e10	4.8 e13	2	3.3 e32	$\sim 209$

**Either way should be able to deliver around  $1 \text{ fb}^{-1}$**



## Medium term: until 2015

from M. Lamont

- Two years at 3.5 TeV
  - 2010: should peak at  $10^{32}$  and yield up to  $0.5 \text{ fb}^{-1}$
  - 2011:  $\sim 1 \text{ fb}^{-1}$  at 3.5 TeV
  - **2012: splice consolidation (and cryo collimator prep.)**
  - 2013: 6.5 TeV - 25% nominal intensity
  - 2014: 7 TeV – 50% nominal intensity
- } Aggressive


Year	Months	Energy	$\beta^*$	$I_b$	$N_b$	Peak luminosity	Lumi / month	Int lumi / Year	Int. lumi cumul.
2010	8	3.5	2.5	$7 \cdot 10^{10}$	720	$1.2 \cdot 10^{32}$	-	0.2	0.2
2011	8	3.5	2.5	$7 \cdot 10^{10}$	720	$1.2 \cdot 10^{32}$	0.1	0.8	1.0
2012									
2013	6	6.5	1	$1.1 \cdot 10^{11}$	720	$1.4 \cdot 10^{33}$	1.1	7	8
2014	7	7	1	$1.1 \cdot 10^{11}$	1404	$3.0 \cdot 10^{33}$	2.3	16	24



## Projection until 2020

from M. Lamont

Pushing to nominal in 2016 and taking a couple of years to get to get to ultimate  
[potential to push phase 1 upgrade not included]




15/04/2010

R.G.

15




## 3. LHC upgrade after 2020



Based on talks at the Chamonix 2010 “LHC Performance workshop” <http://indico.cern.ch/conferenceDisplay.py?confId=67839>

+ report from Task Force on the LHC upgrade

(L. Rossi – 10/03/2010)



Generated tracks per crossing,  
 $p_t > 1$  GeV/c cut, i.e. all soft tracks removed!

15/04/2010

R.G.

16






# Luminosity vs $\beta^*$

from F. Zimmermann

$\langle L \rangle [10^{34} \text{ cm}^{-2} \text{ s}^{-1}]$



1. Beam intensity ( $N_b$ ) is more important than  $\beta^*$
2. Reducing  $\beta^*$  only helps when combined with Crab cavities or smaller emittances




# Luminosity leveling with $\theta_c$

from J.P. Koutchouk

$$\Delta Q_{bb} \propto L \text{ versus } \theta_c$$

Xing bumps + enlarged M's

Leveling may increase  $L_{int}$ !



studied in G. Sterbini's PhD

Crab Xing: minor optical side effects, challenge shifted to active HW and insertion design.

Early Separation Scheme: no optical side effects; not as efficient as crab Xing; passive and robust.

Xing bumps: probably not an option (constraints on max and min beam separation).

In all cases, initial reduction of the length of the luminous region



## Means to increase luminosity

from F. Zimmermann

- Upgrade scenarios with 25 & 50 ns spacing
- Maximum  $N_b \sim 2.3 \times 10^{11}$  at 25 ns,  $\sim 5.0 \times 10^{11}$  at 50 ns
- Minimize Turn around time:  $T_{ta} - 10 \rightarrow 2$  h: 2x higher  $\langle L \rangle$
- $\beta^*$ : factor 2 reduction  $\rightarrow$  10-20% higher  $\langle L \rangle$
- $N_b$ : factor 2 increase  $\rightarrow$  5 times higher  $\langle L \rangle$ !
- Crab crossing or lower emittance: 20-100% higher  $\langle L \rangle$
- Luminosity optimization assumes two IPs;  
needs/policy for ALICE & LHCb?
- $\theta_c$  leveling can increase run time by factor 1.5-3,  
& reduce pile up, at  $\sim$  constant  $\langle L \rangle$
- Annual luminosities may reach 150-300  $\text{fb}^{-1}$

$\Rightarrow$  Emphasis on  $N_b$  (!!),  $T_{ta}$  (!) and Crab crossing



## Critical R & D items

from L. Rossi

- ✓ High Field Quadupoles  
 $\Rightarrow$  reduced  $\beta^*$  and/or more radiation hardness
- ✓ 120 mm I.D. Nb-Ti models to proof design: in case  
Nb<sub>3</sub>Sn or Nb<sub>3</sub>Al will not perform sufficiently (part of risk  
mitigation / contingency plan)  
 $\Rightarrow$  reduced  $\beta^*$
- ✓ Crab Cavities  
 $\Rightarrow$  get higher luminosity from reduced  $\beta^*$
- ✓ SC cables for installing Power Converter on the  
surface and other means of rad-hazard mitigation  
 $\Rightarrow$  increased radiation hardness



## Accompanying measures

- ✓ Implement full performance collimation in LHC
  - ⇒ **increased beam current in the LHC to nominal and possibly beyond**
- ✓ Build, commission and operate Linac4 (~beginning 2015)
  - ⇒ **increased beam brightness at PS injection**
- ✓ Consolidate & upgrade the other injectors (increase PSB energy, upgrade PS and SPS)
  - ⇒ **increased beam brightness/intensity at LHC injection at minimum cost**
- ✓ Pursue SPL R & D focusing on high beam power
  - ⇒ **potential for application to other physics programmes as well**

15/04/2010


R.G.

21



LARGE HADRON COLLIDER UPGRADE  
<http://cern.ch/SLHC-PP>

## 4. SLHC-PP



### 18 partners

CERN (Switzerland), AGH-UST (Poland),  
CEA-Saclay (France), CIEMAT (Spain),  
CNRS-IN2P3 (France), CTU (Czech Republic),  
DESY (Germany),  
ETH-Zurich (Switzerland),  
FOM-NIKHEF (Netherlands),  
GSI (Germany),  
Imperial College (UK), INFN (Italy),  
PSI (Switzerland), STFC (UK),  
UBONN (Germany), UNIGE (Switzerland),  
USFD (UK), RWTH-Aachen (Germany)

The Preparatory Phase of the Large Hadron Collider upgrade (SLHC-PP) is a project co-funded by the European Community in its 7<sup>th</sup> Framework Programme [Grant Agreement n° 212114], CERN and 18 European research institutes and universities.

**Official starting date: 1<sup>st</sup> April 2008**

**Foreseen end date: 31<sup>st</sup> March 2011**

**Total cost: 15.571 MEuros / EU contribution: 5.2 Meuros**

The main aim of the Preparatory Phase project of the Large Hadron Collider upgrade (SLHC-PP) is to prepare the SLHC project for a decision on the approval of its implementation by 2011...

15/04/2010

R.G.

22



## Budget situation (February 2010)

# Participant	Max Total EC contribution	Prefinancing Received (2008)	Payment 1 (2009)	Total received to date	% received funds	Ceiling	To be paid to reach the ceiling
1 CERN	3,062,484.0	1,633,324.80	1,122,910.80	2,756,235.60	90%	2,756,235.60	-
2 AGH-UST	104,000.0	55,466.67	30,152.86	85,619.53	82%	93,600.00	7,980.47
3 CEA-Saclay	465,460.0	248,245.33	170,668.67	418,914.00	90%	418,914.00	-
4 CIEMAT	152,645.0	81,410.67	37,983.98	119,394.65	78%	137,380.50	17,985.85
5 CNRS-IN2P3	105,600.0	56,320.00	993.72	57,313.72	54%	95,040.00	37,726.28
6 CTU	44,940.0	23,968.00	16,478.00	40,446.00	90%	40,446.00	-
7 DESY	99,691.0	53,168.53	1,408.45	54,576.98	55%	89,721.90	35,144.92
8 ETH Zürich	89,131.0	47,536.53	32,681.37	80,217.90	90%	80,217.90	-
9 FOM-NIKHEF	64,200.0	34,240.00	23,540.00	57,780.00	90%	57,780.00	-
10 GSI	72,225.0	38,520.00	11,593.03	50,113.03	69%	65,002.50	14,889.47
11 Imperial	89,131.0	47,536.53	30,770.97	78,307.50	88%	80,217.90	1,910.40
12 INFN	40,000.0	21,333.33	14,666.67	36,000.00	90%	36,000.00	-
13 PSI	108,225.0	57,720.00	30,747.45	88,467.45	82%	97,402.50	8,935.05
14 STFC	489,850.0	261,253.33	76,351.76	337,605.09	69%	440,865.00	103,259.91
15 UBONN	120,000.0	64,000.00	44,000.00	108,000.00	90%	108,000.00	-
16 UNIGE	35,310.0	18,832.00	12,947.00	31,779.00	90%	31,779.00	-
17 USFD	32,100.0	17,120.00	11,770.00	28,890.00	90%	28,890.00	-
18 RWTH Aachen	25,000.0	13,333.33	9,166.67	22,500.00	90%	22,500.00	-
	<b>5,199,992.0</b>	<b>2,773,329.05</b>	<b>1,678,831.40</b>	<b>4,452,160.45</b>	<b>86%</b>	<b>4,679,992.80</b>	<b>227,832.35</b>

86% EC funds already received and distributed

Ceiling: EC retains 10% till end of the project



## Description

The activities are divided into 8 work packages, including one to coordinate the activities of the remaining 7.

Work package nb.	Type of activity	Description
W P 1	Management	SLHC-PP Project Management
W P 2	Coordination	Coordination for the SLHC accelerator implementation
W P 3	Coordination	Coordination for the S-ATLAS experiment implementation
W P 4	Coordination	Coordination for the CMS2 experiment implementation
W P 5	Support	Radiation protection and safety issues for accelerator and experiments
W P 6	RTD	Development of Nb-Ti quadrupole magnet prototype
W P 7	RTD	Development of critical components for the injectors
W P 8	RTD	Tracking detector power distribution



# Status WP1 & 2

## WP1: Project Management

Leader: R. Garoby (CERN)

- Coordination and financial follow-up of whole project
- Monitoring and reporting: organization of Annual meetings, edition of annual reports...
- Dissemination: Annual Public Meetings (next one on June 23 @ CERN), contribution to other events (e.g. ECRI, Barcelona, March 2010)...

## WP2: Coordination for SLHC implementation

Leader: T. Otto (CERN)

- sLHC Web site [<http://project-slhc.web.cern.ch/project-slhc/index.html>]
- Filing of information: new series for sLHC reports & project notes on the CERN Document Server, structured storage for all documentation (e.g. SPL) in EDMS, structured filing of all meetings (e.g. SPL) in Indico
- Development/implementation of upgraded EVM tool
- Preparation of Quality Assurance plan



# Status WP3

Leader: S. Stapnes (CERN)

## Coordination for S-ATLAS experiment implementation

- Establish management structure and review office for R & D
- Schedule R & D phase
- TDR and MoU for new "IBL" (approved project - phase 1)
- Lol for phase 2

### Organisation

- PO --> Open meetings, Joint with USG
  - All players present, much more efficient technical discussions
  - Open to all: very important to give all players a say
  - Allows input on things we are not aware of
- USG Enlarged
  - IBL rep plus separate Pixel rep
  - Germany now represented
  - French representation under discussion
- IBL: approved project
  - Project Leader (PL)
  - Technical Coordinator (TC)
  - Management Board
  - Sub-groups
  - Functioning well

### Organisation (cont.)

- Inner Tracker
  - Extra pixel person brought in to cover sLHC Pixels
  - Strips: Strengthened with one new person
  - Strips structure in place, but still some key positions not really covered
  - Pixels more focussed on IBL
  - Working on an Inner Tracker Management Board




# Status WP4

Leader: J. Nash (Imperial College)

## Coordination for CMS2 experiment implementation

- Establish project structures for construction and installation
- MoU and cost book
- Organize Technical Coordination
- Pilot design and schedule of upgrade project

### CMS Upgrade Project



J. Nash , SLHC-PP meeting  
Madrid (Feb. 2010)



# Status WP5


Leader: T. Otto (CERN)

## Radiation protection and safety issues (accelerators and experiments)

- Identification of crucial radioprotection issues
- Identification of critical areas for maintenance
- Assessment of radiological impact on personnel and environment
- Investigation of operative procedures of intervention
- Estimation of radioactive waste in terms of nature, amount and cost of elimination

⇒ Validation of simulation tools

⇒ Estimation of radiation levels in accelerators and experiments






## Development of Nb-Ti quadrupole magnet prototype

➤ Design, development, manufacture and test of a large bore (~130 mm diameter) NbTi quadrupole for the interaction regions of the LHC upgrade and corrector magnets

- ⇒ Challenges (Heat load, powering and protection, axial forces, collaring)
- ⇒ New features (Porous cable and ground-plane insulation, tuning shims)
- ⇒ Integrated design process (quench simulation, end-spacer design)







## Low- $\beta$ Quadrupole MQXC



- Coil aperture 120 mm
- Gradient 127 T/m
- Operating temp 1.9 K
- Current 13.8 kA
- WP on load-line 85%
- Inductance 5.2 mH/m
- Yoke ID 260 mm
- Yoke OD 550 mm
- Magnetic length 9160 mm (Q1,Q3)  
7760 mm (Q2)
- LHC cables 01 and 02
- Porous cable polyimide insulation
- Yoke OD identical to MB
- Self-supporting collars
- Single piece yoke
- Welded-shell cold mass



## Cable wrapping machine fully Commissioned






15/04/2010

R.G.




31



## Extraction of the Steady-State Heat-Load (Porous Ground-Plane Insulation)



Conventional ground insulation



Open KCS ground insulation

15/04/2010

R.G.



32






## End spacer design and manufacture

Differential Geometry Model



Virtual Reality Preview





Roxie-Catia Interface


CNC-Machining



Rapid Prototyping




## Vertical collaring – hardly possible for a 10 m long magnet!







## Horizontal collaring

Self-locking collars




Collaring Press



Assembly mandrel



## Planning of MQXC model magnet





### Development of critical components for the injectors

- To develop a test bed of the plasma generator of a high duty factor H<sup>-</sup> RF ion source
- To elaborate architecture, to specify components and to demonstrate performance of an RF system stabilizing properly the accelerating field in pulsed superconducting cavities




### Plasma generator for H<sup>-</sup> ion source

During the project second year:

Thermal issues that required solutions were detailed.

The plasma generator was completely redesigned in order to include cooling, and mitigate the effects of adding this.

It is now partially in production.





## Status WP7 – 3/6

from R. Scrivens (CERN)

Test area in preparation, demin water, gas, electricity updated.  
Vacuum system now installed.



15/04/2010

R.G.

39



## Status WP7 – 4/6



from G. Devanz (CEA)

Tuner and coupler characterization in Cryoholab (CEA-Saclay)

Designed & built  
within  
HIPPI (CARE –  
EU FP6)

The full system :

- Beta 0.47 5-cell
- 704 MHz cavity
- 1MW power coupler
- Magnetic shield
- Piezo tuner



15/04/2010

R.G.



40



# Status WP7 – 5/6

from P. Pierini (INFN)

## Special test stand at LASA (Milano) for evaluation of INFN tuner performance




Designed & built within HIPPI (CARE – EU FP6)



# Status WP7 – 6/6

from O. Piquet (CEA)

## Possible layout for the initial high energy part of LP-SPL



Analyzed and reported by O. Piquet (CEA-Saclay) during LLRF09 workshop



## Tracking detector power distribution

- To explore various DC-DC conversion options as well as serial powering schemes
- To select the most suitable schemes for integration into dedicated ASICs
- To test the scheme in full-scale S-ATLAS and CMS2 detector module prototypes.



## DC-DC conversion ASIC prototypes

Prototype	AMIS1	AMIS2	IHP1
ASIC			
Techno	AMIS 0.35	AMIS 0.35	IHP 0.25
Package	QFN48	QFN48 QFN32	QFN48 QFN32
PCB			
Vin	3.3V to 15V	3.3V-12V	2.5V to 12V
Vout	Programmable	Presets at 1.2/1.8/2.5/3/5V	Programmable
Iout	2A	3A	3A
Fsw	1 MHz	1 MHz	2.0 MHz
Efficiency	< 80%	82%	87%
Gate Delay	Fixed	Programmable	Adaptative
Comment	First Prototype. Required an external sawtooth generator and regulators.	Second Prototype. Programmable gate delay improves efficiency. Sawtooth generator integrated, still requires external regulator.	Third Prototype. Adaptative gate delay further improves efficiency.

3 ASIC Prototypes were produced:

### AMIS Technology:

- First sample with core DC/DC functions.
- Second sample, now fully functional.

### IHP technology:

- Fully functional DCDC.

Regulators for control circuitry are still external; they will be integrated in the next IHP sample (in production)




## System tests

Tracker modules have been powered successfully with DCDC prototypes.


### Emission of noise of DCDC :

- Noise measured in lab.
- Conducted noise strongly reduced now.
- DCDC emits E and H fields, that have been reduced but are still present.





### Susceptibility of hybrids

- Susceptibility measured at Liverpool hybrids setup.
- Hybrids were found to be sensitive to E and H fields, not sensitive to conducted noise.
- Shielding of DCDC will be required.
  - Thin foils are sufficient to limit the coupling.
- Susceptibility bandwidth characterized.



## Serial powering scheme: prototypes and test system

- 2 prototypes submitted and tested
  - September 2008, March 2009
  - $V_{out} = 1.2-1.5V$ ,  $V_{dropout} MIN = 200mV$ ,  $I_{shunt} MAX = 0.5A$ ,  $R_{in} = 4\Omega$ ,  $R_{out} = 30m\Omega$
- test setup
  - two SHULDO regulators connected in parallel on the PCB
  - biasing & reference voltage is provided externally
  - input & load current is provided by programmable Keithley sourcemeter
  - input & output voltages are measured automatically using a Labview based system
  - shunt current is measured by 10mΩ series resistors and instrumentation opamp






# Status WP8 – 5/6


## Serial Power Interface

Serial Power interface. Generic chip in 0.25 μm CMOS. Designed by M. Trimpl (FNAL), M. Newcomer, N.Dressnandt (Penn), specified by RAL.



- ● Two shunt regulator schemes
- Data communication/ AC coupling
- ● Power management
- Monitoring/alarms

SPI on test PCBs



- 68 I/O bumps
- 76 power bumps
- Minimum pitch 275 μm


11




# Status WP8 – 6/6

## System test of serial powering: the stavelets

ATLAS community stavelets are planned



- It allows comparison of different power configurations
- Different bus cable designs
- Different grounding and shielding concepts
- Stavelets early 2010, realistic stave 09 late 2010 ?
- Stavelets allow testing of different powering options




16





## 5. Summary



- LHC upgrade plans are being reconsidered, taking into account the “real” speed of progress of LHC performance
- As a result, the lifetime of the LHC will probably extend until ~2030
- R & D on crucial items is essential to allow for a full exploitation of the LHC potential for physics
- Although based on assumptions made in 2007-2008, the SLHC-PP remains a highly valuable contribution to the preparation of the LHC upgrade, participating to a good communication between accelerators and experiments.
- The SLHC-PP will terminate at the foreseen date in April 2011, fulfilling completely almost all of its objectives.
- The next step has to take due account of the new context, and especially of the early experience running the LHC.



**Thank you for your  
attention!**