


# *The deployment of ICARUS at SBN*

*A. Menegolli  
University and INFN Pavia (Italy)*

*on Behalf of the  
ICARUS Collaboration*




*Neutrino Town Meeting  
CERN - October 22<sup>nd</sup> 2018*





# ICARUS T600: a long journey in time and space!

- First proposed in a seminal paper by C. Rubbia in 1977.
- Long R&D effort by INFN, in collaboration with industry, culminating in the first large-scale LAr-TPC physics experiment: ICARUS-T600.



2001: T600 in INFN Laboratories in Pavia (Italy)



June-July 2017: from CERN to Fermilab







# The SBN project

$$L/E_\nu \sim 600 \text{ m} / 700 \text{ MeV} \sim \mathcal{O}(1 \text{ m/MeV})$$

**T600 also off-axis on NUMI beam:  
Asset for DUNE**



*Appearance: LSND 99%CL  
region covered at  $5\sigma$  in 3 yrs*



**FAR DETECTOR:  
T600 – 476 ton**

**3D MODEL**

110 m

TARGET



# The ICARUS collaboration



*Catania (INFN and Univ.)*

*GSSI*

*LNGS*

*INFN Milano Bicocca*

*INFN Napoli*

*Padova (INFN and Univ.)*

*Pavia (INFN and Univ.)*



*Brookhaven (BNL)*

*Colorado State*

*FNAL*

*Houston*

*Pittsburgh*

*Rochester*

*SLAC*



*Texas (Arlington)*





*Spokesman: C. Rubbia (GSSI)*

# T600 overhauling at CERN (WA104/NP01)


- To face the new experimental conditions at FNAL (shallow depth, higher beam rate) T600 underwent intensive overhauling at CERN (WA104/NP01), before shipping to US.
- Purely passive insulation coupled with standard N<sub>2</sub> cooling shield, redesigned and tested at CERN.
- New cold vessels made of extruded Aluminum profiles, welded together at CERN.
- Cathode panels flattened by thermal/mechanical treatment, reducing the residual non-planarity by a factor ~10.
- The new light collection system features 360 PMTs (90 per chamber, 15 phe/MeV) - [arXiv:1807.08577](https://arxiv.org/abs/1807.08577).



- Wire front-end electronics redesigned to improve reconstruction and performance - [arXiv:1805.03931](https://arxiv.org/abs/1805.03931).



# Warm Vessel & Cold shields (June 2018)



# Second Cold Vessel Rigging (August 14, 2018)






# Second Cold Vessel in place (August 14, 2018)



# ICARUS installation at FNAL - status

- Rigging of both modules and placement in the pit was done by August 2018.
- All chimneys installed on top of detector by mid September.
- Continuity tests carried out on all TPC wires soon after.



# ICARUS at FNAL – plans and commissioning

- Top side of cold shield is being installed followed by top of warm vessel.
- Cross flanges installation will start at the end of November.
- Activities on the top will begin during fall: cryogenics/purification/vacuum system, feedthrough flanges, read-out/decoupling boards, etc.)
- Vacuum pumping should start at the beginning of 2019, until TPCs are ready to cool down.

Commissioning will be then organized in three phases:

- **CRYOGENICS**: vacuum (1 month), cooling (15 days), filling (15 days), purification (1 month), stabilization (1 month).
- **TPC/PMT** (2 months): HV system, PMT supply, calibrations, DAQ/trigger commissioning.
- **Cosmic Ray Tagger** (in parallel with the other two phases).

*The strong cooperative effort by INFN, CERN and FNAL will allow to start commissioning and data taking in early 2019!*



Thank you!