

# **CERN** surface treatment infrastructure for RFD

L. Ferreira, N. Chritin, R. Ferreira, V. Gerbet et C. Paolo



#### **CERN** surface treatment infrastructure for RFD

#### Outline

DQW<sub>SPS</sub> surface treatment facility & data

RFD<sub>SPS</sub> surface treatment facility






# **DQW<sub>SPS</sub>** surface treatment facility & data



 $\mathsf{CRAB}\:\mathsf{DQW}_{\mathsf{SPS}}$ 



Bath outlet








# DQW<sub>SPS</sub> surface treatment facility & data

Determining BCP etch rate (T. Jones\_STFC, L.Ferreira\_CERN... SRF2017-TUPB100)

Values from a mock-up trial




CFD simulations predicted that within the foreseen working conditions (temperature and bath flow) the fluid dynamics inside cavity should be close to purely natural convection regime.






#### **DQW<sub>SPS</sub>** surface treatment facility & data









SPS CRAB RFD

 More complex shape compared with DQW (air/bath retentions)

Bath dynamics linked to bath density variation

Rotating bench






- Rotating bench
- Chemical plant
- Automatic control of the installation:
  - Rotating bench: Tilting and rotation movement
  - Chemical plant: Valves, pumps, cooling & instrumentation
  - Interlocks (process and operator safety)

The whole installed in building 118





# Rotating bench



Present Status: Final design by contractor


Frame: S. Steel

Piping/Interfaces: PVDF, PFA, PTFE & FKM





Chemical plant



Present Status: Completing the technical specification for price enquiry. Out in November.

Piping: PVDF, FKM, SiC & PFA





# **Planning**

Item	Delivery	Commissioning
Rotating bench	April 2019	April 2019
Chemical plant	Up to Mai 2019	June 2019
Automatic control	Up to April 2019	June 2019
Process tests & optimisation	-	July-Sep 2019







#### Thank you for your attention

Credits to:



Riccardo Peron\_EN/MME: Drawing office