

# Review of the current underground space at completion of CF

Douglas Pelletier, CF Project Manager

22 August 2018

## Outline


- High level overview of Arup 30% Final EXC Underground Design
  - Major Changes from Preliminary Design
- High level overview of Arup 30% Final BSI Underground Design
- Review remaining deliverable dates and review periods
- Preliminary Excavation Sequence animation


## Major Changes from EXC 100% Preliminary Design

- Removal of septum in North and South Caverns and shortening of the overall caverns in line with F10043159 Rev C.
- Centered Center Access Drifts with respect to the north and south caverns, and moved the Central Utility Chamber so that the alignment with these drifts remains as in the 100% PD
- Removal of the Maintenance Shop, High Voltage Electrical Room and the LV/MV Electrical Room, and enlargement of the Trolley Drift to form the Electrical Substation, in line with the recommendations of the Underground Electrical Substation Relocation Study, 7/14/2016.
- Drift geometry has been updated in line with the Drift Optimization Study, 4/14/2016.


## Major Changes from EXC 100% Preliminary Design

- Modified the location of Ventilation Raise Access Chamber, the Ventilation Raise, and the Spray Chamber location and length.
- The ‘mucking drifts’, which are provided for construction use only, have been modified to avoid impacting the waste pass in the existing trolley drift and minimize the overall excavation volume.
- Mucking drifts have been maintained to the 4910 Level at the base of the caverns, but the connection to the east has been removed as it is no longer needed with the revised construction phasing.
- Refined Ross Brow and junction geometry.
- Yates Brow removed from scope.





# Arup 30% Final EXC Design



NOTES:  
1. FOR GENERAL NOTES AND ABBREVIATIONS, REFER TO DRAWING UG-FD-C-001.

| REV | DATE     | DESCRIPTION       |
|-----|----------|-------------------|
| 1   | 07/13/18 | OWN PD SUBMISSION |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |
|     |          |                   |

**ARUP**  
ARUP Ltd  
175 Bishop Street, New York NY 10038, 1-212 866-0000  
www.arup.com

**McMILLEN JACOBS ASSOCIATES**  
McMILLEN JACOBS ASSOCIATES  
1000 15th Street, Suite 1000, New York, NY 10019  
www.mja.com


**consulting**  
consulting

|        |
|--------|
| SCALE: |
|        |
|        |
|        |
|        |
|        |
|        |
|        |
|        |
|        |


|   |    |      |
|---|----|------|
| <b>Fermilab</b><br><small>Long-Baseline Neutrino Facility</small> |    |      |
| DESIGNED  | AV | ARUP |
| DRAWN   | ES | ARUP |
| CHECKED   | JH | ARUP |

|                                 |         |             |
|---------------------------------|---------|-------------|
| <b>LBNF - FSCF - EXCAVATION</b> |         |             |
| <b>ISOMETRIC VIEW</b>           |         |             |
| DRAWING NO.                     | 15-1-6F | UG-FD-C-105 |
| REV.                            | 1       | 08/24/18    |

# Arup 30% Final EXC Design



# Arup 30% Final EXC Design




## NOTES:

1. FOR GENERAL NOTES AND ABBREVIATIONS, REFER TO DRAWING UG-FD-C-001.
2. DIMENSIONS INDICATED ARE TO INNER FACE OF SHOTCRETE.
3. FOR GROUND SUPPORT DETAILS, REFER TO DRAWING UG-FD-C-003.
4. CONCRETE FOR CAVERN INVERT SHALL HAVE MINIMUM COMPRESSIVE STRENGTH OF 5000 PSI.
5. FOR CONCRETE SLAB OVER DRAINAGE LAYER DETAILS, REFER TO DRAWING UG-FD-C-002.

|  |   |  |                 |
|--|---|--|-----------------|
| <p>7/15/2015 4:00:35 PM</p> <p>ARUP</p> <p>77 Water Street, New York, NY 10038, T 212 904 3000</p> <p>McMILLEN JACOBS ASSOCIATES</p> <p>consulting</p> | <p>PROJECT NORTH</p> <p>SCALE: 1" = 20'-0"</p> <p>DESIGNED: SP ARUP</p> <p>DRAWN: ES ARUP</p> <p>CHECKED: JH ARUP</p> | <p>Long-Baseline Neutrino Facility</p> <p>LBNE • FSC • EXCAVATION</p> <p>4850 LEVEL</p> <p>NORTH CAVERN</p> <p>PLAN AND PROFILE</p> <p>DRAWING NO. 15-1-6F UG-FD-C-200 REV 1</p> | <p>07/15/15</p> |
|--|---|--|-----------------|

# Arup 30% Final EXC Design



**NOTES:**

1. FOR GENERAL NOTES AND ABBREVIATIONS, REFER TO DRAWING UG-FD-C-001.
2. FOR CRANE BEAM DETAILS, REFER TO DRAWING UG-FD-SS-132.
3. DIMENSIONS INDICATED ARE TO INNER SURFACE OF SHOTCRETE.
4. FOR ROCK REINFORCEMENT DETAILS, REFER TO DRAWING UG-FD-C-000.
5. CONCRETE FOR CAVERN INVERT SHALL HAVE MINIMUM COMPRESSIVE STRENGTH OF 5000 PSI.
6. FOR CONCRETE SLAB OVER DRAINAGE LAYER DETAILS, REFER TO DRAWING UG-FD-C-002.

7/13/2018 4:00:41 PM

| REV | DATE     | DESCRIPTION       | REVISIONS |
|-----|----------|-------------------|-----------|
| 1   | 07/13/18 | OWN PD SUBMISSION |           |

**ARUP**

ARUP USA INC.  
1710 Avenue of the Americas  
New York, NY 10019, U.S.A.  
www.arup.com

**McMILLEN  
JACOBS  
ASSOCIATES**

**consulting**

SCALE:



**Fermilab**  
Long-Baseline Neutrino Facility


|          |    |      |
|----------|----|------|
| DESIGNED | SD | ARUP |
| DRAWN    | ES | ARUP |
| CHECKED  | JH | ARUP |

**LBNF - FSCF - EXCAVATION**  
**4850 LEVEL**  
**DETECTOR CAVERNS**  
**INVERT PLAN & ISOMETRIC**

DRAWING NO. **15-1-6F** **UG-FD-C-202** REV. **1**


07/13/18 08:26:15

# Arup 30% Final EXC Design




**TYPICAL ISOMETRIC VIEW**

SCALE: N.T.S.




# Arup 30% Final EXC Design



# Arup 30% Final EXC Design

## NOTES:

1. FOR GENERAL NOTES AND ABBREVIATIONS, REFER TO DRAWINGS C-001 AND C-002.
2. DIMENSIONS INDICATED ARE TO INNER SURFACE OF SHOTCRETE.
3. FOR ROCK REINFORCEMENT DETAILS, REFER TO DRAWING C-600 AND C-601.
4. SHOTCRETE SHALL BE REINFORCED WITH A SINGLE LAYER OF 6" x 6" - W4.0M4.0 WELDED WIRE FABRIC ON THE CROWN AND WALLS OR MACROSYNTHETIC FIBERS AT SUFFICIENT DOSAGE TO MEET THE PERFORMANCE CRITERIA GIVEN ON DRAWING C-002 IN TABLE 1.
5. A GEOTEXTILE DRAINAGE STRIP SHALL BE PLACED BEHIND THE SHOTCRETE AT SPECIFIED INTERVALS OF 16 FT. (5m). REFER TO DRAWING C-601 FOR DETAILS.
6. ADDITIONAL GROUND SUPPORT SHALL INCLUDE SPOT BOLTS, MINE STRAPS, AND SHOTCRETE TO STABILIZE LOCAL GROUND CONDITIONS NOT ADDRESSED BY THE GLOBAL GROUND SUPPORT.
7. ROCK REINFORCEMENT OMITTED FOR CLARITY ON PLAN AND ISOMETRIC VIEWS.
8. SHOTCRETE SHALL BE APPLIED TO ALL EXPOSED SURFACES AFTER MAPPING AND BOLTING OF EACH ROUND, PRIOR TO NEXT ROUNDING.
9. ROSS SHAFT BROW DOVELS TO BE INSTALLED AS CLOSE TO PERPENDICULAR AS POSSIBLE TO ROCK SURFACE, BUT NOT GREATER THAN 15° OFF AXIS.




**LONGITUDINAL SECTION**

SCALE: 1"=10'-0"

### BROW DIMENSIONS

| LENGTH (ft) | HORIZONTAL LENGTH (ft) | VERTICAL LENGTH (ft) |
|-------------|------------------------|----------------------|
| OA 10.2     | OA 10.2                | OA 0                 |
| OB 14.2     | OB 10.2                | OB 9.9               |
| OC 14.5     | OC 8.1                 | OC 12                |
| OD 12       | OD 3                   | OD 12                |
| OE 14.5     | OE 8.1                 | OE 12                |
| OF 16       | OF 13.4                | OF 6.7               |
| OG 16.7     | OG 16.7                | OG 0                 |

| COORD (ft) |
|------------|
| AB 9.9     |
| BC 3       |
| CD 6.1     |
| DE 8.1     |
| EF 7.5     |
| FG 7.5     |




**SECTION +100 FT**

SCALE: 1"=10'-0"

**SHAFT +105.9 FT**

SCALE: 1"=10'-0"




**SHAFT +129.9 FT**

SCALE: 1"=10'-0"

**SHAFT +132.9 FT**

SCALE: 1"=10'-0"



**SHAFT +151.1 FT**


SCALE: 1"=10'-0"

**SHAFT +151.1 FT**


SCALE: 1"=10'-0"

|                                |  |                             |  |   |  |
|--------------------------------|--|-----------------------------|--|---|--|
|                                |  |                             |  | <b>LBNF - FSCF - EXCAVATION</b><br><b>4850 LEVEL</b><br><b>ROSS SHAFT BROW</b><br><b>SHEET 2 OF 2</b> |  |
|                                |  |                             |  | <b>15-1-6F UG-FD-C-218</b>  |  |
| <b>DESIGNED</b> AV <b>ARUP</b> |  | <b>DRAWN</b> ES <b>ARUP</b> |  | <b>REVIEWED</b> JH <b>ARUP</b>  |  |
| <b>DATE</b> 07/13/16           |  | <b>SCALE</b> 1"=10'-0"      |  | <b>REV</b> 1  |  |

# Arup 30% Final EXC Design



# Arup 30% Final EXC Design




**MEZZANINE SUPPORT CROSS SECTION**

SCALE: 3" = 1'-0"

3

# Arup 30% Final EXC Design



Arup added distribution beam to avoid single point failure issues, under re-evaluation.

**MEZZANINE HANGAR CROSS SECTION**

SCALE: 3\"/>


4

## Steel:

# Arup 30% Final BSI Design

## Experiment Cavern Utility Support:

- New supports on Cavern Walls 6'-6" OC (2m)
- Loading per frame:
  - 2800# Cryo Piping
  - 1100# Cable Tray




# Arup 30% Final BSI Design

## Septum Bridge (not in 30% but):

- Concept Study Ongoing
- Approx. Girder Depths – limited to 4ft including bridge deck due to crane constraints
- Rolled sections with splices likely to be most economic.
- If we can revisit hook clearance we can make more economic

### Top Running Crane

The bridge of a top running crane is designed to travel on rails that are mounted onto the runway beams. The beams can be supported by either precisely engineered free-standing columns or by the existing columns of the building.




### Under Running Crane

The bridge of an underhung crane is engineered to travel on the bottom flange of a runway beam. The roof structure of a building typically supports the runway beam in this type of configuration.



W40 bridge girder plus approx. 9" thk. concrete Deck on dovetail decking




## Rerouted Piping




# Arup 30% Final BSI Design

## Additional Chiller




## Arup 30% Final BSI Design

### Substation Room 3D View



# Arup 30% Final BSI Design

## Coordination Challenges



1. Space Constraints
2. Ductwork Clearances
3. Spray Chamber

## Remaining Final Design Deliverables

- 60% EXC due October 5, 2018
- 60% BSI due October 19, 2018
- 60% comments due 3 weeks after delivery, Design is Frozen at this point
- 90% EXC due January 11, 2019
- 90% BSI due January 25, 2019
- 100% EXC & BSI due March 29, 2019 (Issued for Construction Procurement)

# Preliminary Excavation Sequence prepared by KAJV (Disregard dates)

1/15/2021

Week: 59



| Name   | Start      | Finish        | 2021  |       |       |       | Jan 2022 |        |        |        |        |
|--|------------|---------------|-------|-------|-------|-------|----------|--------|--------|--------|--------|
|  |            |               | Dec   | Apr   | Jul   | Oct   | Jan      | Apr    | Jul    | Oct    |        |
|  |            |               | wk 57 | wk 70 | wk 83 | wk 96 | wk 109   | wk 122 | wk 135 | wk 148 | wk 162 |
| MOBILIZATION: Prep "Production" Equipment for Hoisting | 12/15/2020 | 3/9/2021      |       |       |       |       |          |        |        |        |        |
| Milestone: Option 1A Completion                        |            | 1/15/2021 (*) |       |       |       |       |          |        |        |        |        |
| Milestone: Option 1B NTP for Construction              | 1/15/2021  |               |       |       |       |       |          |        |        |        |        |
| Mobilize to 4850 Level                                 | 1/15/2021  | 1/22/2021     |       |       |       |       |          |        |        |        |        |