

BEAM COMMISSIONING OF LINAC4 at CERN

Giulia Bellodi for the LINAC4 Team

MYRRHA, 7th WP2 MYRTE Meeting, CERN, Geneva, 22-24 October 2018



Outline



- LINAC4 layout and choices
- Commissioning results
- Reliability and beam quality run
- Conclusions and outlook


LINAC4

4) II-mode Structure
 100-160 MeV
 23 m
 12 Modules
 8 Klystrons: 12MW
 12 EMQ
 12 steerers

3) Cell-Coupled Drift Tube Linac
 50-100 MeV
 25 m
 7 Modules
 7 Klystrons : 7 MW
 7 EMQ + 14 PMQ
 7 steerers



2) Drift Tube Linac
 3-50 MeV
 19 m
 3 Tanks
 3 Klystrons : 5 MW
 1 EMQ
 2 steerers
 114 PMQ

1) Preinjector
 3 MeV
 Source(s)
 2 solenoids
 RFQ
 11 EMQ
 3 Cavities
 2 Chopper units
 dump




Frequency : 352 MHz
 Duty cycle for PSB : 0.06 %
 Max duty cycle : 5%

Located 12m underground



LINAC4 from 2000's to 2020



Staged commissioning

Low energy test bench at 3 MeV and 12 MeV

Direct measurements

- Transverse emittance with slit-grid
- Energy spread with a bending spectrometer

High energy test bench at 50 and 107 MeV

Indirect measurements

- Transverse emittance with 3 profile monitors
- Longitudinal emittance with bunch shape monitor
- Energy with Time-of-flight

Permanent measurement line in the transfer line for 160 MeV



ion source

RFQ

chopper line

Diagnostics line

spectrometer


beam dump

Extensive measurements at 45 keV



Measurements
varying
solenoidal field
& generate
beam
distributions

Back-track to the
source output





We have an **empirical input beam distribution** that very well represents the dynamics in the LEBT and the rest of the accelerator

Pre-injector: validation of diagnostics





rms normalised
transverse
emittance @ 3 MeV
measured by 3
independent
systems:
0.3 pi mm mrad



Slit-and-grid



From profile measurement



Laser + diamond



November 2016: the final energy is reached!




Nov 2016
160 MeV

Jun 2016
105 MeV

Nov 2015
50 MeV

Oct 2013
3 MeV
27 mA



45 keV
50 mA



- Commissioning in stages is key to swift commissioning!
- Commissioning time ~3-4 weeks per stage >> HW-checkout + Beam commissioning!
- Good beam dynamics combined with good beam diagnostics is key
- Good understanding of beam characteristics at low energy essential

Commissioning lessons



Simulation tools are good guide dogs

Starting the 50 MeV commissioning stage -> low transmission



Advantage of staged commissioning:

- Everything up to DTL1 was commissioned
- Hot-point at DTL3 entrance (radiation measurement)
- Plus beam dynamics simulations

Allowed us to understand that last DTL2 PMQ and first DTL3 PMQ were accidentally inverted
Beam restarted after 3 days...

Reliability/Beam Quality Run (July 17 - May18)

Rationale & Goals

1. Ensure a smooth transition from commissioning to operation: train operators, necessary software development, learn to deal with the increased flexibility, *gain experience with the full system*.
2. Find any weak points and mend them in time for the connection
3. Achieve a *beam-availability* for the PSB as high as possible and possibly above 90% : importance of the *fault tracking system*


2017												2018											
1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Shut down	Half Sector Test	Debuncher installation	Reliability Run									Shut down	Spare for Reliability Run	interventions, repairs						Beam recommissioning	Shut down		
EYETS												shutdown								LS2			

Failure analysis

LINAC4 run 24/7 in parallel to normal operation on **best-effort basis** with:


- ❖ Operators deal with issues where possible
- ❖ **Expert** availability and interventions **only during working hours**
- ❖ Faults are fully tracked (Accelerator Fault Tracker AFT)
- ❖ Stop AFT Clock during off-hours when fault needs expert intervention & during MDs

Thorough logbook verification w/ Timber/LASER information



$$Q = \frac{\text{Logged fault time}}{\text{Effective Operation}}$$

Criterion for LINAC4 availability: Current in BCT before the dump




Availability data

Period: 13/07/2017 – 15/05/2018


Last update: 05/06/2018

Availability	Fault Count	Operation	Suspended OP	Effective Operation	Fault Mean Time to Repair
91.5%	449	23 weeks	~ 8 weeks	~15 weeks	~29 min



Week 47: Anode module change 2x, Pre-Chopper connector to feedthrough to vacuum


Root Cause Downtime by system




Availability data

Period: 13/07/2017 – 15/05/2018

Last update: 05/06/2018



Fault counts / week
(not including parallel faults)




Mostly short faults < 15'

Beam quality run 2018

- 12 weeks of beam quality run spring 2018
 - ❖ Extensive HW checkout, RF setup and beam re-commissioning after YETS activities
 - ❖ Measurements of beam quality & characteristics

Beam pulse shape



RF setup 2018


Via beam-loading measurements:

Initial setup: automatic phase scan of each cavities with beam loading measurement. Offline analysis to fit the data.

Via energy measurements (ToF technique):



Fine tuning of the setting points.
TOF application validated, human discernment needed for correct data interpretation + offline analysis / fits.

Average energy vs cavity phase



ToF sufficiently precise to allow setting each RF cavity to:
 $\pm 0.5\%$ in amplitude
 $\pm 0.5^\circ$ for the phase

Beam quality measurements - current




Beam quality measurements – stability at 160 MeV

Current/position stability along pulse


H/V position on
L4T pick-up

✓ $< \pm 1\text{mm}$




Beam intensity on
L4Z BCT (3 rings)

✓ $< \pm 2\%$



Beam quality measurements - chopping




Chopping pattern for typical LHC pulses for PSB

Beam quality measurements – longitudinal shape




Beam Shape Monitor Commissioning

BSM1



Caterpillar beam

BSM2



LINAC4: measured beam characteristics




Parameter	Measurement
Peak intensity at 160 MeV	25 mA
Emittance rms normalized	0.3 p mm mrad
Max usable pulse length	600 ms
Stability shot-to-shot	2%
Pulse flatness	2% for 160ms pulse 5% fpr 600ms pulse
Beam position jitter along the pulse at the linac dump	+/- 1mm
Fast Chopping at 3 MeV	Rise time < 10ns Extinction factor close to 100% Unprecedented flexibility: beam 1- 600 ms

Conclusions and outlook



- Reliability run proved very useful experience allowing to identify issues beyond the possibilities during pure commissioning
 - ❖ Number of teething problems identified, strategies for mitigation for implementation in 2018
 - ❖ Gain further experience with a complex system
 - ❖ Run time used to measure and improve performance
 - ❖ Identification of areas that need strengthening
- Demonstrated reliable operation of the LINAC4 line to the dump
 - ❖ Most of LINAC4 beam requirements demonstrated (stability, flatness, chopper specifications etc)
 - ❖ Confidence in running LINAC4 after LS2 strengthened
- Transition from Commissioning to Operation ongoing
- More general
 - ❖ Importance of a teststand that includes the full pre-injector and staged commissioning
 - ❖ Importance of a validated machine model and accuracy of particle tracking codes
- Outlook
 - ❖ 2018: 3 months re-commissioning after scheduled RF upgrade and maintenance activity
 - ❖ 2019: 3 months running with LBE line (emittance measurement)
 - ❖ After LS2: LINAC4 sole provider of protons for the whole CERN complex

Thank you for your attention



Transverse emittance at higher energies

Transverse emittances were indirectly measured with:


- the “**Forward method**”
- the “**Hybrid Tomographic method**”

Both based on: The 3 profiles method – Including the space charge forces with multi-particle simulation codes.




@ 50 MeV

@ 107 MeV



Expected
from
simulations



Measured




Half Sector Test (Nov '16 – March '17)



1 μm thick carbon foil (24x68mm)

Beam transverse footprint – stripped – 160 MeV at BTV1077, March '17



Goals:

- Run the beam through half the injection chicane with the aim of mitigating risks for future PSB H⁻ Injection Section – as connection schedule is very tight.
- Improve handling and procedures/ gather operational experience
- Debugging and improvement of beam instrumentation/ Sensitivity measurements
- Stripping efficiency measurements with BCTs & H⁰/H⁻ monitor



Beam quality measurements





Current/position stability along pulse

Beam Shape Monitor Commissioning



BSM1



Caterpillar beam



BSM2



2018 16:14:5

DMP LINDMF

LTB BI

10 Gy/

10

0.0

PMS

TH

LINAC4: A new injector for the CERN proton complex

LINAC2	LINAC4 – CDR -2006	LINAC4 – achieved (2017)	
protons	H-	Stripping and more tested in Half Sector Test	
160 mA	70mA peak at the source 65 mA peak at 3 MeV 40 mA after chopping	50mA peak (in twice the acceptance of the RFQ) 27 mA peak at 3 MeV 20 mA after chopping	Peak current from the source Average beam current after chopping (LEBT and RFQ transmission and chopping factor)
50 MeV	160 MeV	160.48 MeV	All RF structures performing to specs
1 π mm mrad	0.4 π mm mrad	0.3 π mm mrad (at 160MeV)	Smaller emittance , allows for more turns injected
100 μ sec 1Hz	400 μ sec 1Hz (4 rings)	Up to 600 μ sec 1Hz	Longer injection in the PSB (100-150turns)
200 MHz/ 40 m	352 MHz / 80 m		RF frequency that is not widespread anymore. No components “off the shelf”
-	Fast Chopping at 3 MeV 2 μ sec inj kicker rise-time	Demonstrated , including transmitted beam quality	Unprecedented flexibility, to be exploited Beam from 1 μ sec to 150 μ sec
-	Energy painting with the last accelerating modules	Not yet tested	

The 3 MeV pre-injector




45 keV H⁻ ion source – Cesiumated

Delivering stably a 50 mA beam (27 mA within RFQ acceptance).
Further optimisation on-going in a dedicated test stand.

352.2 MHz RFQ


3 m long structure.
Designed and manufactured at CERN.
Reliable operation since 2013.



MEBT with fast beam chopper

3.5 m long matching line from RFQ to DTL
Fast and efficient beam chopping:

- Risetime < 10ns
- Extinguish factor 100%



The accelerating structures




Drift Tube Linac – 3 - 50 MeV

PMQs in vacuum – FFDD focusing scheme
Designed for > 30 years reliable operation at 10% duty cycle
Adjust and Assemble philosophy: Tight tolerance aluminium girder



Cell-Coupled DTL – 50 - 102 MeV

Construction by BINP and VNIITF in Russia.
7 modules x 3 cavities x 3 gaps.
PMQs located in between cavities.
First-ever CCDTL in a working machine !



Π Mode Structure – 102 - 160 MeV

Collaboration with NCBJ and FZ-Jülich.
Discs and rings were tuned and electron-beam welded at CERN.
Long qualification period for series production: 10-20 μm on 500 mm diameter pieces
First low-beta PIMS on an operational machine.




Setting the RF cavities: time-of-flight


Most of the RF cavities settings are found with Time of Flight

- 17 Beam position monitors from 12 to 160 MeV (for 22 cavities)

DTL tank 3




Average energy vs cavity phase



CCDTL module4

PIMS cavity 1



ToF sufficiently precise to allow setting each RF cavity to:

- $\pm 0.5\%$ in amplitude
- $\pm 0.5^\circ$ for the phase

Increasing β & Decreasing number of gaps per cavity

