

GIF++ INSTALLATION IN THE EHN1/H4 BEAM LINE

- ❑ Layout – the Cs¹³⁷ 10TBq source
- ❑ GIF++ organization
- ❑ Schedule

CAPEANS GARRIDO, M – FORTIN, R (PH/DT)

REMBSER, C – (PH/ADE)

EFTHYMIPOULOS, I (EN/MEF)

GIF++ in H4 beam line

2

Introduction

- **GIF** : is a **G**amma **I**rradiation **F**acility
 - ▣ use a powerful source (Cs137, Co60) to irradiate detectors or other equipment for performance, or ageing studies
 - ▣ strong point: presence of a particle beam to check detector performance, i.e. particle identification, on top of a photon background

- **++** : means upgrade wrt present installation in b.190
 - ▣ more powerful source in view of sLHC needs
 - ▣ bigger and better organized irradiation area to cover all needs

- Present installation phased out due to the dismantling of the West Area → no beam !

- Users: all gaseous detector builders (LHC & FT experiments, machine instrumentation) plus groups related with radiation studies (EN/STI, RP,...)


-

- If coupled with a neutron source would be a unique facility
 - ▣ could also cover the needs of accelerator installation (R2E)

GIF++ in North Area/H4 beam line


3

Implementation proposal



GIF++ in North Area/H4 beam line

4 Implementation proposal




GIF++ in North Area/H4 beam line

5

Implementation proposal

Roof shielding of
0.8m concrete over
the irradiation area



GIF++ : The Cs¹³⁷ Source

6


RP considerations – (Heinz Vincke)

- **Cs¹³⁷, 10 TBq**
 - ▣ × 13 than present GIF source
 - ▣ half life 30 years
 - ▣ Radiation field : photons of 662 keV (85.1%)
 - ▣ ~1 Sv/h at 1m


Max. expected doses at sLHC	Equivalent time at GIF++ (~ 50 cm from source → 2Gy/h)
Si-trackers: ~ MGy/y	>> years
Calorimeters: ~ 20 kGy/y	< 1 year
Muon systems: ~ 0.1 Gy/y	~ minutes

- The irradiation area will be classified as **prohibited area**
 - ▣ at 30cm distance from the source we have ~10 Sv/h, i.e. 1000 times the limit of a prohibited area
 - ▣ adequate side and roof shielding is required
- EHN1 is a **Supervised Radiation Area** (new limits since 2006)
 - ▣ < 3 uSv/h at permanent workplaces (was 25 uSv/h)
 - ▣ < 15 uSv/h in low occupancy areas (was 100 uSv/h)

These are the limits to achieve outside the shielding



Lateral view of Source and Beam



Top view of Source and Beam

GIF++ Facility

7

The irradiator assembly





Fig. 3. Vertical cut showing beam, source and filters: (1–3) filters; (4) rod with source at lower end is lifted to place the source in irradiation position; (5) radiation monitor; (6) source; (7) lead housing of source and (8) concrete.



- The irradiator will be purchased as a “box” with all the functionalities and control software included - specs by DG/SCR
- The front filters will be recuperated from existing GIF; we may construct some new ones if needed
- Yearly maintenance by constructor – organized by DG/SCR radioactive source service

GIF++ Facility



GIF++ Construction

9

Status - schedule

- A Proposal was submitted to SPSC in September
 - ▣ CERN-SPSC-2009-029 ; SPSC-P-339
 - ▣ <http://cdsweb.cern.ch/record/1207380/files/SPSC-P-339.pdf>

- **SPSC referees : S. Maury (CERN) + M. Charlton(UK)**
 - ▣ Discussions with proponents and MEF
 - ▣ Main issue: beam time (6-8 weeks/year) and likely re-activation of CMS calorimeter test area – downstream from GIF++


- **On positive recommendation from SPSC (rather likely) it will be brought to the RB for approval**

- We are in a typical round loop: users want CERN approval to start investing money on the project ↔ their funds would ease the approval

GIF++ Construction

10

Tentative schedule



GIF++ Facility

11

Organization – specific tasks

- **EN-MEF group**
 - Overall coordination and management
 - Maintenance of the GIF++ exp. Area and installed equipment
 - Assistance to the users for the installation and integration of their equipment
 - Optimization of required beam conditions
 - Maintenance of the fixed gas supply installations
- **PH-DT**
 - Assistance and liaison with users on a day-to-day basis
 - Maintenance of the detector control system of the facility
 - Maintenance of the gas mixing and purification plants, shared among the users
 - Follow up the annual maintenance of the ^{137}Cs source by a competent external firm
 - TSO of the facility
- **DG-SCR group**
 - Monitoring of all ionizing radiation in the area in view of safety regulations
 - Radiological risk assessments in view of different test conditions
- **Users**
 - Responsible for their specific detectors and peripheral equipment such as user-specific gas equipment, cables, power supplies, readout electronics, DAQ, etc.
 - Data taking shifts
- **PS/SPS Coordinator**
 - Allocation of particle beam time and its sharing between GIF++ users