




LIU Wire Scanner Status

March 2018

P.Anderssen, W.Andreazza, N.Chritin, J.Emery, D.Gudkov, E.Rigutto,
F.Roncarolo, L.Sirvent Blasco, R.Veness

Mechanics production

- Mechanics production and assembly progressing as-per schedule
 - 26 scanners part-assembled in the store room
 - Vacuum acceptance test plan agreed with TE-VSC
 - Baseline Installation dates agreed with planning



Remaining critical path items

- Vacuum tanks
 - Original contractor stopped operating due to management problem
 - Second lowest bidder accepted to take the contract with similar delivery schedule
 - but CERN agreed to forego the pre-series
 - Close follow-up with MME and BI
- Production of metallic optical discs
 - Signal drop-out problem solved following contractor's visit
 - Production now proceeding

45deg tilted

nano

pico

100 μ m

EHT = 10.00 kV
WD = 10.3 mm
Signal A = SE2

Sample ID = LaserTec 15_outer_45deg.

Anite Perez Fontenla
Date :9 Aug 2018
Mag = 200 X

EN

100 μ m

EHT = 10.00 kV
WD = 13.1 mm
Signal A = SE2

Sample ID = SPDT 905 after cleaning.

Anite Perez Fontenla
Date :9 Aug 2018
Mag = 200 X

EN

10 μ m

EHT = 10.00 kV
WD = 10.3 mm
Signal A = SE2

Sample ID = LaserTec 15_outer_45deg.

Anite Perez Fontenla
Date :9 Aug 2018
Mag = 1.00 K X

EN

10 μ m

EHT = 10.00 kV
WD = 13.1 mm
Signal A = SE2

Sample ID = SPDT 905 after cleaning.

Anite Perez Fontenla
Date :9 Aug 2018
Mag = 1.00 K X

EN

Budget Status

- Recent BI review of budget and spending profile for the BWS project
 - Overall project budget envelope has not changed
 - Minor changes in spending profile are being implemented in EVM
 - See Lars Jensen for details
- Recent Budget milestone reached
 - Three 'commercial mechanical components' codes (one per machine) have been 100% committed
 - All mechanical commercial components have now been ordered!
 - Further spending on these codes will be blocked

Main Project Milestones

Domain	Milestone	Delivery
Mechanics	Kinematic units components received and ready for assembly	17-Apr-2018
	Assembled kinematic units, ready for assembly with tanks (19x), after calibration	4-Sep-2018
	Vacuum tanks received	14-Sep-2018
	BWS series ready for installation	17-Dec-2018
Control	Design Validation using calibration bench (Bld. 867) of the prototype VFC based control system	Apr-2018
	Validation with the PS scanner prototype in the machine (VME/VFC/basic FESA system)	Sept-2018
	Components ordering and contracting with TE-MPE	May-2018
	Full production assembly launch, after validation with beam	Oct-2018
	Functional tests of complete control crate using calibration bench	Mid-2019
Acquisition	Baseline design	End-2017
	Final design approval following tests with beam	Sept-2018
	Contract placement starts	Jan-2019
	Assembly starts	End-2019
Infrastructure	Ready for installation	Start-2020
	Completion of final cabling requests: waiting for final design approval of acquisition	TBD
	Racks available: Most already available, SPS still work-in-progress	In progress

Baseline decision taken. Final DICs are now submitted

SPS racks still being finalised

PS prototype tests and
electronics status/plans

What we have learned since YETS2017 (Details)

- 2 issues stopping the operation of the prototype:

Angular position errors

Fixed by Hardware & Firmware modification

Motor cable power loss


Fixed by Hardware & Firmware modification

- Then (preliminary):

Multi-PMT acquisition can operated without filters wheel

CK50 provides sufficient bandwidth for bunch by bunch

Time of flight jitter to hit the beam $\sim 0.5\text{ms}$





PS Machine development run2018

Date	Nbr scans	Beam types	comment	First outcome	Analysis
2018/06/07	176	LHCPROBE, ZERO	No beam available	Glass disk fixation OK motion stability	completed
2018/06/08	206	LHCINDIV	Go through the cycle with static PMT settings	Possible to measure beams with 2 Multi-PMT configuration	completed
2018/06/11	249	LHCINDIV, LHCPROBE, TOF	Static PMT settings & operational scanners comparison	Different PMT are giving same beam size	On-going
2018/06/13	51	LHC25_BCMS	Nominal beam intensity, static PMT settings	Expected first bunch by bunch processing	to do
total	682				








Angular position by the resolver

PS MD offline processing of ~ 500 scans




Acquired by the 'Dspace' motion control prototyping platform

Incremental optical position sensor (IOPS) MD offline processing of ~700 scans







Acquired by the oscilloscope based acquisition system

MD application




Beam profile processing example (2018/06/11 - LHCINDIV)




Beam profile processing example (2018/06/11 - LHCINDIV)


IN + OUT SCANS
0-101 @ 700V



PS LIU Wire scanner prototype today's configuration



PS LIU Wire scanner prototype final configuration to test



Tests plan for the remaining run2018



1. Multi-PMT 1st complete assembly ([tunnel](#))
2. [VME based acquisition](#) of the secondary shower and the incremental optical position sensor (surface)
3. 2nd iteration of the [control electronics](#) (surface)
4. [Link](#) between the control electronics and the VME crate (surface)

Tests plan for the remaining run2018


1. Multi-PMT 1st complete assembly

- To be installed during TS2
- To be qualified with beam:
 - Printed circuit board (PCB) PMT base with amplifiers
 - Removal of the mechanical filters wheel
 - direct connection scintillator/light guide to PMTs housing

Assembly with filters wheel
(similar configuration as today's OP scanner)



PMT R9880U
similar type as today's system



PSB scintillator configuration shown

Tests plan for the remaining run2018


2. VME based acquisition PMT & IOPS

For testing:

Higher resolution digitalizes
Analog inputs signal compatibility
FESA based processing of the PMT and IOPS signal

HW:
VME, HV and TIMING already there
3x VFC-HD and mezzanines to install

SW:
FESA class under construction (LTIM already being used)
Based on existing python processing
And later extended to experiment processing of the PMT and IOPS
(turn by turn integration, bunch by bunch)




Tests plan for the remaining run2018

3. 2nd iteration of the control electronics

based on BI common FPGA platform (VFC-HD)

- We will use a stand-alone software to configure the motion
- Then use LTIM pulse synchro for the motion
- Large work on the FW at the moment (motion feedback)



Tests plan for the remaining run2018


3. 2nd iteration of the control electronics

Motor bench

Intelligent drive

VFC-based motion controller

Development software directly connected to the motion control system




Selected result from the 2nd iteration electronics and motor bench
Nominal parameters PS scanner: 3.14 rad @ 110 rad/s



Tests plan for the remaining run2018

4. Link control electronics <->VME

- Will be used to configure motion parameters from a FESA class
- Scan trigger transmitted using this link
- Custom optical link based on GBT low level layers
- FESA class not yet started (waiting for final memory mapping)



Motion settings + triggers + motion data/IOPS



To be tested after run2018

- Control electronics final hardware (3rd iteration):
 - > 3 PCB boards ready for prototype (Design office done)
 - > Very close to the 2nd iteration that will be tested with beam
 - Lots of changes done 'by hand' on the PCB boards
 - > We believe that the laser calibration bench will assess correctly the future performance of the motion
- Acquisition hardware:
 - > if we change the digitalizers mezzanines
 - > PMT analog signal conditioning