

HL-LHC Crystal collimator day

Crystal HW LHC implementation

I. Lamas Garcia, R. Seidenbinder, C. Bahamonde,
S. Gilardoni, M. Calviani (EN-STI)
in collaboration with EN-SMM



ENGINEERING
DEPARTMENT



Outlook

- Review of present system installed in the LHC machine
- Review of two version 1 installed goniometer, history and issues
- Review of two version 2 installed goniometer, history and issues
- Summary of new design (version 3) advantages plus possible new upgrades
- Radiation protection aspects and how much time it would take to change crystal and stage?
- Technical feasibility of the different proposed scenarios
- Conclusions

Review of present system installed in the LHC machine


| Functional Type | Position | Crystal Type | Installation Year | Version |
|-----------------|----------|--------------|-------------------|---------|
| TCPCH | A4L7.B1 | SD (INFN) | 2013 (LS1) | 1 |
| TCPCV | A6L7.B1 | QM (PINP) | 2013 (LS1) | 1 |
| TCPCH | A5R7.B2 | SD (PINP) | 2018 | 2 |
| TCPCV | A6R7.B2 | QM (PINP) | 2017 | 2 |

See M. Garattini's talk





Review of version 1 goniometer, history and issues

- 1st proposal version 1 included (prior to LS1):
 - The crystals parking position is located on the external side
 - Linear positioning/guiding system
 - View port in front of the crystal
 - Volume closed with a kind of portion of chamber just by closing the C-shape
 - **Electrical contact** between the tank and portion of the chamber



Review of version 1 goniometer, history and issues



- Final proposal version 1 included:
 - First generation of rotational stage, with piezo installed at 90 deg with respect to the piston/rotor
 - **Interferometric heads inside the vacuum**, i.e. impossible to modify after closure of the tank



Review of version 1 goniometer, history and issues




- Final proposal version 1 included:
 - A lifting arm and supports for survey reference points
 - The center of gravity of the device was outside of the collimator stability plane – counterweight to move the center of gravity has been added
- Temperature limitations of optic fiber feedthrough for interferometric heads made device **unbakeable**

Two version 1
Crystal
Collimators
installed during
LS1




Review of version 2 goniometer, history and issues





- Final proposal version 2 included:
 - A new design of the mechanical stage including a different kinematic chain
 - A new design of the mirror, optic heads support and the crystal holder, interferometer heads still **inside the vacuum tank**
 - Validated UHV optic fiber feedthroughs
 - → **Bake able device**



Rotational stage





Review of version 2 goniometer, history and issues




Review of version 2 goniometer, history and issues

- During the mechanical stage validation thermal cycle, a modification of the angular range was found
 - Due to different thermal expansion between the stainless steel frame and the stacked ceramic piezo
- **Preload of the piezo is a key parameters**
→ a compensated elastic contact was developed and put in operation






- The goal is to get the piezo actuator always preloaded for surface-to-surface contact



Review of version 2 goniometer, history and issues

- Two version 2 (V & H) crystal collimators were assembled, aligned, adjusted, tested (mechanical, electrical, impedance), validated and baked

Two version 2
Crystal Collimators
installed during
YETS2016/2017





Review of version 2 goniometer, history and issues

- After an MD, data showed TCPCH.A5R7.B2 not correct crystal roll angle → reflection of skew planes
- Required an exchange of the complete hardware
 - Installation of the only remaining available unit, used also for testing → **no more available for further studies/development/SPARE**

TCPCH version 2
Crystal Collimator
replace by same
type during
YETS2017/2018

Holder w/
crystal




Goniometer assembly version 3



- Due to several technical issues encountered during the operation of version 2 and version 1, it was decided to **proceed towards the design of a version 3 during 2017-2018**, in order to have a “well thought” design within CERN
- In addition, version 1 and version 2 were basically manufactured outside, with **no control of the mechanical design and drawings (no CATIA model available)**
- **This version will be the reference for new potential production**
- **NB: no prototype was financed – the mechanical & control parts have to be validated for final construction**
- **NB2: still no possibility for realignment from outside of the tank**

Summary of new design (version 3)

- Increase of clearance between crystal and beam pipe
- Additional viewport to anticipate possible interference
- Movement of the **interferometric heads outside of the vacuum tank**, plus possibility to **independently align each mirror**
- Increased stroke for stage and beam pipe
- Addition of **mechanical positioning references**
- Improved hoisting point to be balanced with respect to center of gravity



V3 design



Mechanical modelling of version 3

- In order to better understand the behavior of the system & anticipate potential issue, a suite of FEM analysis have been performed
 - Elastic behavior of the piezo + mechanical stage subassembly
 - Definition of the initial pre-load necessary to reach the require angular range
 - Mechanical analysis (stressed, deformation, buckling) of the piezo-mechanical stage subassembly
 - Modal analysis of the piezo-mechanical stage subassembly
 - Mechanical analysis of crystal collimator during bake-out
 - Mechanical analysis of crystal collimator and lifting tool during transport
- Will be documented in a dedicated EDMS document

Radiation protection aspects related to crystals

- Current values measured on the TCPC installed in the LHC – clearly dependent on the use of the device → difficult to make projections towards LS2

| | | 2017 TS#2 | 2018 TS#1 | 2018 TS#2 |
|-------|---------------|------------|------------|------------|
| | | ~1 week ct | ~1 week ct | ~1 week ct |
| | | 19/09/2017 | 20/06/2018 | 17/09/2018 |
| 19843 | TCPCV.A6L7.B1 | 80 | 139 | 225 |
| 19919 | TCPCH.4L7.B1 | 23 | 40 | 70 |
| 20090 | TCPCH.A5R7.B2 | 62 | 98 | 208 |
| 20144 | TCPCV.A6R7.B2 | 55 | 98 | 242 |

μSv/h @ 40 cm

- Radioactive crystal collimator in storage (HCTCPC_001-CZ000001) is at around ~300 uSv/h at contact with the tank

How much time would it take to change the crystal and stage?

- In order to prepare it for installation, the activities that require working at close distance are (**based on real work**):
 - Set up crystal collimator in 272 survey pit and removal of heating straps → 2h
 - Opening of the tank and removal of the mechanical stage subassembly → 4h
 - Mechanical stage thermal cycle including crystal and crystal holder → 2h (effective)
 - Installation of mechanical stage subassembly and shim to avoid parasitic angles in linear stroke → 8h
 - Adjustment of LVDTs and switches → 2h
 - Alignment/adjustment of tank and crystal → 8h
 - Closing up tank and installation of heating straps → 4h
 - Bake-out → 4h (effective)
- TOTAL time at <40 cm from the tank **O(30 hours)**

Comment on technical feasibility of different scenarios

- **Scenario 1** = basic interventions outside the tank, in the tunnel
 - Potentially possible, but it would depend on the dose rate in P7 close to the TCPCs and the foreseen duration of work (30 minutes / 1 hours estimated)
 - Pending detailed analysis by RP and validation of WDP
- **Scenario 2** = required opening of tank to exchange crystal (and stage)
 - Would require transport of the gonio tank on the surface (b 272) and opening of the assembly, including realignment, etc.
 - Given the time required (O(30 hours)) and the equipment dose rate, assuming 100 $\mu\text{Sv/h}$ at 40 cm → **estimated collective dose would be too high (O(several mSv))**
 - **Option very unlikely, pending final survey from RP at the end of the year and projections during LS2**

Comment on technical feasibility of different scenarios

- **Scenario 3** = new generation of goniometers
 - Replacement of full 4 crystal systems not compatible with LS2 (counting only on CERN resources) due to:
 - Purchasing procedures
 - Available man-power
 - Time available between now and end of LS2
 - Potential to start procuring **1 unit towards the end of LS2** should serve as a **prototype unit to validate mechanics and controls and spare of existing system**
- **Procurement of 4+ units would be possible only after the end of LS2 (clear functional specification required) with installation at first YETS after LS2**
- All of these pending the results of last MD – crash program needed in case MD reveals that 1 or 2 crystals have to be changed for beam dynamic reasons or operational scenarios to be re-discussed

Conclusion

- Reviewed the different generations of crystal goniometers installed in the LHC machine
- Difference scenarios for installation and re-work briefly discussed
- It will be difficult – if not impossible - to rework a radioactive v2 coming from the LHC tunnel
- Procurement of a new v3 goniometer only possible towards the end of LS2 at the level of a prototype if counting only on CERN resources
 - To be revised if beam dynamics shows that it is not possible to use the existing system

Thanks a lot

