




## **Status and plans of MQXFBP1 prototype cold mass LMQXFBT**

H. Prin



# Design evolution and status



March 2018

- End covers development
- Cryostating interfaces definition
- IFS routing
- Connection lines to the CFB optimization
- Ancillary lines definition
- Instrumentation pots redesign et reorientation

Sept 2018



Design completed

On going

Target completion 15/10

Fabrication drawings for subcomponents:

- flares
- flanges
- IFS system
- Centring pieces for filling and heat exchanger lines
- Specific extensions
- Instrumentation pots components to be standardised
- Connection box (inspired from the short model)

# Components status

## Ordered/Delivered


|                      |                                   |
|----------------------|-----------------------------------|
| Shells:              | 2 for w38 (+6 in w42)             |
| End covers:          | w44                               |
| Supports:            | Delivered and accepted            |
| Heat exchanger tube: | tested and accepted               |
| Filling pipe:        | recovered from existing N-Line(s) |
| IFS flexible:        | identical to 11T item             |
| Cold bore tube:      | insulation type under discussion  |
| CLIQ leads:          | 600A cables through CFB           |

## To be ordered

|                          |                              |
|--------------------------|------------------------------|
| Optic fiber connectors:  | off-the-shelf (M. Guinchard) |
| D-Sub connectors:        | off-the-shelf (LMF)          |
| Elbows:                  | off-the-shelf (LMF)          |
| Pots pumping connectors: | off-the-shelf (LMF)          |
| Flexible lines:          | ✗ (SM18)                     |
| Splice stabilization:    | MQXFS design (LMF/MDT)       |

## Tooling

|                      |  |
|----------------------|--|
| Alignment bench:     | ✓  |
| Rotation bench:      | ✓  |
| Lifting beam:        | ✓  |
| Welding press:       | ✓ but welding process still under development                  |
| Welding cradles:     | ✗ Feb 19, negotiations ongoing for mid Jan or partial delivery |
| Laser tracker:       | ✓  |
| Magnetic mole:       | ✓  |
| Geomagnetic mole:    | ✗ Dec 18   |
| Finishing bench:     | ✓  |
| Pressure/test bench: | ✓ on going studies for connection                              |



# Schedule

About **4 month** are necessary to assemble the cold mass from the magnet delivery to the pressure/leak tests. It could be faster.

**BUT!!!**

Prototypes assemblies are also used to

- Test several assembly options
- Write and document the procedures inline
- Train for NDT examination of the welds (Omniscan)
- Develop the geometric and geomagnetic measurements and related software



***Thank you for your attention***










***Spare slides***



# Cold Mass Envelope Layout




# CFB Interfaces and Conceptual Cryo-Scheme







# Mechanical Instrumentation inside the cold mass



Inside the cold mass volume

- Cryo thermometer
- 4 gauges for the rods (6 wires per gauge)
- 6 gauges (3 sections - 4 wires)
- 1 fibre cable using 2 connectors measuring 6 locations per coil

wires  
4  
24  
24 (V plane)  
52

Inside insulation vacuum

- 6 gauges (3 sections – 4 wires)
- 12 gauges (3 sections – 4 wires)

8 connectors  
24 (V plane)  
64  
88

Pumping




Sub-B connector weldable




Optical fibre feedthrough, weldable

SG Position Cross-Section



SG Position Longitudinal



Courtesy of G. Vallone