




CLICWEEK2019



Compact Linear Collider Workshop

January 21 - 25, 2019 @ CERN



Accelerator technology, high-gradient structures, and low-emittance beams

- Advanced radio frequency technologies: high-efficiency klystrons, pulse compressors, components, and accelerating structures




- Low emittance beams: beam dynamics, damping rings, beam delivery, instrumentation, alignment, stabilization

- Staged approach: from a 380 GeV Higgs/top factory to TeV energies

e^+e^- collisions at the energy frontier!


Detector technology and software

- Detector R&D: new prototype designs, simulation studies, and test-beam results for tracking detectors and calorimeters
- Software for detector geometry, simulation and reconstruction (DD4hep)
- Tracking and particle flow reconstruction
- Distributed data management and computing (iLCDirac)




Precision physics: Higgs, top, and BSM

- CLIC potential for precision measurements of the Higgs boson and top-quark properties, and the flavour sector
- Global interpretation using Standard Model effective field theory
- Signatures for direct discovery at CLIC, complementarity with indirect probes and hadron colliders

Learn more about CLIC here 

clicw2019.web.cern.ch

The CLIC accelerator studies



The CLIC workshop 2019

Steinar Stapnes on behalf of the CLIC accelerator collaboration



Collaborations

<http://clic.cern/>



CLIC accelerator collaboration
53 institutes from 31 countries

CLIC detector and physics (CLICdp)
30 institutes from 18 countries



For CLICdp see the following talks



CLIC input to the European Strategy for Particle Physics Update 2018-2020

Formal European Strategy submissions

- **The Compact Linear e+e- Collider (CLIC): Accelerator and Detector** ([arXiv:1812.07987](https://arxiv.org/abs/1812.07987))
- **The Compact Linear e+e- Collider (CLIC): Physics Potential** ([arXiv:1812.07986](https://arxiv.org/abs/1812.07986))

Yellow Reports

- **CLIC 2018 Summary Report** ([CERN-2018-005-M](https://cds.cern.ch/record/2311000), [arXiv:1812.06018](https://arxiv.org/abs/1812.06018))
- **CLIC Project Implementation Plan** ([CERN-2018-010-M](https://cds.cern.ch/record/2311000))
- **The CLIC potential for new physics** ([CERN-2018-009-M](https://cds.cern.ch/record/2311000))
- **Detector technologies for CLIC** [In collaboration review]

Journal publications

- **Top-quark physics at the CLIC electron-positron linear collider** [In journal review] ([arXiv:1807.02441](https://arxiv.org/abs/1807.02441))
- **Higgs physics at the CLIC electron-positron linear collider** ([Journal](#), [arXiv:1608.07538](https://arxiv.org/abs/1608.07538))
 - Projections based on the analyses from this paper scaled to the latest assumptions on integrated luminosities can be found here: [CDS](#), [arXiv](#).

CLICdp notes


- **Updated CLIC luminosity staging baseline and Higgs coupling prospects** ([CERN Document Server](#), [arXiv:1812.01644](https://arxiv.org/abs/1812.01644))
- **CLICdet: The post-CDR CLIC detector model** ([CERN Document Server](#))
- **A detector for CLIC: main parameters and performance** ([CERN Document Server](#), [arXiv:1812.07337](https://arxiv.org/abs/1812.07337))

Link: <http://clic.cern/european-strategy>




Compact Linear Collider (CLIC)

-  380 GeV - 11.4 km (CLIC380)
-  1.5 TeV - 29.0 km (CLIC1500)
-  3.0 TeV - 50.1 km (CLIC3000)



CLIC 380 GeV layout and power generation



CAPTION

CR : Combiner ring
 TA : Turnaround
 DR : Damping ring
 PDR : Predamping ring
 BC : Bunch compressor
 BDS : Beam delivery system
 IP : Interaction point
 ■ : Dump


Baseline electron polarisation $\pm 80\%$



380 GeV klystron option



Replace drive-beam complex by local X-band RF power in tunnel
Larger tunnel, simpler module




Modulator






Klystron




Pulse compressor




Accelerating structures



Assembled X-band systems in continues operation at CERN









CLIC parameters




Parameter	Symbol	Unit	Stage 1	Stage 2	Stage 3
Centre-of-mass energy	\sqrt{s}	GeV	380	1500	3000
Repetition frequency	f_{rep}	Hz	50	50	50
Number of bunches per train	n_b		352	312	312
Bunch separation	Δt	ns	0.5	0.5	0.5
Pulse length	τ_{RF}	ns	244	244	244
Accelerating gradient	G	MV/m	72	72/100	72/100
Total luminosity	\mathcal{L}	$10^{34} \text{ cm}^{-2} \text{ s}^{-1}$	1.5	3.7	5.9
Luminosity above 99% of \sqrt{s}	$\mathcal{L}_{0.01}$	$10^{34} \text{ cm}^{-2} \text{ s}^{-1}$	0.9	1.4	2
Total integrated luminosity per year	\mathcal{L}_{int}	fb^{-1}	180	444	708
Main linac tunnel length		km	11.4	29.0	50.1
Number of particles per bunch	N	10^9	5.2	3.7	3.7
Bunch length	σ_z	μm	70	44	44
IP beam size	σ_x/σ_y	nm	149/2.9	$\sim 60/1.5$	$\sim 40/1$
Normalised emittance (end of linac)	$\varepsilon_x/\varepsilon_y$	nm	900/20	660/20	660/20
Final RMS energy spread		%	0.35	0.35	0.35
Crossing angle (at IP)		mrad	16.5	20	20

Key technologies have been demonstrated
CLIC is now a mature project ready for implementation



Updated CLIC Staging



Stage	\sqrt{s} [TeV]	\mathcal{L}_{int} [ab ⁻¹]	increased from
1	0.38 (and 0.35)	1.0	0.5+0.1ab ⁻¹
2	1.5	2.5	1.5ab ⁻¹
3	3.0	5.0	3ab ⁻¹

Electron polarisation enhances Higgs production at high-energy stages and provides additional observables

Baseline polarisation scenario adopted:
 electron beam (-80%, +80%) polarised in ratio (50:50) at $\sqrt{s}=380\text{GeV}$; (80:20) at $\sqrt{s}=1.5$ and 3TeV


Staging and live-time assumptions following guidelines consistent with other future projects: Machine Parameters and Projected Luminosity Performance of Proposed Future Colliders at CERN [arXiv:1810.13022](https://arxiv.org/abs/1810.13022), Bordry et al.

Accelerator challenges


Four challenges:

High-current drive beam bunched at 12 GHz

- Power transfer + main-beam acceleration
- ~100 MV/m gradient in main-beam cavities
- Alignment & stability




Drive beam quality:
Produced high-current drive beam bunched at 12GHz



Current in combiner ring

28A
←

Drive beam arrival time stabilised to CLIC specification of 50fs



Examples of measurements from CLIC Test Facility, CTF3, at CERN.

CTF3 now the 'CERN Linear Electron Accelerator for Research' facility, CLEAR

Accelerator challenges

Four challenges:


High-current drive beam bunched at 12 GHz

Power transfer + main-beam acceleration




~100 MV/m gradient in main-beam cavities

Alignment & stability

Demonstrated 2-beam acceleration



31MeV = 145MV/m



Four challenges:

High-current drive beam bunched at 12 GHz





Power transfer + main-beam acceleration

~100 MV/m gradient in main-beam cavities

Alignment & stability



X-band performance: achieved 100MV/m gradient in main-beam RF cavities





Accelerator challenges

Four challenges:




High-current drive beam bunched at 12 GHz

Power transfer + main-beam acceleration
~100 MV/m gradient in main-beam cavities

Alignment & stability

The CLIC strategy for nano-beams:

- Align components (10 μ m over 200m)
- Control/damp vibrations (from ground to accelerator)
- Measure beams well
 - allow to steer beam and optimize positions
- Algorithms for measurements, beam and component optimization, feedbacks
- Tests in small accelerators of equipment and algorithms (FACET at Stanford, ATF2 at KEK, CTF3, Light-sources)





Accelerator challenges

Four challenges:


High-current drive beam bunched at 12 GHz

Power transfer + main-beam acceleration
~100 MV/m gradient in main-beam cavities


Alignment & stability

The CLIC strategy for nano-beams:



- Align components (10 μ m over 200m)
- Control/damp vibrations (from ground to accelerator)
- Measure beams well
 - allow to steer beam and optimize positions
- Algorithms for measurements, beam and component optimization, feedbacks
- Tests in small accelerators of equipment and algorithms (FACET at Stanford, ATF2 at KEK, CTF3, Light-sources)



See talk of Daniel Schulte



Industrialisation




Investigating paths to industrialisation

Baseline manufacturing technique:
bonding and brazing

Alternatives:
brazing as for SwissFEL also for disks
machining halves

Target is structures that are
low-cost & easy-to-manufacture & shorten
conditioning time



X-band technology base



- X-band activities and studies in institutes and industry (intensity linked to resources, publications ...)
- Similar maps possible to draw for Asian and US activities (and for other technologies than X-band)
- X-band used as part of machines (linearizers, deflectors) or as main RF

See talk of Walter Wuensch










- 104 x 2m-long C-band structures (beam \rightarrow 6 GeV @ 100 Hz)
- Similar μm -level tolerances
- Length \sim 800 CLIC structures
- Being commissioned




Sources and Injectors


The Klystron and Drive-Beam Modules



Technical developments - II



Pulse Compression System for the Klystron-Based Option









Klystrons and Modulators

PETS and Accelerating Structures









Technical developments - III






Beam Instrumentation

Survey and Alignment
Ground Motion
Stabilisation

Normal Conducting Electro-
Magnets and Permanent
Magnets






- Super-Conducting Damping Wiggler
- Vacuum
- Beam transfer
- Controls
- Fine Time Generation and Distribution
- Machine Protection
- Beam Interception Devices




Important effort within:

- Civil engineering
- Electrical systems
- Cooling and ventilation
- Transport, logistics and installation
- Safety, access and radiation protection systems


Crucial for cost/power/schedule



(a)




(b)



Drive-beam option: 168 MW



Klystron-based option: 164 MW




- Main-beam injectors
- Main-beam damping rings
- Main-beam booster and transport
- Drive-beam injectors
- Drive-beam frequency multiplication and transport
- Two-beam acceleration
- Main linacs (klystron)
- Interaction region
- Infrastructure and services
- Controls and operations

Power estimate bottom up (concentrating on 380 GeV systems)

- Very large reductions since CDR, better estimates of nominal settings, much more optimised drivebeam complex and more efficient klystrons, injectors more optimisation, etc

Further savings possible, main target damping ring RF


Will look also more closely at 1.5 and 3 TeV numbers next



From running model and power estimates at various states – the energy consumption can be estimated

CERN is currently consuming ~1.2 TWh yearly (~90% in accelerators)


Collision Energy [GeV]	Running [MW]	Standby [MW]	Off [MW]
380	168	25	9
1500	364	38	13
3000	589	46	17



~

Machine has been re-costed bottom-up in 2017-18

- Methods and costings validated at review on 7 November – similar to LHC, ILC, CLIC CDR
- Technical uncertainty and commercial uncertainty estimated



Domain	Sub-Domain	Cost [MCHF]	
		Drive-Beam	Klystron
Main Beam Production	Injectors	175	175
	Damping Rings	309	309
	Beam Transport	409	409
Drive Beam Production	Injectors	584	—
	Frequency Multiplication	379	—
	Beam Transport	76	—
Main Linac Modules	Main Linac Modules	1329	895
	Post decelerators	37	—
Main Linac RF	Main Linac Xband RF	—	2788
Beam Delivery and Post Collision Lines	Beam Delivery Systems	52	52
	Final focus, Exp. Area	22	22
	Post-collision lines/dumps	47	47
Civil Engineering	Civil Engineering	1300	1479
	Electrical distribution	243	243
	Survey and Alignment	194	147
Infrastructure and Services	Cooling and ventilation	443	410
	Transport / installation	38	36
	Safety system	72	114
Machine Control, Protection and Safety systems	Machine Control Infrastructure	146	131
	Machine Protection	14	8
	Access Safety & Control System	23	23
Total (rounded)		5890	7290

CLIC 380 GeV Drive-Beam based: 5890^{+1470}_{-1270} MCHF;

CLIC 380 GeV Klystron based: 7290^{+1800}_{-1540} MCHF.

Other cost estimates:

Construction:

- From 380 GeV to 1.5 TeV, add 5.1 BCHF (drive-beam RF upgrade and lengthening of ML)
- From 1.5 TeV to 3 TeV, add 7.3 BCHF (second drive-beam complex and lengthening of ML)
- Labour estimate: ~11500 FTE for the 380 GeV construction

Operation:

- 116 MCHF (see assumptions in box below)
- Energy costs
 - 1% for accelerator hardware parts (e.g. modules).
 - 3% for the RF systems, taking the limited lifetime of these parts into account.
 - 5% for cooling, ventilation and electrical infrastructures etc. (includes contract labour and consumables)

These replacement/operation costs represent 116 MCHF per year.




Schedule



Updated schedule:

Construction + commissioning for 380 GeV: 7 yr

Full physics programme 27 yr




Integrated luminosity [ab^{-1}]






Klystron and overall schedules



More details





Next phase

2013 – 2019

Development Phase

Development of a project plan for a staged CLIC implementation in line with LHC results; technical developments with industry, performance studies for accelerator parts and systems, detector technology demonstrators

2020 – 2025

Preparation Phase

Finalisation of implementation parameters, preparation for industrial procurement, pre-series and system optimisation studies, technical proposal of the experiment, site authorisation

2026 – 2034

Construction Phase

Construction of the first CLIC accelerator stage compatible with implementation of further stages; construction of the experiment; hardware commissioning

2020

Update of the European Strategy for Particle Physics

2026

Ready for construction

2035

First collisions

Activities

Purpose

Design and parameters

Beam dynamics studies, parameter optimisation, cost, power, system verifications in linacs and low emittance rings

Luminosity performance and reduction of risk, cost and power

Main Linac modules

Construction of 10 prototype modules in qualified industries, Two-Beam and klystron versions, optimised design of the modules with their supporting infrastructure in the Main-Linac tunnel

Final technical design, qualification of industrial partners, production models, performance verification

Accelerating structures

Production of ~ 50 accelerating structures, including structures for the modules above

Industrialisation, manufacturing and cost optimisation, conditioning studies in test-stands

Operating X-band test-stands, high efficiency RF studies

Operation of X-band RF test-stands at CERN and in collaborating institutes for structure and component optimisation, further development of cost-optimised high efficiency klystrons

Building experience and capacity for X-band components and structure testing, validation and optimisation of these components, cost reduction and increased industrial availability of high efficiency RF units

Other technical components

Magnets, instrumentation, alignment, stability, vacuum

Luminosity performance, costs and power, industrialisation

Drive beam studies

Drive beam front end optimisation and system tests to ~ 20 MeV

Verification of the most critical parts of the drive beam concept, further development of industrial capabilities for L-band RF systems

Civil Engineering, siting, infrastructure

Detailed site specific technical designs, site preparation, environmental impact study and corresponding procedures in preparation for construction

Preparation for civil engineering works, obtaining all needed permits, preparation of technical documentation, tenders and commercial documents

- Working group for use of Novel Acceleration Technologies (NAT) – plasma with various drivers, dielectrics, etc (short chapter in Project Implementation Plan document)
 - Physics and accelerator parameters (luminosity in particular)
 - Consider status of various studies
 - Key challenges beam-quality, positrons, energy efficiency for suitable luminosities
- Possible re-use of tunnel/infrastructure/drive-beams/injectors etc interesting for a LC infrastructure
- The fact the actual effective ML might remain short (and hence possibly “cheap” and inter-changeable in a limited time) makes this long term perspective worth considering
- Have not found any “constrains/guidance” from these very long term “hopes” that would impact the design of CLIC stages 1-3
 - CLIC is laser-straight and with a “reasonable” crossing angle likely to compatible with higher beam energies and the bunch separations needed for these technologies

- CLIC is now a mature project, ready for implementation
- The main accelerator technologies have been demonstrated
- The cost and implementation time are similar to LHC
- The physics case is broad and profound (see next talks)
- The detector concept and detector technologies R&D are advanced (also next talks)
- The full project status has been presented in a series of Yellow Reports and other publications: <http://clic.cern/european-strategy>



Thanks to all providing material - and more generally ALL contributors to the CLIC project implementation plan documents, from which this material is drawn