



# Availability Studies for

Odei Rey Orozco



# Availability studies for CLIC

- Key performance indicator ->> Integrated luminosity ->> Availability
- Availability target for CLIC -> 75% in 185 days of scheduled operation


## Goals:

- Demonstrate that CLIC availability requirement of 75 % can be reached.
- Identify the key accelerator systems and components that drive availability.
- Investigate the impact of failures on machine operation and recovery.
- Optimise the design with the best balance between availability and cost.
- Find the optimal technical stops and operational schedule that maximizes availability.
- Provide guidelines for availability-driven improvements of system and component designs.

# Availability studies for CLIC

Bottom-up approach:  
**Availability models**


Top-down approach:  
**Availability requirements**



# Availability studies for CLIC

Bottom-up approach:  
**Availability models**

Top-down approach:  
**Availability requirements**



# CLIC Failure scenarios and Operational impact

| Failure scenario  | Beam kept?             | Beam off time / Repair time | Consequence in Luminosity | Example  | Recovery times of faulty system     |
|---|------------------------|-----------------------------|---------------------------|--|-------------------------------------|
| <b>Hardware failures that do not require an interlock</b>   | yes                    | <b>no</b>                   | Minimal loss / Negligible | RF Breakdown   | <b>No recovery</b>                  |
| <b>Short beam interruptions due to spurious interlocks.</b> | yes                    | <b>Short (~400s)</b>        | Short loss / Small        | Simultaneous RF breakdowns   | <b>Short recovery Ramp-up</b>       |
| <b>Short hardware failure</b>                               | Partial beam           | <b>Short</b>                | No production             | Simultaneous breakdowns, requiring minor changes of the machine configuration<br>Equipment breakdown and swap with hot spare | <b>Short recovery Ramp-up</b>       |
| <b>Failure requiring a hardware intervention</b>            | Partial beam           | <b>long (&lt; 4 h)</b>      | No production             | Equipment breakdown requiring expert to come to change hardware (outside the accelerator housing)                            | <b>Long recovery</b>                |
| <b>Repair with access to the accelerator housing</b>        | Partial beam / No beam | <b>short (&lt; 4h)</b>      | No production             | Failure requiring a hardware intervention under controlled access in some areas of the machine                               | <b>Long recovery</b>                |
|   | No beam                | <b>long (&gt;&gt; ??)</b>   | No production             |  | <b>Very long recovery / Restart</b> |

# CLIC Failure scenarios and Operational impact

| Failure scenario  | Beam kept?             | Beam off time / Repair time | Consequence in Luminosity | Example  | Recovery times of faulty system     |
|---|------------------------|-----------------------------|---------------------------|--|-------------------------------------|
| <b>Hardware failures that do not require an interlock</b>   | yes                    | <b>no</b>                   | Minimal loss / Negligible | RF Breakdown   | <b>No recovery</b>                  |
| <b>Short beam interruptions due to spurious interlocks.</b> | yes                    | <b>Short (~400s)</b>        | Short loss / Small        | Simultaneous RF breakdowns   | <b>Short recovery Ramp-up</b>       |
| <b>Short hardware failure</b>                               | Partial beam           | <b>Short</b>                | No production             | Simultaneous breakdowns, requiring minor changes of the machine configuration<br>Equipment breakdown and swap with hot spare | <b>Short recovery Ramp-up</b>       |
| <b>Failure requiring a hardware intervention</b>            | Partial beam           | <b>long (&lt; 4 h)</b>      | No production             | Equipment breakdown requiring expert to come to change hardware (outside the accelerator housing)                            | <b>Long recovery</b>                |
| <b>Repair with access to the accelerator housing</b>        | Partial beam / No beam | <b>short (&lt; 4h)</b>      | No production             | Failure requiring a hardware intervention under controlled access in some areas of the machine                               | <b>Long recovery</b>                |
|   | No beam                | <b>long (&gt;&gt; ??)</b>   | No production             |  | <b>Very long recovery / Restart</b> |

# CLIC Availability models

- Use of component reliability data to estimate overall machine availability
- Focus on most critical systems of CLIC
  - Main LINAC and Drive Beam LINAC RF powering systems (@380 TeV and 3TeV)
  - Main Linac Magnets powering
  - RTML and transfer lines (on-going)
  - Technical Infrastructures, cooling and ventilation (on-going)

## Assumptions

- The simulation period corresponds to the CLIC scheduled operation time: 175 days.
- Components failure behaviour follow an exponential distribution.
- Failed components are repaired only when the system is down due to components failures, unless otherwise defined.
- All repairs must be finished before restarting operation, including spare part repairs.

## Simulation tool


- AvailSim Availability simulation software (Monte Carlo simulations)



# Main Linac Drive Beam based RF Powering System @380TeV

## CLIC Availability models

| @380TeV                            | Availability | Times Down | Downtime (h) | MTTR (h)  | MTTF (h)   |
|------------------------------------|--------------|------------|--------------|-----------|------------|
| 472 modules +<br>12 standby spares | <b>98.2%</b> | <b>5</b>   | 75           | <b>15</b> | <b>822</b> |



| Major contributors to  |                      |
|------------------------|----------------------|
| # Failures             | Downtime             |
| Cavity breakdown (41%) | Cooling system (64%) |
| LLRF (20%)             | Wave guides (17%)    |
| Cooling system (15%)   | Klystrons (8%)       |
| Klystrons (9%)         | LLRF(6%)             |

# Main Linac Drive Beam based RF Powering System @380TeV



## CLIC Availability models

If planned Maintenance each 6 days of operation...

- Continuous machine operation for 6 days (Availability = 100%)
- Maximum 2 standby spares in use before PM
- Component failures:

|                       | Failures / system | Time Spent Repairing [h] ( during Operation ) |
|-----------------------|-------------------|---|
| RF Structure          | 4.7               | 0.16  |
| Klystrons             | 1.3               | 16.3  |
| LLRF                  | 2.6               | 10.2  |
| Modulators            | 0.61              | 7.7   |
| <b>Cooling System</b> | 1.05              | 0   |
| <b>Wave guides</b>    | 0.7               | 0   |


Components to be repaired during PM ~ 15h



# Main Linac Klystron based RF Powering System @380TeV

## CLIC Availability models

| @380TeV                                    | Availability  | Times Down | Downtime (h) | MTTR (h)  | MTTF (h)     |
|--|---------------|------------|--------------|-----------|--------------|
| 1500 units / linac +<br>150 standby spares | <b>93.5 %</b> | <b>6.8</b> | 272          | <b>40</b> | <b>577.7</b> |




| Major contributors to        |                     |
|------------------------------|---------------------|
| # Failures                   | Downtime            |
| Vacuum system (62%)          | Vacuum system (62%) |
| Accelerating structure (15%) | Klystrons (24%)     |
| Modulators (12%)             | Modulators (5%)     |
| Klystrons (4.4%)             | Cooling system (5%) |

# Main Linac klystron based RF Powering System @380TeV


## CLIC Availability models

If planned Maintenance each 6 days of operation...

- Availability = 96.75% ( 12% of prob. of a vacuum failure to interrupt operation of the machine)
- Maximum 26 standby spares in use / linac before PM
- Component failures:



|                         | Failures / system | Caused downtime |
|-------------------------|-------------------|-----------------|
| Alignment system        | 3.82              | 0               |
| Accelerating structures | 47.61             | 0               |
| Cooling system          | 9.77              | 0               |
| Vacuum                  | 0.12              | 0.12            |
| Klystrons               | 13.45             | 0               |
| LLRF                    | 15.85             | 0               |
| Modulators              | 45.37             | 0               |
| Wave guides             | 4.54              | 0               |



# Main Linac Drive Beam Magnets powering @3TeV

## CLIC Availability models

48 sector (24 sector / linac)

860 QD magnets / Sector = 41280 QD

Magnet strings powered in series using trimmers to decrease current

830 trimmers / Sector – 20 failure tolerance

100 power converter modules / sector


12 PC of 4 modules

16 PC of 3 modules

2 PC of 2 modules

N+1 redundancy in Power converters modules


1 controller per PC (30 /sector)



# Main Linac Drive Beam Magnets powering @3TeV

## CLIC Availability models

| Availability | Times Down | Downtime (h) | MTTR (h)    | MTTF (h)    |
|--------------|------------|--------------|-------------|-------------|
| <b>99.7</b>  | <b>2.7</b> | 10.6         | <b>3.99</b> | <b>1575</b> |



- Failure of magnets powering caused by **PC Modules**
- **If no redundancy in PC, availability = 93.9%**
- Trimmers failures do not cause system failure due to implemented redundancy.
- **If Planned Maintenance each 6 days of operation**, minimum failure tolerance not to suffer from trimmers failure -> 2/830

# Main Linac Main Beam Magnets powering @3TeV

## CLIC Availability models

### Dipoles

- Powered individually
- Failure tolerance: 1%

### Quadrupoles



- Powering strategy: individually OR in couples but 7 / sector individually
- N+1 redundancy in Power converters modules (N=1, 2 OR 3)

|             | Magnets | Magnets /linac | 7 QD/ sector Powered individually | Powered in couples | PC for individual powering | PC for QD in couples + individual |
|-------------|---------|----------------|-----------------------------------|--------------------|----------------------------|-----------------------------------|
| Quadrupoles | 4142    | 2071           | 168                               | 952                | 2071                       | 1120                              |
| Dipoles     | 3996    | 1998           | -                                 | -                  | 1998                       | 1998                              |

# Main Linac Main Beam Magnets powering @3TeV

## CLIC Availability models

- Coupled powering higher lifetime
- Best option ( in terms of availability): Coupled powering + PC of 2 modules -> **99.7%** (match with powering requirements)





# Main Linac Main Beam Magnets powering @3TeV

CLIC Availability models

| AVAILABILITY [%]                |                     | PC modules , N+1 redundancy |               |           |           |
|---------------------------------|---------------------|-----------------------------|---------------|-----------|-----------|
| Failure tolerance in correctors | Powering strategy   | 1 modules                   | 2 modules     | 3 modules | 4 modules |
| 0%                              | Individual powering | 89.48%                      | 93.84%        | 94.06%    | 94.10%    |
|                                 | Coupled powering    | 91.53%                      | 94.18%        | 94.23%    | 94.21%    |
| 1%                              | Individual powering | 94.34%                      | 99.45%        | 99.38%    | 99.33%    |
|                                 | Coupled powering    | 96.83%                      | <b>99.67%</b> | 99.63%    | 99.63%    |
| 2%                              | Individual powering | 94.3%                       | 99.45%        | 99.39%    | 99.33%    |
|                                 | Coupled powering    | 96.66%                      | <b>99.68%</b> | 99.64%    | 99.62%    |

# Main Linac Main Beam Magnets powering @3TeV

CLIC Availability models


| MTTF [h]                        |                     | PC modules , N+1 redundancy |           |           |           |
|---------------------------------|---------------------|-----------------------------|-----------|-----------|-----------|
| Failure tolerance in correctors | Powering strategy   | 1 modules                   | 2 modules | 3 modules | 4 modules |
| 0%                              | Individual powering | 33.97                       | 60.89     | 63.33     | 63.81     |
|                                 | Coupled powering    | 43.19                       | 64.69     | 65.26     | 65.01     |
| 1%                              | Individual powering | 66.63                       | 715.18    | 641.17    | 592.59    |
|                                 | Coupled powering    | 121.87                      | 1199.44   | 1070.17   | 1064.72   |
| 2%                              | Individual powering | 66.63                       | 720.14    | 648.18    | 595.14    |
|                                 | Coupled powering    | 115.80                      | 1227.67   | 1104.19   | 1051.29   |

Planned maintenance each 6 days (MTTF >144 h)

# Availability studies for CLIC


**Bottom-up approach:**  
**Availability models**

**Top-down approach:**  
**Availability requirements**




# Availability allocation by complexity criteria

- An **availability requirement** based on the complexity is assigned to each subsystem **to meet the CLIC 75% requirement**
- Experts assess the **complexity** of each subsystem **based on influential factors**
- The **more complex** a subsystem is, the **less available** is required to be



# Availability allocation by complexity criteria

Allocated availability from average complexity



# Summary & Outlook

# CLIC Availability studies

## Summary & Outlook

- The investigated key failures do not compromise the operation of CLIC thanks to the implemented redundancy and hot-standby spares.
- Further studies are required to include a more complete list of failures and to optimise the design for robustness.
- Recovery times will be included as a function of downtime to understand the impact of failures on operation
- A maintenance schedule will be developed with optimised length and frequency of technical short stops.
  
- The availability allocation method shows intuitive results
  
- A luminosity production model could be developed taking as input the results from the availability models

# Thank you!



## **Special thanks to:**

A. Apollonio, S. Doebert, M. Jonker, A. Latina,  
G. Mcmonagle, M. Motyka, D. Schulte and S. Stapnes