





CERN - CEA - PSI - SLAC







LUCKÝ US WE DIDN'T INSTALL BEFORE MARCH 5TH.....

High Voltage Modulator





Modulator finished to be assembled : beginning of April but only missing the bucking coil power supply for the klystron

lrfu



Factory Acceptance Test

saclay

- Test performed with a resistive load
- ✓ Long run Test at 430kV/270A 1.3µs/50pps
- ✓ Test during few minutes at 450kV
- ✓ At nominal point, FWHM is 2.6µs
- ✓ Flat top ripple and pulse to pulse stability measurement will be achieved with the load at CERN

Shipping and Installation

- Modulator already shipped, should be at CERN in few days.
- Installation to be foreseen with CLIC colleagues at CERN

Installation and Site AcceptanceTest with klystron ? Summer <u>2010</u>





















General Performance Observations

The tube operated quietly in terms of gun arcs and tube vacuum spikes during the initial run-up, perhaps better than most. The majority of activity was in the external waveguide system.

The external waveguide system suffered from outgassing, breakdown and multipactor; this was believed to be in the rf coupler and splitter, with normal(?) processing of the loads. Multipactor was noted always above ~1-3MW. These issues severely limited tube operation.

Gain, bandwidth and power output met or exceeded spec.

April 27, 2010 Daryl Sprehn XL5-1 Tube Processing Slide 3





RF network for test





Pulse waveform after SLED compression





Pulse Compressor (Gycom)





KM Schirm BE-RF 10

1.00





Solid State Modulator: from order to delivery 11 m; performance o.k.; SCANDINOVA; CEA; PSI

Pulse Compressor: compact design; fast production; cheap; some performance issues; GYCOM

CERN Participants (minimum): Gerry, Ghislain, Stephane and Igor



Layout Phase 1











Design and fabrication by CEA/CERN

The RF valve has been introduced by A. Grudiev (CERN) in the CTF3 30 GHz test stand. It works on the circular mode TE₀₁° mainly to avoid surface electric field and have steps in diameter to "focus" the wave in the center of the guide. Based on the same principle, RF valves working at 11.4 GHz have also been developed at SLAC for accelerating structure testing. The 12 GHz RF valve is a scaled version of the SLAC one.





- Cleaning
- Brazing, machining, brazing, machining, brazing...

lrfu

CLIC Test Stand 12 GHz



Circular taper design

saclay

A circular taper is needed to connect the existing circular waveguides (50 mm diameter) with the RF valve and the mode converter calculated previously (with a diameter of 36.27 mm). It is composed of different steps of diameters with various lengths optimized for matching on a large bandwidth. It has been scaled from part of the 3 GHz power phase shifter of CALIFES.



Mode converter

Design and fabrication by CEA/CERN

The mode converter is made in two parts. The first part is a rectangular waveguide bend on H plane. It converts the TE_{10}^{\Box} mode into a TE_{20}^{\Box} mode. The second part is a circular waveguide with two posts positioned at 180 ° at a certain distance of the rectangular section. This design is based on an original idea of S. Kazakov (KEK). It is compact and relatively easy to fabricate





Bandwidth of 150 MHz @ -20dB reflection and -0.0618 dB transmission at 11.994 GHz giving 98.6% conversion efficiency in power

The fabrication technology is based on classical high temperature vacuum brazing of machined CuC2 and 316LN pieces. First the two half parts of the bend and the circ. waveguide with the two posts are brazed separetly. The stainless steel flanges are brased in a second step after re-machining. The third brazing concerns the two sub-assemblies and an intermediate round base used for the transition between the rect, and the circ. Parts.







Half of the structure is represented
 Total length = 175 mm

CLIC









! Klystron and Modulator scheduled to arrive at CERN!
!RF components and network require new strategy and more efforts!
! 12 GHz power (without compression) should be available in CTF2 in May 2010
!12 GHz power (without compression) is available in the gallery in May 2010!



Conclusion



- Installation is started and main supplies are at CERN (in time and in budget)
- Performance of power source better than specs
- RF component issues will cost time and money
- Structure testing still for CDR?? Needs help (SLAC?)
- The coming months will be extremely busy with the restarting of CTF3 – will we have enough resources for commissioning the test-stand in parallel??