

ITS OB HIC Production - Status and Plans

Vito Manzari - INFN Bari





12th ALICE ITS upgrade, MFT and O2 Asian Workshop 19-21 November 2018 Inha University



Outline

ALICE ITS Upgrade



- ① Detector Layout
- ② HIC Construction overview
- ③ FPC Production
- ④ HIC Production and Plans
- **5** HIC Yields
- 6 HIC Distribution
- ⑦ Remarks

(8) Conclusions

Detector Layout

ALICE ITS Upgrade





OB HIC elements

ALICE ITS Upgrade



HIC construction process



OB HIC construction sites (MAM site acceptance test)



ALICE ITS Upgrade







OB HIC construction - Tooling, Procedures and Training

ALICE ITS Upgrade

















OB HIC construction - Tooling and Procedures





Ultrasonic wedge bonding for FPC to chip interconnection:

new bonding machine procured for Bari, Strasbourg and Wuhan; a supply contract signed with Sejung company for Pusan; resources allocated by the laboratory management for Liverpool

OB HIC construction - Tooling and Procedures

ALICE ITS Upgrade









Qualification and Endurance test systems



OB FPC production

ALICE ITS Upgrade



Nominal quantity of FPCs needed: 2700 (including spares, yield, quality control) Production at GS Swiss will be completed by the end of 2018

Pre-production and 1st ÷ 5th production batches:

2014 FPCs (1607 Tab-A and 407 Tab-B type) produced, validated and distributed to HIC sites 6th production batch:

308 FPCs (276 Tab-A and 32 Tab-B type) Cross-Cables mounting and validation ongoing, distribution will start this week

7th production batch: ~470 FPCs, production at GS Swiss just started, delivery expected before Christmas

Extra batch: ~350 FPCs, purchasing order in preparation

~970 FPCs still available (~200 already distributed + 770 from 6th and 7th batches) and ~1200 HICs still to be produced (see following slides)

Quality controls and preparation:

Extensive **quality assurance** tests (metrology, electrical tests, visual inspection) at **Trieste** and **Catania Metal quality** verification via sample **wire bonding/pull tests** @ CERN and assembly sites Soldering of **cross cables** (for connection to power and bias cables), test, **drying** and cleaning at Trieste *V. Manzari - 12th ALICE Upgrade Asian Workshop*, *Inha University - Nov 19th*, 2018





Stable production yield per batch: 93% ÷ 97%

~1% metrology out of specs

<1% electrical out of specs

2% ÷ 6% optical inspection: bending, local deformations and/or defects



Electrical tests

Check for short or open lines at different stages



Verification of position of selected structures and

edges with respect to center of central dowel pin hole

Optical inspection

Main source of found defects Few random problems Structural bending





ALICE ITS Upgrade



N.B.: In the following plots and tables, Pusan \rightarrow Pusan/Inha

Number of HICs to equip the OB layers: **1692** Assuming a convoluted HIC (~83%) & Stave (~90%) Yield: ≈75% Number of HICs to build to equip the OB: 1692/0.75 = **2256**

HICs built so far: 1388 (~62%)

Additional spare HICs to build: $\approx 250 \rightarrow \approx 2500$ HICs overall

	PRODUCED	QUALIFIED	NOT QUALIFIED	WORKING	NOT WORKING	ENDURANCED
Bari	367	346	21	293	53	270
Liverpool	397	375	22	317	58	300
Strasbourg	365	321	44	270	51	255
Pusan	64	3	61	0	3	0
Wuhan	195	185	10	142	43	108
TOTAL	1388	1230	158	1022	208	933

End of HIC production Mar 2019

Target production rate: **50 HICs/week**

2 HICs/day/site assuming 5 working day/week

Modified procedure, based on a shorter curing time inside MAM, allows to increase the weekly production rate

OB HIC production

ALICE ITS Upgrade



Steady production in Bari, Liverpool, Strasbourg, Wuhan and ramping-up in Pusan/Inha



	week 41	week 42	week 43	week 44	week 45	week 46
	pr. week 47	pr. week 48	pr. week 49	pr. week 50	pr. week 51	pr. week 52
Bari	12	9	1	7	12	14
Liverpool	14	11	11	11	11	12
Strasbourg	11	11	12	S	6	6
Pusan	5	9	10	8	7	6
Wuhan	12	11	12	10	9	9
TOTAL	54	51	46	36	45	47

Production rate of ~49 HICs/week in the last 5 weeks

w44 excluded because of holidays in Italy and France



OB HIC production

ALICE ITS Upgrade



OB HIC production status





OB HIC production projection

ALICE ITS Upgrade



HIC Production End milestone Mar 2019 → 17 weeks left



Exploit the modified procedure (reduced MAM downtime due to pre-curing) to fulfill the milestone

OB HIC yields

ALICE ITS Upgrade





OB HIC weekly yields





Average number of qualified HICs per week is substantially below the nominal production rate of 50 HICs/week

V. Manzari - 12th ALICE Upgrade Asian Workshop, Inha University - Nov 19th, 2018

OB HIC weekly yields

ALICE ITS Upgrade





V. Manzari - 12th ALICE Upgrade Asian Workshop, Inha University - Nov 19th, 2018

ALICE

OB HIC distribution







WEEKs

BERKELEY FRASCATI TORINO DARESBURY NIKHEF

	week 41	week 42	week 43	week 44	week 45
Enduranced	48	50	38	48	20
Distributed	35	38	62	22	37



	HICS AVAILABLE FOR SHIPMENT																									
	SILVER ASSEMBLED BRONZE ASSEM										MBLED	3LED "BURNT THROUGH"								"NO BACK BIAS"						
	BL	AL	BR	AR	TOTAL	LAST UPDATE	BL	AL	BR	AR	TOTAL	LAST UPDATE	BL	AL	BR	AR	TOTAL	LAST UPDATE	BL	AL	BR	AR	TOTAL	LAST UPDATE		
BARI	0	0	0	0	0	18/11/2018	0	0	0	1	1	18/11/2018	0	4	0	5	9	18/11/2018	0	1	0	0	1	18/11/2018		
LIVERPOOL	3	5	0	0	8	18/11/2018	0	2	0	2	4	18/11/2018	0	5	1	3	9	18/11/2018	1	7	1	3	12	18/11/2018		
STRASBOURG	3	0	1	0	4	18/11/2018	1	0	0	1	2	18/11/2018	0	0	0	0	0	18/11/2018	0	1	1	0	2	18/11/2018		
PUSAN	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0			
WUHAN	0	0	0	0	0	18/11/2018	0	0	0	0	0	18/11/2018	0	0	0	1	1	18/11/2018	0	0	0	0	0	18/11/2018		
TOTAL	6	5	1	0	12		1	2	0	4	7		0	9	1	9	19		1	9	2	3	15			

1 AR NOBB is also BT

	н	ICs D	DISTR	BUTE	D TO TH	E STAVE SITES				HI	Cs IN TR/	ANSIT		- 1	HICs	мои	NTED ON	N STAVEs	HICs STILL AVAILABLE AT THE STAVE SITES					HICs REJECTED		
	BL	AL	BR	AR	TOTAL	LAST UPDATE	BL	AL	BR	AR	TOTAL	SHIPMENT DATE	BL	AL	BR	AR	TOTAL	LAST UPDATE	BL	AL	BR	AR	TOTAL	LAST UPDATE	TOTAL	LAST UPDATE
DARESBURY	10	50	10	60	130	18/11/2018	0	0	0	0	0	18/11/2018	8	48	9	54	119	18/11/2018	0	0	1	1	2	18/11/2018	5	18/11/2018
LBNL	22	64	23	67	176	18/11/2018	2	6	2	4	14	18/11/2018	16	48	17	52	133	12/11/2018	3	5	2	5	15	12/11/2018	6	12/11/2018
LNF	12	70	15	68	165	18/11/2018	1	7	0	0	8	18/11/2018	8	48	9	54	119	23/10/2018	1	3	2	2	8	15/10/2018	8	15/10/2018
NIKHEF	15	60	13	56	144	18/11/2018	1	2	1	5	9	18/11/2018	7	42	7	42	98	13/11/2018	4	3	4	1	12	13/11/2018	4	13/11/2018
TURIN	20	109	19	110	258	18/11/2018	1	7	1	7	16	18/10/2018	14	84	15	90	203	26/10/2018	2	6	1	3	12	31/10/2018	5	09/10/2018
TOTAL	79	353	80	361	873		5	22	4	16	47		53	270	57	292	672		10	17	10	12	49		28	

OB HIC yields vs chip category

ALICE ITS Upgrade





OBHIC Qualification test result

OB HIC quality monitoring - Bond Pull Test

ALICE ITS Upgrade



	TEST	AVG - AVERAGE (g)	AVG - STD.DEV. (g)	AVG - MINIMUM (g)	AVG - MAXIMUM (g)	MIN - MINIMUM (g)
BARI	51	13.06	0.98	9.90	15.07	5.63
LIVERPOOL APEX	49	11.81	2.12	6.79	15.47	4.72
LIVERPOOL	60	10.55	1.12	7.81	13.08	5.07
STRASBOURG	45	10.25	1.02	7.64	12.36	5.20
PUSAN	0	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	0.00
WUHAN	38	10.47	1.66	6.23	13.60	2.69



V. Manzari - 12th ALICE Upgrade Asian Workshop, Inha University - Nov 19th, 2018

OB HIC quality monitoring - Qualification plots

ALICE ITS Upgrade



Standard set of plots in preparation

See Markus Keil's talk







ALICE ITS Upgrade



Careful cleaning of environment and jigs as well as careful manipulation of the components is mandatory to ensure good quality HICs over the production

Wire-bonding process requires constant check of possible interconnection pad contaminations and evaluation of the bonding quality by visual inspection and bond pull test

Regular cleaning of the wedge tool (~every second HIC) and replace (~50k bonds)

The outcome of the Impedance test has been reconsidered: See Markus Keil's talk

Now used to identify the occurrence of shorts only, which should be tried to remove by mean of the burn through procedure, and not to asses the HIC classification

If impedance value below 10 Ohm, HIC physical status is set to NOK

All HICs, regardless the results of the impedance test, should undergo the Qualification Test

FPCs rejected upon the visual inspection should be promptly returned back to Trieste with their own carrier plates

Double check HIC components availability to prevent interruption of the production



Conclusions

ALICE ITS Upgrade



Steady production in Bari, Liverpool, Strasbourg and Wuhan, ramping up in Pusan

- ≈60% of the production already done
- Target to achieve a production rate of 60 HICs/week exploiting the modified procedure

Quality Control and Assurance is extremely important to ensure HICs of proper quality throughout the whole production

- Bond Pull Test and Qualification plots
- Prompt upload of assembly and test data in the database

Attend the HIC weekly meeting on Thursday at 10h:00am CET and report on the production status

Conclusions

ALICE ITS Upgrade



Steady production in Bari, Liverpool, Strasbourg and Wuhan, ramping up in Pusan

- ≈60% of the production already done
- Target to achieve a production rate of 60 HICs/week exploiting the modified procedure

Quality Control and Assurance is extremely important to ensure HICs of proper quality throughout the whole production

- Bond Pull Test and Qualification plots
- Prompt upload of assembly and test data in the database

Attend the HIC weekly meeting on Thursday at 10h:00am CET and report on the production status

This was and still is a challenging and exciting enterprise

now we just see the top of the mountain but we are not yet there

let us make the final effort to reach it



ALICE ITS Upgrade

Back-up

ALICE ITS Upgrade



