Commissioning of ITS R/O system



12th ALICE ITS upgrade, MFT and O2 Asian Workshop Inha University, Incheon, Korea 19-21 November 2018





The Inner "Barrel"

art here

S

- Construction of Inner Barrel is complete
- First commissioning is done half-layer by half-layer "HL"
- Starting with "IB-HL-0"



M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018











• Setup is based on final (or realistic) components

Stave IB-HL-0

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

Setup











XP

"black box" Set-up Overview IBO-HLO

new enclosure control PC (now mostly working from HL-0 in power patching counting room) black box

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

ELMB for PT100 (DCS)



CAEN crate PB, RU







- For humidity control, setup is place in a gas- (and light-)tight box
- Humidity is controlled by:
 - continuous flushing with dry air
 - desiccant bags —
- Monitored by USB data logger
- New box prepared: switch over with next HL

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – In

Enclosure





data logger desiccant bags

Cable feed-through





Cooling

- Cooling of staves up and running
- Cooling of RUs and PBs: currently air cooling only
- Working on monitoring/interlock/DCS integration





M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – In

t c	CO	ntro	ol ir	nte	erf	ac	0	ceme		
EVB90	1_AL1_F	OMPE PPV	901 OFF	larm	<u>کی ا</u>	∎ 	UE		128/ 128	
RD - I Setj		BARREL Pressure IN LL	PCV	PV IN	PV OUT	Pressure OUT	DSS		9.	42.38 A.M
0.9	0 bar	0.95 bar O	8.3 8.4 AR	×	×	0.81 bar	•	Panel	Alarms	
0.9) bar	0.90 bar O	12.0 11.9 AR	×	×	0.62 bar	•	Panel	Alarms	
0.9	D bar	0.93 bar O	0.0 0.1 AR	¥	-	0.78 bar	•	Panel	Alarms	
0.9	0 bar	0.77 bar O	100.0 100.0 A R	×	×	0.60 bar	•	Panel	Alarms	
0.9	0 bar	0.78 bar O		×	×	0.60 bar		Panel	Alarms	
0.9	10 bar	0.67 bar O	0.0 0.0 A P	×	×	0,57 bar	\diamond	Panel	Alanns	
0 :	30 bar	0.67 ber Ø	0.0 A P	巫	1 1	Q 57 bar	\Diamond	Panel	Alarms	
				4	**	0.62 bar		Panel	Alarms	
			N AP	R	Æ	0.73 bar		Panel	Alarms	
			N.0 OTAP	×	*	0.54 bar		Panel	Alarms	







- CAEN rack is being used to supply all power
- Currently manually controlled
 - no interlock with cooling
 - no remote control via scripts (only GUI)

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Ir

Power I/II Power to RUs, PBs







Power II/II Power to staves

- *Temporary* mapping of PB channels to staves
 - non-availability of enough PBs
 - non-availability of steering boards (MOSAICs or RUs) -
- Flexibility given by patch panels
- Uses cables of final length and cross-section
- 3 PBs are ready and installed
 - only 2 can be used at the moment due to missing breakout boards/cables
 - no show-stopper at the moment

M. Mager - Commissioning of ITS R/O system - 12th ALICE ITS upgrade, MFT and O2 Asian Workshop - In









- Now based entirely on RUs v1.1
- 6 RUs installed already
 - integration with FLPs ongoing, firmware and software under development
 - enough for HL-0
 - up to 3 more expected in the following weeks
- Cables:
 - 8m prototypes from Samtec: first try, but connector causes problems (see next slide)
 - 8m commercial cables: different dielectric (slightly worse electrical performace), but better connectors + softer cables

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

Readout Hardware









Not all work reliably! them more For now: switched to commercial cables

Glue and cable attachment of these prototypes is too close to connector \rightarrow fixed in final cables

Need final cables ASAP

S R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – In

Readout Cables

Clearly different penetrations Impossible (for me) to insert





Readout Software(s)/Firmware(s)

- Stave-RU-CRU-FLP+PB communications working
 - at least sometimes for some of the channels
 - still a lot of debugging needed!
- Software based on RU test bench and DAQ tools
 - moving to "readout.exe", the DAQ readout tool for DAQ
 - need discussion on tools for detector configuration/monitoring
- Very good support from O2

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

Architecture (lab)





This clearly needs to evolve to include (more) final DAQ/DCS tools

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018



Architecture (experiment; simplified) ALICE



M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

OK, for data taking ... but we would like something in-between for configuation/calibration/testing





Architecture proposal





M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018



Next commissioning plan

- Establishing slow control communication with all staves
 - works since last week after move to commercial Samtec cables
 - stress testing started, using FIFO test with magic patterns: data=(3**stave.ru_link*5**chip*7**region*11**fifoaddr)%(2**24-1) data=0xFFFFFF data=0x000000
 - found 2 stuck bits (one at zero, one at one)
- Establishing readout of all chips
 - started, but not yet systematic -
 - system (chip, RU, CRU, data)
 - need to synchronise data amongst chips and staves (see next slide) -

- working on tool to gather and cross-check all data flow monitor counters in the

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018





Triggering – feature requests

Table 1: Trigger Types									
Bit	Name	Comment]						
0	ORBIT	ORBIT	l→ senc						
1	HB	Heart Beat flag							
2	HBr	Heart Beat reject flag	(oniy						
3	HC	Health Check							
4	PhT	Physics Trigger	l→ seno						
5	PP	Pre Pulse for calibration							
6	Cal	Calibration trigger]→ seno						
7	SOT	Start of Triggered Data							
8	EOT	End of Triggered Data]						
9	SOC	Start of Continuous Data]						
10	EOC	End of Continuous Data]						
11	TF	Time Frame delimiter]						
••••	•••	Spare	→ send						
29	TPCsync	TPC synchronisation							
3 0	TPCrst	TPC reset]						
3 1	TOF	TOF special trigger							

Currently implemented: only PhT trigger, selectable TRIGGER or PULSE

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

- d BCRST command once, armed by SOT/SOC?)
- d TRIGGER command d PULSE command (maskable)

d DEBUG command (only once, arm-able)







Summary & Outlook

- Commissioning of IB still required and still requires a lot of developments
- memory faults)
- time
- Cross-check of results from Stave testing

M. Mager – Commissioning of ITS R/O system – 12th ALICE ITS upgrade, MFT and O2 Asian Workshop – Inha Univ., Incheon, Korea – 19-21 Nov 2018

Stability of results has to be closely monitored (~ appearing FIFO

 DCS need to be implemented in a way that still allows monitoring, interlocks, while still offering full control via our tools at the same



