


Joachim Mnich (DESY) Plenary ECFA Meeting 15/16 November 2018





# The European XFEL

entering routine user operation



## The European XFEL

The longest SC linac in the world

### **Soft and hard X-ray light experiments**

~800 TESLA-type cavities

Resonance frequency 1.3 GHz


32 cavities per XTL RF station


Design energy 17.5 GeV

Pulsed operation 10 Hz

Routine user operation at several stations

Reached 17.6 GeV and 2700 bunches!





# Particle Physics Activities

DAF and LHC Upgrades
Belle II
ALPS et al.

# **LHC Upgrades**

### At DESY and in Germany

# Germany has significant and diverse contributions to the HL-LHC upgrades, with large Helmholtz involvement

- For many subdetectors for all four LHC experiments
- Most complex and challenging components to be built: tracker end-caps for ATLAS and CMS

### **Funding:**


- 90 MEUR from BMBF for universities
- 15,7 / 4,3 MEUR for DESY / KIT from Helmholtz
- 10 MEUR from DESY for detector assembly facility (DAF)

#### **Central role of DESY:**

- Complex organisation of tracker end-cap construction
- Strong collaboration between DESY and German universities
- DESY also organises controlling and reporting of BMBF funds for universities

			a divid agrado
CMS	Pixel detector	Hamburg	involvement
	Outer tracker	Aachen, DESY, KIT	
	Myon system	Aachen	

	Pixel detector	Bonn, Dortmund, Göttingen, Siegen, Wuppertal	
	Strip tracker	Berlin, DESY, Dortmund, Freiburg	
ATLAS	LAr calorimeter Dresden, MPI		
	Myon system	Freiburg, Mainz, München, MPI, Würzburg	
	TDAQ	Heidelberg, Mainz	



German ATLAS

& CMS ugrade

# **Detector Assembly Facility (DAF) - I**

**DESY Building 25c** 

Remember: DAF a 10 MEUR investment for LHC upgrades

Buildings 25c and hall 1

Building 25c infrastructure & cleanroom (ISO-6) ready

Commissioning almost done. R&D activities started



View of the ATLAS area of the cleanroom with microscopes and probe station. Gantry system for automated module assembly will be installed in November





View of the CMS area of the cleanroom with microscopes and automated module assembly system. All major devices are installed and are being commissioned

# **Detector Assembly Facility (DAF) - II**

**DESY Building 26 – hall 1** 

### **Building infrastructure is refurbished.**

- Cleanroom (ISO-7) construction finished.
- Commissioning will start Jan 2019.



View from the endcap integration area side with air conditioning and filter units on top. Construction and commissioning of cleanroom is finished, final tests are being done now. Expect hand over beginning of December.






View of endcap integration area just before final cleaning. Cleanroom is ready for installation of equipment now. Installations will start mid of November Commissioning until mid 2019

## **Belle II: Phase 2 Commissioning**

25 April 2018; SuperKEKB ramping up towards design lumi



## **Belle II Pixel Detector (PXD)**

### Main German contribution to Belle II

 German consortium consisting of 12 institutes (Universities, Max-Planck, Helmholtz)















LJNIVERSITÄT MAINZ









## **De-Scoping of PXD for Phase 3**


Too high failure rate during ladder assembly step


 Opted to proceed with a de-scoped version of PXD in 2018: L1 complete with 8 ladders, L2 only partial with 2 out of 12 ladders

After pre-commissioning in Germany half shells were transported to KEK, mounted and combined with SVD


### Next steps:

- VXD commissioning Oct 15 Nov 09
- VXD installation in Belle II: end of Nov
- Ongoing studies to determine the impact on track/vertex resolutions
- "PXD 2020": Installation planned for a future extended shutdown






### Cosmic track in PXD



# **ALPS II Progress at DESY**


**Progressing towards data taking in 2020** 




A company has been hired to review the safety concept for the operation in the HERA tunnel.

# **ALPS II Progress at DESY**

**Progressing towards data taking in 2020** 






# **ALPS II Progress at DESY**

**Achievements and schedule** 

#### **ALPS IIc could start data taking in 2020:**


					7/ 4 84
D	ð	Task Name	Duration	Start	F
0		Arbeiten ALPS setup	1215 dys?	Fri 11.12.15	1 0
1		Dipole	723,5 dys	Tue 20.09.16	F
47		West	614 dys	Thu 05.01.17	1
51	$\checkmark$	Halle Nord	44 dys	Thu 08.02.18	1
58		NR Abbau	90 dys	Wed 21.03.18	
102		NL Abbau	84 dys	Wed 28.03.18	
142	<b>%</b>	Aufbau NORD	714 dys	Wed 01.11.17	
257	<b>%</b>	Einbau Dipole	200 dys	Wed 07.08.19	Tue 12.05.20
326		TUEV Pruefung	38 dys	Wed 22.04.20	Fri 12.06.20
334		Abschluss Halle Nord	97 dys	Wed 25.03.20	Thu 06.08.20
337			1 dy?	Fri 11.12.15	Fri 11.12.15
338	$\checkmark$		1 dy?	Fri 11.12.15	Fri 11.12.15



- The ALPS IIc site in HERA North has been cleared.
- A new dilution cryostat BF-SD (67 μW at 50 mK) for the TES detector has been put into operation successfully.
- 13 (out of 20) HERA proton dipoles have been straightened without any problems.
- Locking the regeneration cavity via 532 nm light and keep it resonating to 1064 nm with a length noise rms of 0.5 pm demonstrated.


### **On-Site Experiments – Future**

#### MADMAX – search for dark matter axions



### MADMAX (dark matter)

- Conversion of axion to microwave in 10T B field; 80 dieletric discs made of LaAlO3 with ε = 25
- Aachen, DESY, Hamburg, MPI Munich, Saclay, Tübingen, Zaragoza



#### **MADMAX** collaboration

- Collaboration founded at DESY in 2017; selected DESY site: north hall (H1) area
- Site now being prepared
- Magnet studies by Bilfinger-Noell and CEA Saclay, aim for magnet decision in late 2018



Intermediate experimental stage before IAXO

inal IAXO bores final ones.

igation for full IAXO

BabyIAXO

BabyIAXO: a first stage towards IAXO Letter of Intent to DESY PRC

Date: October 7, 2018 Page 3 of 38

Version: 1.2

Letter of Intent to the DESY PRC

# BabyIAXO: a first stage of the International Axion Observatory IAXO

#### Free bore [m]

Magnetic length [m]

Field in bore [T]

Stored energy [MJ]

Peak field [T]



: CERN



# **Strategy DESY-2030**

### For particle physics

#### **Explore the LHC and beyond**

- Upgrade ATLAS and CMS for HL-LHC
- Prepare leading participation in future global collider project; eagerly awaiting ILC decision from Japan

#### Harvest at Belle II

Data taking and analysis until ~2027

#### **On-site experiments**


- Prepare a future on-site experiment after ALPS-II
- Detector R&D & testbeam operation

#### Theory:


 Maintain broad spectrum of research topics and world-leading expertise


#### DESY as a "hub":

Support projects with large German participation























# Backup









PXD commissioning set-up at DESY




PXD mounted on beam pipe at KEK




PXD half shell ready for transport to KEK




PXD combined with one half of SVD












# **IAXO Conceptual Design**

- Large toroidal 8-coil magnet
   L =~20 m
- 8 bores: 600 mm diameter each
- 8 x-ray telescopes + 8 detection systems
- Rotating platform with services



## **IAXO Magnet & Optics**


### **IAXO** telescopes


- Slumped glass technology with multilayers
- Cost-effective to cover large areas
- Similar to NuSTAR optics
- Focal length ~5 m
- 60-70% efficiency
- LLNL+UC+DTU + MIT + INAF






Cryostat





### **IAXO** magnet

- Superconducting "detector" magnet.
- Toriodal geometry (8 coils)
- Based on ATLAS toroid technical solutions.
- **CERN+CEA** expertise
- 8 bores / 20 m long / 60 cm Ø per bore



Baseline developed at:


IAXO Conceptual Design: JINST 9 (2014) T05002


(arXiv:1401.3233)

кованоп эуысМ

# **BabylAXO**

Magnets ontics detectors







"Common coil" configuration chosen Minimal construction risk: move to construction asap

Cost-effective: Best use of existing infrastructure (tooling) at CERN Winding layout very close to current IAXO toroidal design.

Optics - baseline option: Segmented-glass and flight spare XMM optics from ESA. Minimal risk to the project

Risk reduction for final IAXO segmentedglass optics

XMM optics specs very close to IAXO optics design


Detectors - baseline option: 2
Micromegas setups
In addition: a R&D generic
platform to improve and tests all
other detection technologies


### **IAXO** and **BabylAXO**

### Milestones and plans

- First concept studies date back to 2011.
- CERN SPSC reviewed positively physics program of IAXO in 2014.
- IAXO progress is being followed by "Physics Beyond Colliders" process at CERN (to provide feedback for the European Strategy Part Phys)
- Collaboration formally established in last year's collaboration meeting at DESY:
  - 17 institutions to sign IAXO bylaws
  - Management structure defined and operative.
- Near term goal defined for the collaboration: BabylAXO
  - Full intermediate experiment with relevant physics potential
- BabylAXO Magnet under design at CERN (Applied fellow)
- Important support decisions obtained recently: ERC funding in 2018. But also, preparatory IAXO projects granted in Germany, Croatia, Spain, US....
- Solid plans towards BabylAXO. First physics could come in 3-4 years. Discussion started towards an MoU, detailed cost sharing and timetable.

# **BabylAXO at DESY**







HERA south hall (former ZEUS experiment hall): preferred site for BabylAXO BabylAXO collaboration suggested review by DESY PRC by spring 2019 → in-depth scrutiny (optics, magnet, cryo, infrastructure, physics, detector, ...)

DESY infrastructure & expertise very well suited to IAXO