



Status of RFD Cryomodule Development

Thomas Jones

on behalf of Crab Cavity collaboration

14th September 2018



Science & Technology
Facilities Council



The Cockcroft Institute
of Accelerator Science and Technology

Lancaster
University




Contents

- Project Planning
- Module Requirements
- Vacuum Specifications
- Cavity String Development
- Cryomodule Design
- Daresbury Laboratory assembly facility development


DQW Cryomodule

World First Crabbing of a Proton Beam in May 2018!

CERN/STFC/LARP Collaboration.



RFD Cryomodule Build Plan




Module Requirements

Fundamental changes to module from DQW SPS;

- Second beam pipe to be introduced.
- Vacuum diagnostic ports to be added to cavity beamline.
- Beam screens will be required in second beam pipe.
- Shielded bellows to be used in both beam lines.
- BCAM system will not be required for LHC.
- Infra-structure and assembly tooling to be updated from DQW SPS to RFD LHC (and modification to suit Daresbury Laboratory facilities).
- Cryomodule length will increase due to longer cavities and addition of vacuum diagnostics, effects OVC, Magnetic and thermal shields.
- Vacuum separation of OVC from service module.
- Cryogenic safety systems to be incorporated into cryomodule.

Module Requirements

Further study is also required in the following areas;


- HOMs designs.
- Cavity design updates required for LHC.  Led to project delays
- Study of active vs passive positioning of the cryomodule.
- Interchangeable helium level probes
- Cooling capacity of LHe vessels as designed.
- Effect of -1.23% tunnel slope on the cryomodule.
- Support structure analysis for RFD cavity (longer cavity and offset FPC).
- BCP processing of RFD cavity due to potentially increased complexity.
- Material selection for radiation resistance.
- Transportation of module from Daresbury to CERN.

Module Requirements



Fixed design areas (will be updated with lessons learned from SPS);

- Cryomodule will contain 2 cavities.
- Cavities will not require active alignment.
- Cavity support system principle (cavities on FPC with additional blade supports).
- Helium tank design should remain fixed.
- Tuner principle (Warm actuation, cold connection).
- Thermal shield design. (Helium gas cooled, copper construction).
- FSI system will remain for LHC, but will not use BCAM.
- Outer vacuum chamber design principle.
- Magnetic Shielding design principle.
- Tooling will be as compatible/similar as practicable to CERN tooling for DQW.


SPS LSS6 integration area



LHC Point 5 integration area




Vacuum schematic



Cavity String

Connections to vacuum diagnostics







Updates :

- New compact RF valves study (new LHC standard which avoid the staging)
- New RF bridge design on going (see next slide)
- New Tuner Frame + double actuation pipes
- New vacuum tank fully welded

Thanks to T.Capelli


Cold-Warm Transition Calculations

- Analyzing the design of Cryomodule CWTs to minimise heat leak to 80 & 2 K
- Calculation developed combines:
 - Thermal resistance networks
 - Non-linear thermal conductivity integrals
 - Thermal contact resistance estimates
 - Iterative temperature convergence




Cold-Warm Transition Calculations

Option 1



Option 2





Option	L2 (mm)	Bellows Convol'	4 x Q80 (W)	4 x Q2 (W)
1	123.8	6.5	13.11	1.61
2	113.4*	4.5	14.11	1.01


Weighting Function of low-temp. refrigeration exergetic cost:

$$Q_{tot} = Q_{5K} * 125 + Q_{70K} * 16$$


Estimated Total Heat Load @ 80 & 2 K




RF bridges (under validation)




Inter-cavities Circular/Circular



Inter-cavities Octogonal/Octogonal



Cold-Warm Transition Circular/Octogonal



Cold-Warm Transition Circular/Circular

Updates :




-4 configurations in design

-1 prototype to be designed and produced for validation tests (RF and mechanical)

Thanks to T.Capelli

Cold Magnetic Shield Modifications

- New cavity geometry clashes with existing shield design
- Cold magnetic shield modified to suit updated cavity-helium vessel





Cold Magnetic Shield Modifications


New Parts: 14

Modified Parts: 3

Unchanged: 7



Outer vacuum chamber




Updates :

- New welded interfaces in order to reduce the work in case of dismantling
- Remove rubber gaskets which couldn't be repaired in the tunnel
- New length (increase of cold/warm transition length and inter cavities length)
- FSI ports with new location and CF flanges (metal gaskets)
- Doors with rubber gasket, with the possibility to weld them if needed

Daresbury Lab Engineering Technology Centre Systems Integration Building



ETC Floor Plan






Machine Centre



Cleaning in Vacuum Lab



Magnet Test Lab



Ovens in Vacuum Lab



Facility reconfiguration

Engineering Technology Centre 3D Layout




ETC ISO 4 Cleanroom




Cavity String lifter selection


4 x Servo Motor



Option 2
Modified commercial car lifter




Lifter Integration



Cavity String Mobile (Trolley)

Cavity String Option 1


4.6m



Cavity String Option 2

3.5m

1.5m




Cavity String Option 3

0.5m

3.5m


0.5m




Now on order

Mobile Cleanroom Assembly Frame

- 3.4 – 4.5 m Mobile Cleanroom Assembly Frame
- Contract Placed with ESE Engineering Aug '18
- Cost: £40k
- Expected Feb '19



Cavity String Mobile (Trolley)



- Green route is for shorter trolley.
- Reduced turning area required, increase in ease of transport gives less risk of damage.
- More space to work around the string on the assembly frame.

Summary

- Cryomodule requirements and design ongoing.
- UK team focussed on Magnetic Shielding, Thermal Shielding and Assembly tooling.
- Facility development at Daresbury has begun.
- Placed order for RFD cleanroom assembly frame.



Questions?



**Science & Technology
Facilities Council**



The Cockcroft Institute
of Accelerator Science and Technology

**Lancaster
University**

