



# Plug development: status, plan and key milestones for intermediate validation, production plan

Y. Leclercq, JB. Deschamps on behalf of the Plug development team : 31 Jan. 2019

***Conceptual design review of the DFX***



# DFX-Triplet plug specifications

- 19 bus bars through the plug:

		$I_{cable}$ [kA]	$N_{cables}$
MQXF	●	18	2
Trim Q1/Q2a/Q2b/Q3	●	7	3
MCBXF%	●	2	12
MBXF (D1)	●	18	2



- Separates 2 Cryogenic volumes:

Helium volumes	Phase Nominal	$T_{nom}$ [K]	$P_{nom}$ [bara]	Design pressure PS [bar]
Triplet cold mass He enclosure	Superfluid	1.8	1.3	20
DFX - SCLink	Sat. liquid	4.5	1.3	3.5

Preliminary\_naming\_parameters\_and\_flow\_diagrams\_for\_HL-LHC  
 Courtesy D. Berkowitz [EDMS1573115](https://edms.cern.ch/record/1573115)

- Design requirements

	Specification
Overall leak rate @ RT (target)	$1.10^{-4}$ mbar.l.s <sup>-1</sup>
Insulation to ground/cable @ RT	4.6 kV
Thermal cycles	50
Radiation levels (1.6m distance from beam)	Dose Neutron fluence 100 kGy $2.10^{14}$ cm <sup>-2</sup>



R.Garcia et al. "LHC and HL-LHC: Present and future radiation environment in the HL collision [...]" [CDS2310128](https://cds.cern.ch/record/2310128)



# DFX-Triplet plug conceptual design

- Bus bars configuration
- 2 different plugs 18 kA & 2 kA


- Physical layout proposal

- Plug LHC inspired design proposal:


- From 13 kA LHC plug
- From 3 x 6kA LHC plug

	$I_{\text{cable}}$ [kA]	$N_{\text{cables}}$	Cable type		
			Triplet side	Plug	DFX side
MQXF	18	2	18 kA Nb-Ti round	2 x MQXF leads	2 x MQXF leads or round
MBXF (D1)	18	2	13 kA Nb-Ti flat		1 x MQXF lead or round
Trims	7	3	18 kA Nb-Ti round		
MCBXF%	2	12	6 kA Nb-Ti round	LHC 6 kA	MCBXF + Cu or round




D1 interface configuration



Plug proposal



SCLink configuration



# Bus-bar design

	$I_{\text{cable}}$ [kA]	$N_{\text{cables}}$	Cable type		
			Triplet side	Plug	DFX side
MQXF	18	2	18 kA Nb-Ti round	2 x MQXF leads	2 x MQXF leads or round
MBXF (D1)	18	2	13 kA Nb-Ti flat		1 x MQXF lead or round
Trims	7	3	18 kA Nb-Ti round		
MCBXF%	2	12	6 kA Nb-Ti round	LHC 6 kA	MCBXF + Cu or round


Nb-Ti bus: same amount of Cu stabilizer in cable on magnets side, in cable in plug and in cable in DFX

Nb-Ti to Nb-Ti splices: specific development - with associated measurement campaign


# Infrastructure & Know-How

Procedures 6kA, 13kA & N line LHC plugs


- Know-how from LHC experience
  - Various plugs types and technologies
  - Drawings, manufacturing procedure
  - Qualification procedures




Drawings LHC plugs




Line N LHC plugs



6 kA LHC plugs



13 kA LHC plugs






CF




# Infrastructure & know-how

- Dedicated laboratory in SMI2
  - Tooling & plug design area
  - Preparation area
  - Injection area
  - Qualification area
- Train staff on LHC type plugs
  - Design & manufacturing of tooling/plug
  - Optimisation of manufacturing & QA procedures




Some plugs developed at SMI2



# Plug general manufacturing & qualification procedure

- Plug Cable preparation
  - Soldering into copper structure
    - (if required)
  - QA: leak test of soldered cable
  - Surfaces preparation for gluing
    - Sand blasting, plasma treatment
- Parts preparation
    - Warm up & degassing
  - Glue injection under vacuum
  - Qualification
    - Leak test @ RT :  $1.10^{-4}$  mbar.l.s<sup>-1</sup>
    - 10 x thermal cycling in LN2
    - Pressure test (EN13458-2)
    - Leak test @ RT :  $1.10^{-4}$ mbar.l.s<sup>-1</sup>

*Cable preparation*



*Parts warm up*

*Parts Degassing*

*Soldering cable to copper*






*Glue injection under vacuum*

*Glue tightness qualification*

*QA test for solder qualification*




*Thermal cycling in LN2*



# Schedule & plan

- Equip Laboratory, Know-How & define procedures
- Bus bars definition
- Plug layout proposal
- Manufacture and test demonstrator
- Review of design before prototype production
- Prototype manufacturing & qualification
- Available for assembly in test proto
- Series production (@ SMI2 ; 4 + 4 spares)





# Spare slides