



# HL-LHC Crab Cavity Review

## Introduction and Overview

O. Brüning

CERN, 19 June 2019

# HL-LHC Crab Cavity Review


## Introduction and Overview

The project management calls this review to assess if the present design of the cavities with their cryomodules and all ancillaries is adequate to meet the required performance and if the production plan is well harmonized with due margin (considering the complex scheme with many in-kinds) in the HL-LHC schedule.

**Review Panel members:** Akira Yamamoto (Chair, CERN), Edward Daly (JLAB), Carlo Pagani (INFN), Sébastien Bousson (IN2P3) and Delio Duarte Ramos (CERN).

**Review link persons:** R. Calaga (CERN), T. Jones (UK-STFC), B. Laxdal (TRIUMF), L. Ristori (US-AUP)

# LHC / HL-LHC Plan



## HL-LHC TECHNICAL EQUIPMENT:

DESIGN STUDY

PROTOTYPES

CONSTRUCTION

INSTALLATION & COMM.


PHYSICS

## HL-LHC CIVIL ENGINEER:

DEFINITION

EXCAVATION / BUILDINGS

# Goal of High Luminosity LHC (HL-LHC):




# implying an integrated luminosity of  **$250 \text{ fb}^{-1}$**  per year,  
# design oper. for  $\mu \delta$  **140** ( $\rightarrow$  peak luminosity  **$5 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$** )

$\rightarrow$  Operation with levelled luminosity!


$\rightarrow$  10x the luminosity reach of first 10 years of LHC operation!!

# Luminosity Levelling


- In certain conditions and depending on the experiments request, it is desirable to adapt the luminosity dynamically with beams in collision – **levelling**
- Each levelling technique has its advantages and drawbacks




Levelling by beam offset / separation



Levelling by crossing angle




Levelling by  $\beta^*$  (= beam size at IP)



All levelling Options have been successfully demonstrated in LHC Run2!!!

# Luminosity Optimization: Crossing Angle & Crab Cavities

## Insertion Layout:




## Parasitic bunch encounters:

Operation with ca. 2800 bunches @ 25ns spacing  $\rightarrow$  approximately 30 unwanted collision per

Interaction Region (IR)

$\rightarrow$  Operation requires crossing angle



## non-linear fields from long-range beam-beam interaction:

efficient operation requires large beam separation at unwanted collision points  $\rightarrow$  Separation of 10 -12  $\sigma$   $\rightarrow$  luminosity reduction!!!

# Luminosity Optimization: geometric

## reduction

### Crab Cavity Luminosity


#### Reduction Factor:

- Reduces the effect of geometrical reduction factor
- Independent for each IP

$$F = \frac{1}{\sqrt{1+Q^2}}; \quad Q \propto \frac{q_c S_z}{2S_x}$$

- Challenging space constraints:

→ requires novel compact cavity design



# Crab Cavities Implementation for HL-LHC

HL-LHC baseline [after re-baselining in 2016]:

2 Crab Cavities in one cryostat on each side of the main Interaction Points per beam → 8 Crab Cavities per IP  
→ 16 Crab Cavities in total


IP1: horizontal crossing angle and CC deflection

IP5: vertical crossing angle and CC deflection

→ Two types of Crab Cavities [horizontal and vertical]

HL-LHC baseline: full overlap with CC and  $\beta^*$  levelling





HL-LHC WP15

# HL-LHC cavity designs

Double Quarter Wave



2 Designs with  
Different Coupler concepts and  
Deflection planes

$$f_0 = 400 \text{ MHz}$$

$$V_T = 3.4 \text{ MV}$$

$$(E_p, B_p < 40 \text{ MV/m}, 70 \text{ mT})$$


$$\text{Beam aperture} = 84 \text{ mm}$$

$$\text{Beam-to-beam dist} = 194 \text{ mm}$$

Common FPC

DQW crab-cavity  
Cryomodule for  
SPS tests


RF Dipole



# Crab cavity cryo-module for installation in the SPS



Magnetic shields  
from UK  
(UNILAN-CI)



# Compact Crab Cavity: SPS Installation




Commissioned in 2018 and now ready for operation with beam!!!

New SRF infrastructure in the SPS!!


# First proton crabbing ever!

TEST in SPS ongoing since 2018

Crabbing Voltage from Head-Tail Monitor  
2018-05-23 17:02:39



Study and R&D has been very useful to obtain this result



RFD proto: delayed design will not be installed in LS2

# Multi-National Collaboration


- Cavity Design: US-LARP [SLAC, LBNL, BNL and FNAL], Lancaster, ODU, CERN
- Prototyping:
  - DQW: Manchester, Liverpool, Lancaster, CERN & **LARP-NIOWAVE [DOE-SBIR]**, [KEKB electro-polishing]
  - RF-Dipole: **LARP-NIOWAVE [DOE-SBIR]**, CERN, JLAB, ODU, FNAL-ANL
- Production:
  - DQW: **CERN**, **UK-STFC** Lancaster & **RI**
  - RF-Dipole: CERN, **AUP-FNAL**, JLab, **TRIUMF** & **Zanon**
- Power: Solid State Power Sources: **BINP Novosibirsk [Russia]**

# In-kind Contribution

- UK1 – RFD-Cryomodule prototype with CERN providing dressed cavities & partial components
- US-AUP – 10 RFD dressed cavities (He-tank, HOMs, Field Ant)
- UK2 – 4-DQW cryomodules with CERN providing dressed cavities & partial components [and CERN building 1 DQW CM]
- TRIUMF – 5-RFD cryomodules with US-AUP providing dressed cavities and CERN with partial components
- Novosibirsk – Proposal to provide SSPA amplifiers jointly with Russian industrial partner [special Russian contribution]

# Masterplan

See Rama's presentation for details!






# Review Goals

- Review of the CC System readiness for production
  - Pre-series will be launched in 2019 before we can finalize RF-Dipole tests in the SPS
  - Multi-National and Multi-Laboratory network for series production
    - are all interfaces sufficiently defined and established?
- Future SPS test:
  - What is missing from the DQW SPS tests?

- Reserve

# Completion of the shaft excavation at Point 1



Shaft picture seen from the bottom



Reinforced concrete ring at the shaft end

# Start of cavern excavation at Point



Hydrocarbon presence  
(as expected)



# C.E. : so far so good with a few issues under control Some necessary modification causes moderate extra-cost.




Panoramic view (08 Apr 19) - Contract T118 – CIB (P5)



# LHC 2017 : separation levelling

- Introduced separation levelling for all experiments (Separation levelling is used since many years for ALICE and LHCb)
- Dynamic orbit bump changes overlap of colliding bunches
- Initial spike before leveling reaching  $2.2 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$

Max. lumi      With separation





# International Review of the Crab Cavity system design and production plan for the HL-LHC

19-21 June 2019

CERN

Europe/Zurich timezone

Overview

Timetable

Contribution List

My Conference

My Contributions

Registration

Participant List

Accommodation

Practical information

Elodie Kurzen

 [elodie.kurzen@cern.ch](mailto:elodie.kurzen@cern.ch)

 00.41.75.411.87.46

The CC system is a critical equipment in the HL-LHC project. Following the construction of the first HL-LHC CC cavities at CERN and in the US, and the crash program for the SPS DQW cavity cryomodule construction and installation in the new SPS facility, the first tests with proton beam in a CC were successfully achieved in the SPS during 2018. The final design of CC and the complete cryomodule is being finalized, both for DQW (double quarter wave) and RFD (RF Dipole) types, while the construction of a second complete cryomodule prototype (RFD type) is under construction by CERN and UK. The in-kind contribution from US-AUP (all dressed cavities of RFD type), UK-STFC and Lancaster U. (four DQW cryomodule assemblies) and Canada-Triumf (five RFD cryomodule assemblies) are agreed or in final negotiation stage. The construction of the DQW jacketed cavities by Industry for CERN is already under way.

The project management calls this review to assess if the present design of the cavities with their cryomodules and all ancillaries is adequate to meet the required performance and if the production plan is well harmonized with due margin (considering the complex scheme with many in-kinds) in the HL-LHC schedule.

**Review Panel members:** Akira Yamamoto (Chair, CERN), Edward Daly (JLAB), Carlo Pagani (INFN), Sébastien Bousson (IN2P3) and Delio Duarte Ramos (CERN).

**Review link persons:** R. Calaga (CERN), T. Jones (UK-STFC), B. Laxdal (TRIUMF), L. Ristori (US-AUP)

**Date and Place:** The review is scheduled from **19 June afternoon to 21 June 2019** at CERN, room **774-R-013**.



The CC system is a critical equipment in the HL-LHC project. Following the construction of the first HL-LHC CC cavities at CERN and in the US, and the crash program for the SPS DQW cavity cryomodule construction and installation in the new SPS facility, the first tests with proton beam in a CC were successfully achieved in the SPS during 2018. The final design of CC and the complete cryomodule is being finalized, both for DQW (double quarter wave) and RFD (RF Dipole) types, while the construction of a second complete cryomodule prototype (RFD type) is under construction by CERN and UK. The in-kind contribution from US-AUP (all dressed cavities of RFD type), UK-STFC and Lancaster U. (four DQW cryomodule assemblies) and Canada-Triumf (five RFD cryomodule assemblies) are agreed or in final negotiation stage. The construction of the DQW jacketed cavities by Industry for CERN is already under way.

The project management calls this review to assess if the present design of the cavities with their cryomodules and all ancillaries is adequate to meet the required performance and if the production plan is well harmonized with due margin (considering the complex scheme with many in-kinds) in the HL-LHC schedule.

**Review Panel members:** Akira Yamamoto (Chair, CERN), Edward Daly (JLAB), Carlo Pagani (INFN), Sébastien Bousson (IN2P3) and Delio Duarte Ramos (CERN).

**Review link persons:** R. Calaga (CERN), T. Jones (UK-STFC), B. Laxdal (TRIUMF), L. Ristori (US-AUP)