



Protons see Crabs



Crabbing Voltage from Head-Tail Monitor
2018-05-23 17:02:39





Overview of Crab Cavities for HL-LHC

HL-LHC WP4, CERN

International Review of the Crab Cavity system design and production plan for the HL-LHC


Big thanks to BE, EN, TE, HSE, IPT departments
& Canada, UK, US collaborations and all involved



WP04-CC Scope


16 SC compact crab cavities to partially compensate the geometric angle ($500 \mu\text{rad}$) at ATLAS+CMS.
 Beam tests in the SPS protons

today





TDR-Basic Parameters

- Frequency = 400.79 MHz
- Aperture = 84 mm
- Voltage = 3.4 MV /cavity (2 cavities /beam /IP side – 16 total*)
- Frequency tuning = ± 150 kHz
- $Q_{ext} = 5 \times 10^5$, RF power to cavity = 40 kW (80 kW peak)
- $P_{static} = 18$ W, $P_{dyn} \leq 30$ W (per module)
- Operating temperature = 2.0 K



*For full compensation, 4 cavities /beam /IP side

Workpackage Structure



Past Reviews & Outcome

- **May 2014:** Cavity design review
 - Led to down selection to 2 cavities (DQW, RFD) for SPS-test/LHC
- Feb 2015: 1st HOM coupler review
- Mar 2015: Cost & Schedule review I
 - Study the effect of only ½ of system (16 instead of 32)
- May 2015: CERN-STFC Helium vessel review
- **Nov 2015:** SPS Cryomodule review
 - Develop minimum goal for SPS tests, review individual critical components, integrated production/test planning including infrastructure
- Oct 2016: Clean room assembly review
- Oct 2016: Cost & Schedule review II
 - Reduction to ½ system, HPRF 40 kW-CW
- Nov 2016: Operational safety review in SPS
- **April 2017:** Crab cavity performance review for HL-LHC
 - Perform SM18 tests prior to SPS installation with minimum success criteria, establish formal agreements, specifications, acceptance criteria and interfaces
- Mar 2018: Cost & Schedule review III
 - Endorsed with new strategy (UK, US-AUP, Canada)

Mandate for 2019 Review

Full Mandate


- CQ1: SPS-CC experience & lessons learned to be implemented into HL-LHC CC
- CQ2: SPS beam tests & extrapolation to HL-LHC, open questions ?
Readiness of RFD pre-series cryomodule?
- CQ3: Readiness for series production? Open points being addressed
implying changes
- CQ4: Status of HPRF, LLRF and other auxiliary components, do we need
further attention over the coming years?
- CQ5: Baseline schedule including collaborations w.r.t HL-LHC schedule?
Management of in-kind and preparations for work framework – risks for
production/testing ?
- CQ6: Is CERN ready to finalize the agreements (status of acceptance
criteria & procedures of different sub-components)
- CQ7: QA/QC and risks for deliverables between partner labs

Agenda of this Review

- Introduction
 - Overview of main systems + integration/interfaces
- SPS-tests Hardware & Beam Experience
- HL-LHC Pre-Series status & Series preparation
- HL-LHC main interfaces & integration
- Specifications, norms, conformity & safety

Reminder: Dressed Cavity Geometries

Double Quarter Wave



$$f_0 = 400 \text{ MHz}$$

$$V_T = 3.4 \text{ MV}$$




($E_p, B_p < 40 \text{ MV/m}, 70 \text{ mT}$)

Beam aperture = 84 mm

Beam-to-beam dist = 194 mm

Common FPC = 40 kW-CW

RF Dipole




Vertical Cavity Tests (6 Cavities)

Nominal Spec $V_{\text{kick}} = 3.4 \text{ MV}$

		DQW #1 (CERN)	DQW #2 (CERN)	DQW #1 (USLARP)	DQW #2 (USLARP)	RFD #1 (USLARP)	RFD #2 (USLARP)
Max Volt	[MV]	5.04	4.8	5.8	5.3	5.0	5.75
E_p, B_p [MV/m, mT]		56, 109	54, 103	65, 125	59, 114	42, 73	56, 96
R_s min	[n Ω]	10	10	9	9.5	11	7.6
R_s , 3.4MV	[n Ω]	15	18	15	17	13	8.2
Max Volt with HOM	[MV]	3.3*	-	-	4.7	-	5.5

CERN DQW



USLARP DQW & RFD



* Voltage limit for SPS-DQW with HOMs due to inadequate BCP of HOMs

Summary of SPS-test Experience

- Bare cavity performance is +50% of the nominal voltage
 - In SM18 dressed cavities exhibited limit $\sim 3\text{MV}$, now understood
 - Performance of the SPS-test module limited to 1MV for machine developments, 2MV stable
- First crabbing of protons demonstrated. Main aspects such as transparency, beam loading, emittance growth, crab dispersion and other aspects studied – no show stopper
- Several hardware limitations: direct beam coupling, pondermotive instabilities, RF non-linearity at low power, RF/Cryo/Vacuum stability beyond 2MV..
- Consolidation of SPS test stand underway during LS2 with 2021 operation of DQW and 2022 RFD

Main Modifications since SPS-test

- Cavity design evolution
 - RFD cavity design updated for reduction in HOM power from most dangerous HOM at 760 MHz, DQW HOM coupler improved for better damping
 - DQW & RFD field antenna design change to reduce direct beam coupling, including modification to 25Ω for all RF feedthroughs
- RFD-Cryomodule prototype fully compatible HL-LHC (Cryogenics, Vacuum & RF interfaces)
- Strong effort towards solid state for HPRF
- LLRF improvements for faster RF setup & migration from VME \rightarrow μ TCA beyond LS2

Highlights, since last review


- DQW-SPS prototype demonstrates with first ever crabbing with protons, transparency & high intensity demonstrated. Detailed studies will continue in 2021
- DQW-HL-LHC jacketed cavities contract with RI signed & ongoing
- DQW-HL-LHC cryostating in final stages of negotiation for building 1-CERN and 4-UK
- RFD-SPS test cavity fabrication started at CERN, cryostating to be performed at UK and the conceptual design is almost complete
- RFD-HL-LHC dressed cavities in-kind contribution from US-AUP with CD2 approval & progressing well
- RFD-HL-LHC cryostating as in-kind from Canada-TRIUMF, detailed agreement in preparation
- Discussions ongoing with Novosibirsk for an in-kind contribution of high power RF amplifiers using solid state technology
- Big effort on integration for HL-LHC, including design adapted for left/right IP symmetry and IR1/5 swappable option

WP4 Planning & Collaborations

- Update strategy & planning in place since last review including 3+ collaborations
- In-kind contributions
 - UK1 – RFD-Cryomodule prototype with CERN providing dressed cavities & partial components
 - US-AUP – 10 RFD dressed cavities (He-tank, HOMs, Field Ant, Cold B-shields)
 - UK2 – 4-DQW cryomodules with CERN providing dressed cavities & partial components
 - TRIUMF – 5-RFD cryomodules with US-AUP providing dressed cavities and CERN with partial components
 - Novosibirsk – Proposal to provide SSPA amplifiers jointly with Russian industrial partner – pending final approval

Masterplan WP4-CC

28/05/2019



SPS-test CMs

HL-LHC CMs

RF Services

WP4- PSM 2019
4th review

Baseline: Dec -2018



WP4, Documentation QA/QC








- EDMS/MTF WP4 - [CERN-0000096385](https://cds.cern.ch/record/0000096385)
 - Centrally managed (specifications, drawings, manufacturing inspection plans, test procedures, results, quality control)
- Strategy for compliance: An engineering specification along with specification drawing (where applicable) for each main component. Also includes acceptance criteria
- Safety folder (SPS-test & HL-LHC)

Specification Documents	Document Number	Status
Dressed cavities	EDMS 1389669	V2.49 <i>final editing</i>
Cryomodule	EDMS 2043014	V0.1 for WP4 internal circulation
SSA System Safety Assessment	EDMS 2010001	V0.13 Engineering check
Guidelines for compliance with CERN safety rules	EDMS 2058183	V0.2 Eng. Check + Memo from HSE to WP4

Summing Up



- SPS-test Crab Cavities
 - Despite many hurdles, a monumental effort was put in to conclude 2018 beam tests a success – hunt for higher voltage and beam current in 2021
 - Many lessons learned are being implemented for RFD-prototype jointly with UK & US, it is on schedule for 2022 SPS tests
- HL-LHC Crab Cavities
 - RI-DQW pre-series contract progressing well, RFD industrial prototypes under US-AUP progressing well. SSPA with Novosibirsk looks very promising
 - Challenging year to consolidate the detailed specifications, responsibilities between CERN and external partners and adapt planning
 - Communication between CERN & external partners has ramped up significantly in 2019 – very healthy sign

Thank You !



HL-LHC Cryomodule Layout

- RFD-proto already HL-LHC type
- Both types of cryomodules integrated in the IR
- 1-spare module per type (or IR) with left/right symmetry. Also swappable between IRs
- Integration & interfaces with all services in advanced stage



P. Fessia et al