



# US Contribution to SPS Crab Cavity Prototypes and Lessons Learned

Alessandro Ratti - SLAC  
for the LARP and AUP collaboration



Review of CC System Design and Production Plan – Jun 19<sup>th</sup>–21<sup>st</sup>, 2019

# Outline

- A historic perspective of crab cavities in LARP
- Cavity development path and processes
- Production history and results
- Test results of all LARP cavities
- Summary of major program accomplishments

# Historic Perspective

- CC proposal started before the commissioning of the LHC
  - First CC workshop (CC-08 BNL/LARP/CARE-HHH) held at BNL 24-5 Feb. 2008
  - Motivated by the great benefit in luminosity leveling and coping with the necessary crossing angles in the LHC
  - HL-LHC makes it even more compelling
- Initial challenge → demonstrate sufficient deflecting voltage in the limited space available = Local vs. Global
  - Beampipe separation 40 cm
  - Limited longitudinal space in the IR → significant gradients
- Three candidate designs were built and successfully tested by 2013
  - LARP led the DQW and RFD;
  - STFC led the 4-rod cavity
  - All PoP cavities built by Niowave

# Initial Cavity System Requirements

■ Resonance frequency [MHz]	400.79
■ Bunch length [ns]	1.0 (4 $\sigma$ )
■ Maximum cavity radius [mm]	$\leq 145$
■ Nominal kick voltage [MV]	3.4
■ R/Q (assumed, linac convention) [ $\Omega$ ]	400
■ Dynamic Load	$\sim 3\text{W}$ (for SPS)
■ $Q_{\text{ext}}$ (fixed coupling range)	$3 \times 10^5 - 5 \times 10^5$
■ RF power [kW]	80
■ Power coupler OD (50 $\Omega$ ) [mm]	62
■ LLRF loop delay [ $\mu\text{s}$ ]	$\approx 1$
■ Cavity detuning [kHz]	$\approx 1.0$



# First LARP Results – the PoP Program

2008-2013


- Demonstrated EM conceptual design and feasibility
- Not ready for beam
- No peripherals

# LARP PoP Test Results


2013




# RFD - Proof-of-Principle Design



Proof-of-Principle cavity fabricated at Niowave Inc.





**E Field**



**B Field**

Parameters	Value	Units
Frequency of fundamental	400	MHz
Frequency 1 <sup>st</sup> HOM	590	MHz
Deflecting Voltage ( $V_t^*$ )	0.375	MV
Peak Electric Field ( $E_p^*$ )	4.02	MV/m
Peak Magnetic Field ( $B_p^*$ )	7.06	mT
$B_p^*/E_p^*$	1.76	mT/(MV/m)
Stored Energy ( $U$ )	0.195	J
$[R/Q]_t$	287.0	$\Omega$
Geometrical Factor ( $G$ )	140.9	$\Omega$
$R_t R_s$	$4.0 \times 10^4$	$\Omega^2$

At  $E_t^* = 1$  MV/m



Bead pull measurements of on axis electric and magnetic field components

# Two Crab Cavity Designs Selected

May 2014

- LARP supported the R&D that led to both designs that are part of the baseline HL-LHC design
- Proof of Principle cavities were built and tested in a VT
  - Successful measurements demonstrated feasibility
- Both LARP designs were chosen to address kicks in the H (CMS) and V (ATLAS) planes.
- **Two main reasons to keep both designs:**
  - HOMs are a dominant factor
    - different cavities have different spectra
  - Cryomodule integration
    - 90 deg rotations are “easy” only in principle



# First LARP Prototype Cavities

- We started a program to build two DQW and two RFDs
  - Complete with tuners, couplers (HOM and pickups) and He tanks
- Funding was not available through LARP
- Cavities were developed through small business grants from DOE to Niowave



# Functional Specification for SPS tests



- System Specifications
- Functional parameters
  - Including HOMs, Z...
- Enclosures (incl. materials...)
- Cryogenics
- RF Power incl. couplers
- LLRF
- SPS Integration

Released by CERN in Feb. 2013

Updated for HL-LHC



CERN-ACC-NOTE-2013-003

**HiLumi LHC**

FP7 High Luminosity Large Hadron Collider Design Study

**Scientific / Technical Note**

## Functional Specifications of the LHC Prototype Crab Cavity System

Baudreghien, P  
*et al*

28 February 2013



The HiLumi LHC Design Study is included in the High Luminosity LHC project and is partly funded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404.

This work is part of HiLumi LHC Work Package 4: Crab cavities.


The electronic version of this HiLumi LHC Publication is available via the HiLumi LHC web site <<http://hilumilhc.web.cern.ch>> or on the CERN Document Server at the following URL: <<http://ods.cern.ch/search?p=CERN-ACC-NOTE-2013-003>>

# QA Requirements for Manufacturing Readiness

Due 1 month before start of manufacturing for CERN approval

#	Requirements
1	Niobium material samples according to Section 3.2
2	Material certificates and quality control of raw materials (including RRR measurements)
3	Material certificates of welding consumables (whenever applicable)
4	Functional and manufacturing drawings (with tolerances)
5	Design reports demonstrating that welds are designed to withstand the specified load cases (refer to Section 3.6.1)
6	Welding plan including: <ul style="list-style-type: none"><li>• Welding maps</li><li>• Welding and brazing procedure qualification record including CERN acceptance criteria in Section 4.2 (WPQR and BPQR)</li><li>• Welding and brazing procedure specification (WPS and BPS)</li><li>• Welders performance qualification (GTAW), Welding and Brazing Operators Performance Qualifications (electron-beam welding and vacuum brazing) – WPQ, WOPQ and BOPQ</li></ul>
7	Manufacturing procedures (whenever required in Annex 6.3)
8	Test procedures (whenever required in Annex 6.3)
9	EB welded and vacuum brazed samples according to the requirements specified in Section 3.8.4
10	NDT personnel qualifications
11	Manufacturing and inspection plan (MIP) – list of all manufacturing and quality control operations.


# Initial RFD Cavity Design for SPS




Frequency	400	MHz
Aperture	84	Mm
Nearest HOM	633.5	MHz
$E_p^*$	3.6	MV/m
$B_p^*$	6.2	mT
$[R/Q]_t$	429.7	$\Omega$
Geometrical Factor ( $G$ )	106.7	$\Omega$
$R_t R_s$	$4.6 \times 10^5$	$\Omega^2$
At $E_t^* = 1.0$ MV/m		
$V_t$	3.4	MV
$E_p^*$	33	MV/m
$B_p^*$	56	mT

- Operates in  $TE_{11}$  like mode
- Next HOM is 1.5 times fundamental mode
- Multipacting is improved compared to P-o-P cavity
- Surface fields are lower compared to P-o-P cavity
- Shunt impedance higher compared to P-o-P cavity
- Reduced multipoles components with curved poles

# FPC & HOM Coupler Designs



- FPC/HOM ports oriented to keep clearance for the second beam pipe
- Couplers at locations of low field region on cavity body
  - Minimizes RF heating on the coupler components
- Location preserves field symmetry
  - Electrical center moved by only 50 microns
- H-HOM coupler with 30 degree hook orientation with no change to filter elements



- Selective coupling (V-HOM) to reduce the number of filters
  - 7 mm offset incorporated into the pickup tip to enhance coupling to the dipole modes at around 2GHz
  - Small RF power leakage through the coupler, ~1.5W, due to asymmetry
- FPC coupler:  $Q_L = 5.0 \times 10^5$ 
  - Hook shaped coupler reduces RF heating → 69 W

Zenghai Li, S de Silva, J Delayen



# Beam Pipe Testing Summary



## Assembly and Dimensions:

- Some dimensions are not compliant with spec. tolerances
  - The parallelism between the flange and the ring, and the diameter of the ring are the most relevant tolerances not achieved
- The knife edge is acceptable

## Welding and brazing:

- Radiographic tests were acceptable
- Metallurgic tests were acceptable

# DQW – Assembly and Specifications





# DQW Main Components



**NIOWAVE**  
[www.niowaveinc.com](http://www.niowaveinc.com)








# RFD – Main Components



**NIOWAVE**  
[www.niowaveinc.com](http://www.niowaveinc.com)

# Nb Parts Measurements

- GREY AREA DEPICTS A CHECK FIXTURE ALLOWING FORM TO BE MEASURED. CHECK FIXTURE MADE WITH A .25MM GAP FROM THE NOMINAL CAKE PAN FORM.
- MATERIAL THICKNESS MEASUREMENTS WERE TAKEN WITH DIGITAL CALIPERS AT 12MM INCREMENTS.
- SHIM STOCK WAS USED ALONG THE FLAT GAUGE PINS IN RADIUS.



TOLERANCES: UNLESS OTHERWISE SPECIFIED, ARE IN MILLIMETERS	PROJECT MANAGER APPROVAL: DATE:	
.XX = ± 0.1 .XXX = ± 0.01 XXXX = ± 0.005 XX* = ± 0.5 XX* = ± 0.1*	MODELED BY: DATE:	
PROPRIETARY & CONFIDENTIAL INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF NIOWAVE, INC. ANY REPRODUCTION IN PART	DETAILED/ CHECKED BY: DATE:	
	MANUFACTURING APPROVAL: DR. TERRY GRIMM DATE:	
	TITLES:	
	MATERIALS:	
	ESTIMATED WEIGHT: 6.66 lbs	
		SCALE: 1:1



# RFD Subassemblies at Jefferson Lab




**NIOWAVE**  
[www.niowaveinc.com](http://www.niowaveinc.com)





# DQW Sub-Assemblies at BNL



**NIOWAVE**  
[www.niowaveinc.com](http://www.niowaveinc.com)



# Issues with Cavity Production at the company

- Some tests and qualifications not shared or not verified
  - I.e. parts unavailable for a few months until after welding
- Company treated several steps as proprietary information
- After the fact QA showed some non compliances that were not reported
  - I.e. double weld on RFD external assembly

# Role of LARP cavities

- Due to lack of documentation and inspections, CERN was forced to run a rush program to complete cavities (and CMs) for the SPS beam test of 2018
  - See the next talk
- Nevertheless the LARP cavities played a crucial role developing processes and understanding limits and performance





# Summary of LARP/CERN Cavities Test Results

	CERN DQW1	CERN DQW2	LARP DQW1	LARP DQW2	LARP RFD1	LARP RFD2	LARP RFD1 @FNAL
VMax [MV]	5.0	4.8	5.9	5.3	4.4	5.7	5.02
Epeak [MV/m]	56	54	65	58	42	54	56
Bpeak [mT]	109	103	125	113	73	95	109
Rs min [nOhm]	10	10	9	10	11	7	
Rs @ 3.4MV [nOhm]	15	18	15	12	13	9	
FE onset [MV]	4.0	3.5	4.1	2.8	> 4.4	4.5	
Q0 max			9.2E+9	8.8E+9	1.1E+10	1.5E+10	1.5E+10
Q0 @3.4MV			6.2E+9	7.3E+9	8.5E+9	1.2E+10	1.1E+10

# Niowave RFD Cavities at JLAB


- Two cavity sub assemblies arrive at JLAB




28 April 2016

# RFD Process Flow at JLAB

Inspection and frequency measurement between each step



# RFD final Machining at JLAB



BNL  
CERN  
LU/STFC  
JLAB  
ODU  
SLAC

contributed



27 Oct 2016




Review of CC System Design and Production Plan – Jun 19<sup>th</sup>–21<sup>st</sup>; 2019

# SPS-RFD Cavity: Trimming Sensitivity

Trimming sensitivity for RFD cavities

$$df/dz = -119.85 \text{ kHz/mm}$$





Measured sensitivity:

- CAV001: -129.3 kHz/mm
- CAV002: -116.1 kHz/mm




Good agreement with simulations



S. DeSilva - ODU

# HOM Dampers Fabrication Process





	Niobium (RRR>300)
	316L SS (Helium Jacket)
	316LN SS (Flanges)

**Jlab**



# HOM Dampers Fabrication

Temperature  
 Type: Temperature  
 Unit: K  
 Time: 1  
 Custom  
 Max: 11.299  
 Min: 2



**Jlab**



# Summary of LARP RFD test data


Test Date	Cavity #	Location	HHOM	VHOM	MAX V	Q AT 4.1 MV	Low field Q
2/12/2017	LARP RFD#1	JLab			4.04	1.60E+09	1.23E+10
3/23/2017	LARP RFD#1	JLab			4.38	8.21E+09	1.03E+10
6/2/2017	LARP RFD#2	JLab			5.75	1.13E+10	1.46E+10
8/20/2017	LARP RFD#1	FNAL			4.70	1.10E+10	1.95E+10
4/30/2018	LARP RFD#1	FNAL			3.54	N/A	1.49E+10
5/8/2018	LARP RFD#2	JLab	YES	YES	4.77	1.22E+09	measure error
5/31/2018	LARP RFD#2	JLab	YES	YES	5.03	1.32E+09	1.45E+09
6/13/2018	LARP RFD#1	FNAL			3.47	N/A	1.67E+10
8/16/2018	LARP RFD#2	JLab	YES		5.26	6.60E+08	7.18E+08
10/9/2018	LARP RFD#2	JLab	YES		4.18	1.08E+09	1.56E+09
11/14/2018	LARP RFD#2	JLab	YES	YES	5.50	5.00E+09	6.50E+09
11/28/2018	LARP RFD#2	JLab	YES	YES	5.50	7.35E+09	1.05E+10
3/27/2018	LARP RFD#2	JLab	YES	YES	5.33	6.50E+09	9.00E+09
5/2/2019	LARP RFD#1	FNAL			5.10	1.00E+10	1.50E+10



# Summary of LARP DQW test data

Test	Assembly	Surface preparation		Max Vt (MV)	FE (MV)	Q0, low	Q0,nom	CX	LFD
		Cavity	HOM filter				[P (W)]		(Hz/(MV) <sup>2</sup> )
Feb'17	DQW01	Bulk BCP, 600C, light BCP, HPR, 120C	N/A	5.9	4.1	1.00E+10	6.00E+09	#B-2	
							[4.5]	#F-4	
May'17	DQW01+HOM01	None	Flash BCP (on hook); rinse	2.8	n/a	1.00E+10	n/a	#B-5	-450
	Flange set #b							#D-7	
								#E-8	
Jun'17	DQW02	Bulk BCP, 600C, light BCP, HPR, 120C	N/A	5.3	3.3	9.00E+09	5.00E+09	#A-567	
							[5.4]	#F-4	
Sep'17	DQW02	Light BCP, HPR	N/A	5.3	4.1	1.00E+10	6.00E+09	#C-1	-554
							[4.5]	#A-7	
							6.00E+09	#F-4	
Oct'17	DQW02+HOM01	Light BCP, HPR	Flash BCP (on hook); rinse	3.6	n/a	1.00E+10	[4.5]	#D-7	-499
	Flange set #a							#E-8	
Jan'18	DQW02+HOM01	None	100 um BCP, 600C, light BCP, rinse	3.1	2.6	1.00E+10	n/a	N/A	-599
	Flange set #a								
May'18	DQW02+HOM01	HPR, 120C	Rinse, 120C	4.7	3.2	1.00E+10	7.00E+09	None	-772
	Flange set #a						[3.8]		
Jul'18 (testing anomaly)	DQW02+HOM01	HPR, 120C	Rinse, 120C	5.9	None	8.00E+09	5.00E+09	N/A	
	20mm NbTi spacer						[5.4]		
	Flange set #a								
Sep'18	DQW02+HOM01	HPR, 120C	None	5.1	2.7	9.00E+09	5.00E+09	#E-8	
	20mm NbTi spacer						[5.4]		
	Flange set #a								
May'19	DQW02+HOM01	None	None	4.4	2.1	1.00E+10	5.00E+09	#C-1	-700
	Flange set #a						[5.4]	#F-5	
								#D-7	

# All the US DQW cavity tests with one HOM filter



# Transition to AUP and First HL-LHC Prototypes

- Many more details available for tuners, HOM dampers...
  - Focused on RFD cavity production here
- Lessons learned from LARP cavity production and testing applied to first AUP and HL-LHC prototypes
- AUP developed a lessons learned document for RFD
  - See US-HiLumi-doc-2152
    - Frequency recipe, dimensional adjustments, tolerances, chemistry
- See talk by L. Ristori

# Funding

- LARP
  - Engineering and Design
- DOE SBIR
  - Cavity production, PoP RFD Design
- CERN
  - Welding and processing at JLAB (through LARP)
  - Final DQW testing at JLAB
- AUP
  - All RFD testing and development since AUP start in 2017

# Summary

- The LARP program led the way to:
  - Demonstrate the design of SRF cavities capable of meeting the field and dimensional requirements
  - Including the HOM spectra and impedance requirements
  - Demonstrate the fabrication and assembly procedures
  - Including the chemistry and all cavity processing leading to test results that exceeded the required performance

# Conclusions

- LARP was a key contributor to enable the CC program by demonstrating the feasibility of SRF cavities meeting the constraints of the HL-LHC upgrade
- LARP program gave very important results for HL-LHC and AUP
  - Both cavity designs exceed performance requirements
  - Developed processes that lead to successful results
    - For the DQW good results came from both sides of the ocean -> good sign of the maturity of the design
- The LARP processes and cavities are giving very valuable support to the AUP tasks and to the HL-LHC

# Questions



Science & Technology  
Facilities Council



# RFD Bulk BCP Chemistry at JLAB

Assembly



VHOM-002 After BCP



- Bulk BCP completed for HHOM-002 and VHOM-002









# RFD BCP Setup – CTR-002

Two thickness gauges were used.



# RFD Thickness Measurements Results – CTR-002



**Average removal – 95 micron**



# RFD Frequency Recipes

## CAV-001

Step (Recipe for 20 C, 50 % and 1013.25 mbar)	$\Delta f$ [kHz]	$f_n$ [MHz]
<b>Cavity after trimming and thinning</b>		<b>399.840296</b>
Shift due to bulk BCP (140 microns)	-39.441	
<b>Cavity after bulk BCP</b>		399.800855
Weld shrinkage	115.645	
Weld bead	5.000	
<b>Cavity after final weld</b>		399.921500
Shift due to light BCP (20 microns)	-5.762	
<b>Cavity after light BCP</b>		399.915738
Shift due to mounted couplers	4.906	
<b>Fully assembled cavity with HOM couplers</b>		399.920644
Pressure effect (760 Torr differential)	-60.800	
Dielectric effect air to vacuum	130.341	
<b>Evacuated cavity at 20 C</b>		399.990185
Thermal shrinkage	572.877	
<b>Colled down cavity at 4.2 K</b>		400.563062
Shift due to change in skin depth	28.000	
<b>Cavity frequency adjusted for skin depth</b>		400.591062
Pressure from 760 Torr to 23 Torr in He tank	58.960	
<b>Cooled down cavity at 2.0 K</b>		400.650022
Shift due to tuner activation to its mid range	150.000	
<b>Cavity with tuner activated</b>		400.800022
Lorentz detuning	-10.022	
<b>Operational cavity with RF on</b>		400.790000

Achieved after trimming - 399.845874 MHz



## CAV-002

Step (Recipe for 20 C, 50 % and 1013.25 mbar)	$\Delta f$ [kHz]	$f_n$ [MHz]
<b>Cavity after sub-assembly fabrication</b>		399.843949
Shift due to bulk BCP of End Plates (140 microns)	-26.988	
<b>Cavity after trimming and thinning</b>		<b>399.816961</b>
Shift due to bulk BCP of Center Body (140 microns)	-16.106	
<b>Cavity after bulk BCP</b>		399.800855
Weld shrinkage	115.645	
Weld bead	5.000	
<b>Cavity after final weld</b>		399.921500
Shift due to light BCP (20 microns)	-5.762	
<b>Cavity after light BCP</b>		399.915738
Shift due to mounted couplers	4.906	
<b>Fully assembled cavity with HOM couplers</b>		399.920644
Pressure effect (760 Torr differential)	-60.800	
Dielectric effect air to vacuum	130.341	
<b>Evacuated cavity at 20 C</b>		399.990185
Thermal shrinkage	572.877	
<b>Colled down cavity at 4.2 K</b>		400.563062
Shift due to change in skin depth	28.000	
<b>Cavity frequency adjusted for skin depth</b>		400.591062
Pressure from 760 Torr to 23 Torr in He tank	58.960	
<b>Cooled down cavity at 2.0 K</b>		400.650022
Shift due to tuner activation to its mid range	150.000	
<b>Cavity with tuner activated</b>		400.800022
Lorentz detuning	-10.022	
<b>Operational cavity with RF on</b>		400.790000




Achieved after trimming - 399.809239 MHz

# RFD Frequency Measurement Setup






# RFD Frequency Measurements

- Trim center body to achieve target frequency at pre welding
- $df/dz = -119.85 \text{ kHz/mm}$
- Trimming sensitivity for
  - CAV-001  $\rightarrow df/dz = -129.3 \text{ kHz/mm}$
  - CAV-002  $\rightarrow df/dz = -116.1 \text{ kHz/mm}$




# Final BCP Closed Chemistry Cabinet



Chemical Injection Quill "Snorkel" directs the flow of Acid & Water



End cap mating to Horizontal HOM



# DQW cavities at BNL



Jun 26, 2016

Inspected at BNL  
Visual and  
Dimension Check



All Vectors Summary: Vector Group				
ANALYSIS::MID PART				
Statistic	dX (mm)	dY (mm)	dZ (mm)	Mag (mm)
Min	-0.781	-0.849	-0.674	-0.998
Max	0.754	0.907	0.491	0.557
Average	0.006	0.002	0.001	-0.227
StdDev from Avg	0.216	0.211	0.056	0.207
StdDev from Zero	0.216	0.211	0.056	0.307
RMS	0.216	0.211	0.056	0.307
Tol Range				-0.400 0.400
In Tol				3010 (80.6%)
Out Tol				1930 (19.4%)
Count	9940			

Profile spec  $\leq 0.8$  mm



All Vectors Summary: Vector Group			
ANALYSIS::TOP			
Statistic	dX (mm)	dY (mm)	MagXY (mm)
Min	-0.822	-0.566	-0.822
Max	0.810	0.517	0.325
Average	0.006	-0.002	-0.131
StdDev from Avg	0.218	0.153	0.232
StdDev from Zero	0.218	0.153	0.267
RMS	0.218	0.153	0.267
Tol Range			-0.400 0.400
In Tol			5569 (87.0%)
Out Tol			834 (13.0%)
Count	6403		


Edge deviation 9.293 mm down from the edge

# DQW n 1 Final Trimming at Niowave

15 Sep 2016



Trim tuning at Niowave – frequency check setup







**LARP**

# Evolution of LARP proposals



LARP initial proposal was to contribute all cryomodules, for both the SPS test and the HL-LHC then....

- **Nov 2013**

- LARP and CERN realize this was too ambitious
- New LARP scope → deliver all cold masses only

- **May 2014**

- CC System External Project Review
  - A. Yamamoto (Chair), M. Champion (SNS), A. Facco (INFN), M. Kelly (ANL), C. Pagani (U. Milano), H. Padamsee (Cornell/FNAL)
- Down-selected cavities and established a prioritization criteria for SPS CC production

- LARP is not able to secure funding for M&S and cavity fabrication

- Only option to team up with an ongoing SBIR effort at Niowave

- **No contractual agreement between Niowave and LARP**





**LARP**

# Evolution of LARP proposals (2)



- **Aug. 2014**
  - Niowave starts the extensive manufacturing qualification process requested by CERN
- **Winter of 2014/5**
  - LARP and CERN agree to modify the scope of the collaboration a second time
    - CERN loans magnet wire to LARP freeing up M&S funds
    - LARP engages JLAB to weld all cavity parts, process and test the completed cavities
    - Niowave agrees to provide formed cavity parts for welding at JLAB
- **March 2015**
  - CERN takes on responsibility for tuners and HOM dampers for the SPS
    - LARP held the HOM Design Review - Feb. 2015, JLAB
  - LARP now delivering for the SPS only DQW and RFD cavities with He tanks





# Evolution of LARP proposals (3)



- **May 2015**
  - Niowave informs the collaboration that it will weld cavity subassemblies
  - JLAB is now only welding the final sub-assemblies
- **August 2015**
  - Niowave provides the first welded cavity parts for inspection
- **October 2015**
  - After a ~6 months process, JLAB receives the funding to start the work





# Evolution of LARP proposals (4)



- **Jan 2016**
  - CERN starts its effort to produce DQW cavities for the SPS
  - LARP decides to build bare cavities only, without He tanks
    - CERN and LARP agree the DQW cavities produced at CERN are the lead candidate for integration in the SPS test.
  
- **Mar 2016**
  - In light of schedule constraints for the SPS test, CERN decides to test the DQW first, before LS2
  - The RFD prototypes for the HL-LHC will be tested after LS2
  
- **May 2016**
  - LARP-AUP and CERN agree on the US contribution to the HL-LHC: limited to all RFD dressed cavities only.



# The Team – Principal Contributors

- LARP
  - BNL – Q.Wu, S. Verdu-Andres, B. Xiao, J. Skaritka, Ilan Ben-Zvi
  - FNAL – C. Ginsburg, T. Nicol, T. Peterson, L. Ristori
  - JLAB – A. McEwen, E. Daly, H. Park (also ODU)
  - LBNL – J. Qiang
  - ODU – J. Delayen, S. De Silva, H. Park
  - SLAC – Z. Li, A. Ratti (formerly LBNL)
- World Wide Collaboration
  - CERN – R. Calaga, O. Capatina, M. Garlasche', C. Zanoni
  - STFC – G. Burt, N. Templeton, T. Jones
- Many others are actively involved, in particular in the work centers of CERN and JLAB
  - and many contributed in the past

# LARP Team Organization

- Cavity EM Design - **BNL, ODU/SLAC**
  - RF measurements, Frequency Analysis (w. Proc.), HOM studies
- Cavity processing and testing – **Jefferson Lab**
  - Parts inspection and acceptance
  - Welding (w. procedures)
  - Chemistry (w. procedures)
  - Vertical Testing (w. procedures)
- Project Coordination – **SLAC**
- Project Engineering – **FNAL**
  - Development of Pre-Series cavities
  - Planning for AUP

Working as a team, everyone encouraged to contribute  
CERN actively involved