
MBRDS1 Mechanical Measurements

Andrea Bersani



Summary of Strain Gauges



Pre-collaring

- Involved SGs are the "P" ones
- No measurement has been performed during operation
- → SGs were zeroed before
- "Small" pressure was applied to insert temporary keys
- Some initial stress is foreseen on the poles



Poles Strain


μm/m	PUL1T	PUL1Z	PUL1C	PUL2T	PUL2Z	PUL2C	PUL3T	PUL3Z	PUL3C	PDLT	PDLZ	PDLC	PURT	PURZ	PURC	PDRT	PDRZ	PDRC
t = 0	21	19	17	-28	76	19	-35	46	18	125	0	17	58	-52	25	16	-5	25
final	-120	126	28	-198	251	22	21	200	23	95	251	27	52	77	21	75	179	16

μm/m	average T	average Z	average C
t = 0	26	14	11
final	-1.3	181	23
exp	-500	150	0

Collaring: Aperture 2


- → 1 press is in touch
- → 2 100 bar (stop for electrical tests)
- → 3 200 bar
- → 4 250 bar
- → 5 350 bar (stop for electrical tests)
- 6 400 bar
- 7 500 bar (first keys insertion, stop for electrical tests)
- → 8 550 bar (calculated collaring pressure)
- → 9 600 bar (insertion of most of the keys)
- → 10 press release 100 bar steps

Collaring: Aperture 2



Yoking

- Involved SGs are the "R" ones
- We had MANY problems with the readout
- Thanks to redundancy we had some readout during yoking




μm/m	average T	average Z	average C
t = 0	0	0	0
final	-138	68	1.3
ехр	-130	40	O



Yoking Operations

- > start: 11:10
- up @step 50bar to 150bar
- 11:13 down to 50bar
- 11:14 up to 150bar
- 11:15 up to 200bar
- 11:18 up to 225bar
- 11:19 up to 250bar
- 11:20 up to 275bar
- 11:25 down
- 11:30: free, operation ended






Longitudinal Pre-Stress


- Involved SGs are the "B" and "T" ones
- Measurements have been performed at CERN with Sohrab
- 13 out of 16 "B"s were readable
- 5 out of 6 "T"s were readable
- Goal on the "B"s was 8kN on each bullet

Longitudinal pre-Loading





Final "B"s Readings



Summary

- "P"s readings are controversial
- "R"s readings are good, but many channels are missing
- "B"s readings are good, but EXTREMELY sensitive
- Overall, the information is partial and not always clear, but I see no show-stoppers
- The interaction between ASG, INFN and CERN for the SGs installation and monitoring was cumbersome and ineffective