

DE LA RECHERCHE À L'INDUSTRIE

cea

# Cryogenics for high magnetic field whole body MRI :

## ISEULT 11.7 T at NEUROSPIN



Double Chooz



ALICE



Edelweiss



HESS



Herschel



CMS

*Déchiffrer les rayons de l'Univers*



Philippe BREDY

30<sup>th</sup> of september 2019


Initial parameters of the Sc magnet

Main cryogenics choices

Detailed design and  
cooling down

Associated cryoplant


Cool-down and first  
measurements with field



## *Magnetic Parameters*


Maximum Nominal Frequency	499,8	MHz
Internal diameter for whole body	900	mm
Maximum User Field (for maximum frequency)	11,739	T
Homogeneity on the 22 cm diameter sphere (Peak-to-Peak)	< 0.5	ppm
Homogeneity on the 22 cm diameter sphere (RMS)	< 0.05	ppm
Long term drift	0,05	ppm/h
Short term drift (time tbd)	0,4	ppb
5 Gauss line position (radially)	< 13.5	m
5 Gauss line position (axially)	< 10.5	m

## Design of the Sc coils to be cooled (with a fixed current density on NbTi conductor\*)



\* : *Nb<sub>3</sub>Sn* excluded (lack of internal knowledge and high level technological risk)


**Design of the Sc coils to be cooled into a common bath  
inside 3 tanks communicating together**



*7000 litres to be filled !*

## *Superconducting parameters and $T^\circ$ of bath*

- High magnetic field ( 11.7 T)
  - Use of **NbTi** , very close to its Sc limits
- ⇒ Operating  $T^\circ$  below 4.2 K (4.2 K = He I at 1 atm)




## *Sc coil operation*

- ❑ With a “customized” industrial Cu/NbTi conductor, for the required **current density**

⇒ nominal current at 1483 A

⇒  $T_{\text{current sharing}} = \mathbf{2.8\ K}$  (need to operate below this temperature)



- ❑ Required magnetic field **time stability**

⇒ permanent connection with external electrical power supply for continuous correction of current (significant difference compared to classical MRI)

⇒ Installation of a pair of 1500 A current leads, cooled between **4 K and 300 K** and electrically supplied permanently.



## Superconductor operation

- ❑ Arbitrary **temperature margin of 1 K** for Sc conductor (usual margin...)



$$T_{op} = T_{cs} - \text{margin} = 2.8 - 1 = \mathbf{1.8 \text{ K}}$$
 as nominal operating temperature

- ❑ **Cryostability criteria**

(*H* : one complete turn of the winding transited without reaching critical flux)

⇒ Need internal channels inside the winding to perfectly wet the Sc conductors




⇒ Double pancake technology with radial channels and direct contact between fluid and Sc conductor






## Cooling architecture

- ❑ Based on previous successful experiments on TORE SUPRA, LCMI and LHC
- ❑ Choice of a **static pressurized superfluid helium bath at 1.8 K and ~ 1.2 bars (pressurized He II)**
  - To avoid sub-atmospheric conditions on a large cryostat (risk of air inlet on cryogenic device)
  - To improve electrical insulation (higher voltage breakdown of He II at 1 atm ● compared to He II saturated at 1.8 K/16 mbars ●)
  - To gain in thermal performances
    - Very high thermal conductivity of He II
      - ✓ Isothermal bath all around the winding
      - ✓ Remote the cold source outside the cryostat
    - Enthalpy margin before He I transition




## General principle of a pressurized superfluid helium bath

### Double bath or "Bain Claudet"



## ***Applying the pressurized superfluid helium bath for Iseult magnet***

- No enough space inside the cryostat and above the cryostat in the magnet room
- + Choice for no active cryogenic element directly on the magnet cryostat




*=> Installation of a remote cryogenic satellite able to produce the double bath and contain all the interfaces between Sc coil and utilities*

**Cryogenic satellite**


## Applying the pressurized superfluid helium bath for Iseult magnet

Remote the cold source and consider the He tank around the coils as « *cul de sac* » :

⇒ Cryogenic satellite and He II pipe as thermal link (caloduc)




## *Applying the pressurized superfluid helium bath on Iseult* Final configuration in the magnet room





## SEHT test facility :

*Preliminary test to validate the operation of a similar Sc double pancake winding with a superfluid pressurized helium bath (including quench behaviour)*




Overview of SEHT facility



Sc coil (ex LCMI 8 T NbTi coil in vertical axis)



Magnet cryostat



Cryogenic satellite

## SEHT test facility : Cooling down process


Different steps in the SEHT cooling down (through its temperatures)






## SEHT test facility :


Quench (triggered) and thermohydraulic studies (He overpressure)




## Internal tanks of satellite




7400 l to be filled  
110 tons to cool down from 300 K to 1.8 K




## Rinsing and purging with pure He



## Cooling of the unique thermal shield down to 80 K (LN2 flow)




## Cooling of the He tanks and coils from 300 K down to 5K (cold GHe flow from He liquefier)






## He tanks and coils near 5 K and thermal shield cooled by « 50 K » GHe flow from He liquefier







## Filling of satellite with LHe produced by He liquefier (thermal shield still cooled by « 50 K » GHe)




*R : As a dead-end, the coil tanks and their static heat losses can't be biffled with Hel*



**Starting up of the cold source below 4 K by pumping unit (tank filling by condensation of GHe down to He II at  $T_\lambda = 2.17$  K)**




*R : With our slow cooling down, the small hydraulic leaks on the Lambda plate are sufficient to maintain 1.2 bars during condensation phase (without extra heat leaks...)*



**Coil tank entirely filled with subcooled superfluid He (He II at 1.8 K and 1.2 bar)**


R : 7400 l at 1.8 K = huge thermal inertia in case of He pumping unit stop (or in case of transient heat load)


Ex :  $\sim 6$  hours for reaching 1.9 K from 1.8 K in case of He pumping unit stop...



## Pressure levels in ISEULT system

Publi 23/08/2016





And all the other equipment needed for reaching the CRYO OK...

110 tons of cold mass to be cooled down from 300 to 1.8 K

2.4 tons of thermal shield to be cooled from 300 to 50 K

7400 liters of He II to be filled and to maintain at 1.8 K (*1.95 K max with current*)

Estimated heat loads :

He liquefier  
requirements

➤ **20 W at 1.8 K** (magnet + satellite) (tech : 1 W à 1.8 K  $\Leftrightarrow$  2.4 l/h)

➤ **9 l/h** LHe for current leads cooling

**70 l/h**

➤ **600 W at 50 K** (magnet + satellite)

**900 W at 50 K**

➤ **27 W at 4.4 K** (transfer lines and satellite)


**40 W at 4.4 K**

- Magnet continuous operation : 24 h/day and 365 days/year
- Absorb losses induced by:
  - the pulsed gradient coils
  - slow discharge
  - fast discharge
- Secure the equipment in case of quench or vacuum failure
- Withstand any utility failure (electrical, water, compressed air)
- In case of a big cryoplant failure, maintain the magnet at 80 K maximum (LN2)
- Allow the maintenance actions without magnet desenergising
- Minimize manual actions on the process

**Redundancy !**



# THE CRYOPLANT FOR THE MAGNET OPERATION






Cryo-plant underground view



Control room



PLC



Power supply



He recovery



He gas buffers  
and LN2 tank



Cryogenic  
stillite



## « HELIAL » Cold box

Measured capacities:

120 l/h

or

200 W @ 4.4 K

or

**40 W + 81 l/h (nominal mode)**

Thermal shield circuit I/O

**900 W @ 50/55 K**

Cool down circuit 300-5 K





**He compressor unit**

**2 compressor + 2 ORS for  
redundancy**

**2 x 132 kW**

**40 g/s at 14.5 abars each**

**Air cooling  
(2 x 25000 m<sup>3</sup>/h)**



**LHe dewar**

**5000 liters**

**0.35% static losses**

**Atmospheric heat exchangers**

for by-passing cold box during 300  
K-100 K cooling down

*R: view before installation of the Cold Box*



Mass flow vs suction pressure for various roots speed


## He compressor unit (Oerlikon)

Roots (2000 m<sup>3</sup>/h with VFD 20-100 Hz) + vane pumps (750 m<sup>3</sup>/h)

2 Units for redundancy

1 g/s at 13 mbars each (50 Hz)

Air + water cooling







**Vacuum insulated electrical heaters  
installed on low pressure circuit between  
satellite and He pumping units  
(Cryodiffusion)**

**4-300 K / 8 kW**


**Low pressure drop (< 1 mbars @ 1 g/s))**

**2 heaters in parallel for redundancy**



## *Magnet room*

Satellite connection  
(vacuum barrier on satellite)



LN2 thermally shielded for safety

LHe dewar

He pumping unit line

LN2

*Cryogenic room*

Cold Box:

- Cool down circuit outlet
- Thermal shield I/O (50/55 K)
- GHe return from 4.4 K tank of satellite



During tests at workshop




(Cryodiffusion)

Interface for :

- Fluids
  - Hel
  - Hel saturated
  - Hel pressurized
  - LN2 and GHe
- Instrumentation
  - Magnet
  - Cryo
  - Safety
- Safety
- Electrical
  - 1500 A
  - Cryoshim
  - EIS
- Vacuum





He II pipe  
He and LN2 circuits  
(shields, cool down)  
1500 A busbars  
Cryoshim circuits  
EIS heaters







# FIRST step of cooling down : 300-120 K






- 110 tons to be cooled from 300 K to 120K
- 210 000 liters of LN2
- 7 weeks

# SECOND STEP OF COOLING DOWN : 120 – 4.2 K




- 110 tons to be cooled 120 K – 4.2K
- 50000 liters of LN2
- 5 weeks



- Filling the magnet with 7400 liters of He II
- Cooling down from 4,2K to 2.17 K then from 2.17 K to 1.8 K
- Complete the 5000 liters LHe Dewar
- Vaporiser 13 bidons de 1000 litres d'hélium dans le cycle
- 25000 liters of LN2
- 4 weeks






A little bit long 😞 but unique 😊 and with no He leak or unexpected heat loads : 😊


## Measured heat losses:

- 12 W @ 1.8 K without current
- **14 W @ 1.8 K** with 1483 A (20 W estimated)
- > 16 W @ 4.4 K (tbc)
- **8.1 l/h** for currents leads (8 l/h estimated)
- **572 W** with 38 K on magnet ThS and 41 K on satellite ThS (570 W estimated...)

## 9.5 T THEN 11.72 T WITH SLOW DISCHARGE




## 7 T THEN 10.5 T WITH FAST DISCHARGE



**Fast discharge** (normal contraction of the HeII bath under a significant heat deposit (eddy currents) !)

- To continue to consolidate the control-command software by testing and analysing the maximum of fault scenarios modes (several « instructive » failures since one year of continuous mode...)
- To analyse the thermal effect (extra transient heat losses) of the pulsed gradient coils (not yet installed inside the magnet hole)
- To implement all the maintenance procedures, equipment and contracts with manuals for operators

# Thank you for your attention



And great acknowledgements to all the collaborators involved in this work...



Commissariat à l'énergie atomique et aux énergies alternatives  
Centre de Saclay | 91191 Gif-sur-Yvette Cedex

Etablissement public à caractère industriel et commercial | R.C.S Paris B 775 685 019

Direction de la Recherche Fondamentale  
Institut de recherche  
sur les lois fondamentales de l'Univers  
DACM