




The LIEBE high-power target: Offline commissioning results

Ferran Boix Pamies




ENGINEERING
DEPARTMENT

Isolde hall layout




ISOLDE



Introduction/Context

- High power target for exotic species




Long tradition of operation of molten targets at ISOLDE

$$i = \Phi \cdot \sigma \cdot N \cdot \epsilon_{target} \cdot \epsilon_{source} \cdot \epsilon_{sep} \cdot \epsilon_{transport}$$

Protons/pulse	Current (μA)	Energy (GeV)	Cycle length (s)	Average power (kW)
3.3×10^{13}	2.2	1.4	1.2	3.1
1×10^{14}	6.7	1.4	1.2	9.3
1×10^{14}	6.7	2.0	1.2	13.4

Possible update parameters of the proton beam sent to ISOLDE, R. Catherall et al 2017.

→ Lanthanum eutectic + SnCl molecular beam:
Towards 100Sn beams at HIE-ISOLDE
T. Stora et al., EMIS 2018








Concept scheme, E. Noah et al, EURISOL-DS



Introduction/Context Concept

• LIEBE: Liquid Eutectic lead Bismuth for Eurisol

- Target material: LBE
- Operational temperature: [200-600]°C
- Targeted isotope: ^{177}Hg (130ms half-life)
- LBE Velocity preferred: **2 m/s** → **Q=0.13 l/s**
- **Ø0.4 mm** droplets → factor **5** more release



Images from Melanie Delonca CERN Ph.D thesis


LIEBE prototype design & completed assembly

Concept


Prototype

- The target:

- Compatible



Transfer line




Chimney

LIEBE prototype design & finished assembly

- The EM pump:

University of Latvia
Institute of Physics



Coupling rails

Alignment table

Dedicated trolley

Offline commissioning: Flow assessment

Concept


Prototype

Offline commissioning

• Test objectives:


- Operate in the absence of cavitation
- Reach the desired flow for release optimization (0,13L/s)

Increased diameter: $\varnothing 10\text{mm}$ \rightarrow $\varnothing 16\text{mm}$



Screenshot of the tests setup

Flow assessment in previous tests at IPUL



- 1- EM pump
- 2- Level sensors
- 3- Manometers
- 4- Venturi tube
- 5- Mechanical valve
- 6- Channel connected to EM pump
- 7- LBE tank

Offline commissioning: Flow assessment


Concept

Prototype

Offline commissioning



- Results:

- Drift observed between measurements due to clogging of the sensors
- LBE oxide formation in contact with air



Offline commissioning: Alignment/vibration tests

- **Vibration tests:** Concept → Prototype → Offline commissioning
 - Check vibration transmission
 - Evaluate the level of vibration for each rotational frequency







Empirically measured maximum distances
in case of perfect alignment

Test setup after alignment

Offline commissioning: Alignment/vibration tests

• Results:

- Sudden vibration increase due to natural resonant frequencies



Rotor Fr= 20Hz

Rotor Fr= 40Hz

	PUMP			LIEBE_SIDE (Uncoupled)			LIEBE_SIDE (Coupled)		
	+X	+Y	+Z	+X	+Y	+Z	+X	+Y	+Z
Baseline	0.20	0.19	0.19	0.06	0.05	0.04	0.05	0.05	0.04
10Hz	0.83	0.54	0.47	0.05	0.05	0.04	0.52	0.17	0.22
20Hz	0.54	0.39	0.64	0.06	0.05	0.04	0.24	0.85	1.27
30Hz	0.88	0.79	1.13	0.06	0.05	0.04	0.45	0.39	0.19
40Hz	1.44	0.92	1.19	0.07	0.05	0.04	0.48	0.22	0.25
50Hz	4.28	1.76	1.41	0.05	0.05	0.05	0.73	0.27	0.25

- Good/satisfactory levels for operational frequencies of LIEBE
- Addition of an accelerometer to monitor the vibration throughout operation with LBE

Offline commissioning: Leak issue





Concept

Prototype

Offline commissioning

Leak emergence:


- Appropriate vacuum level with cold target
- Leak appearing when heating up the ion source to 1700 °C



Offline commissioning: Remaining tests

- Full operation of the loop with molten LBE in an offline mass separator:

- Thermal control
- Safety measures:
 - Pressure sensor
 - Accelerometer
- Mass scans



Operational review



Conclusions

- Prototype and offline commissioning:
 - Flow developed by the EM pump : within specification
 - Vibration : within specification
 - Target handling & optimization : within specification
- New base design for leak-tight confinement vessel
- Remaining full operational tests in an offline separator
- Online tests foreseen for the last run at ISOLDE

Acknowledgements

EN-STI-RBS : Bernard Crepieux, Andres Vieitez, Melanie Delonca, Thierry Stora, TISD group, Ana Paula Bernardes, Ermanno Barbero, Beatriz Conde Fernandez

EN-STI-TCD : Edouard Grenier-Boley

EN-MME : Laurent Prever-Loiri, Lukasz Jerzy, Vincent Barozier

EN-SMM : Thierry Feniet, Antje Behrens, Alexandre Beynel

EN-HE : Jean Louis Grenard

BE-OP : Pascal Fernier

SINP, IPUL, SCK.CEN : Susanta Lahiri, Kalvis Kravalis, Donald Hougbo,



ENGINEERING
DEPARTMENT



Thank you for your attention



ENGINEERING
DEPARTMENT

Backup slides

The main loop part




- Filling tank
- Heat Exchanger (HEX)
- Irradiation & diffusion chamber
- Hypertaks/feedthroughs




- Water connectors
- Electrovalves
- Bellows
- Extraction line and ion source -> standard VADIS ion source

LIEBE: Heat Exchanger

- 5 LBE temperatures (200-600degC)
- CFX Calculations of the heat exchanged for every channel





3D printed steel Heat Exchanger



Offline commissioning: Leak issue


- Attempts to solve it:
 - Increasing sealing pressure
 - Shielding the ion source
 - Only able to operate the source up to 1900 °C




Offline commissioning: Alignment/vibration tests

- Alignment tests:

- Cylinder axis and pump axis are on the same line within 0.1mm



Measurement of the EM pump axis





Best fit distances between EM pump and target

Offline commissioning: Alignment/vibration tests


VIBRATION SEVERITY PER ISO 10816					
Machine		Class I small machines	Class II medium machines	Class III large rigid foundation	Class IV large soft foundation
in/s	mm/s				
Vibration Velocity Vrms	0.01	0.28			
	0.02	0.45			
	0.03	0.71		good	
	0.04	1.12			
	0.07	1.80			
	0.11	2.80		satisfactory	
	0.18	4.50			
	0.28	7.10		unsatisfactory	
	0.44	11.2			
	0.70	18.0			
	0.71	28.0		unacceptable	
	1.10	45.0			

Offline commissioning: Flow assessment




Offline commissioning: Alignment/vibration tests

- Results:




Displacement Power Spectral Density comparison, Rotor Fr=30Hz, EM Wheel Fr= 4,11Hz direction +Y

Offline commissioning: Alignment/vibration tests




Displacement Power Spectral Density comparison, Rotor Fr=20Hz, EM Wheel Fr= 2,75Hz direction +Z

Offline commissioning: Alignment/vibration tests



Displacement Power Spectral Density comparison, Rotor $F_r=30\text{Hz}$, EM Wheel $F_r=4,11\text{Hz}$ direction +Z

Offline commissioning: Alignment/vibration tests



Displacement Power Spectral Density comparison, Rotor Fr=40Hz, EM Wheel Fr= 5,48Hz direction +Z