



Status of Beam Instrumentation (WP13)

Manfred Wendt (CERN BE-BI-BP)
for the HL-LHC Beam Instrumentation Team



9th HL-LHC Collaboration Meeting, Fermilab, Batavia, USA
14-16 October 2019

Scope of WP13

- ***New and Upgrades of Beam Instrumentation for the HL-LHC***
- Long-Range Beam-Beam Compensation
 - *Studies leading to proof of concept*
 - *Design study for possible final implementation*
- Electron Beam Test Stand (in frame of the hollow electron beam)
 - *Construction and operation of a test stand at CERN*
 - *Coordination of e-beam simulations*



Thursday
WP2/WP13
Satellite meeting

Tue, 16:00
One West
S. Sadovich


Task	Description
13.1	Radiation Hard BLM Electronics
13.2	Gas Curtain Monitor
13.3	New BPMs Q1 to Q5 with dedicated acquisition electronics
13.4	Luminosity Monitors
13.5	Electro-optical BPM
13.6	Upgrade of the Synchrotron Light Monitor
13.7	Beam Gas Vertex Detector
13.8	Long Range Beam-Beam Compensator Studies
13.9	Electron Beam Test Stand

Beam Loss Monitoring

- Need for cryogenic BLMs removed
- Radiation Hard ASIC development
 - Minimize length of cables \Rightarrow improve S/N
 - Requires rad-tolerant electronics in the tunnel
 - Collaboration with EP-ESE-ME
 - Two fully functional custom chips being developed to evaluate performance of two different architectures:
 - Current to Frequency Converter
 - Better for large currents & quickly varying signals
 - Delta-Sigma ADC
 - High accuracy due to oversampling & filtering
 - Milestones:
 - Test of a prototype by end of 2019
 - Design to be completed by 2020
 - Series production start in 2021



BPMs for the Interaction Regions (P1 & P5)



- A total of 32 “cold” BPM pickups
 - Requiring new, dedicated acquisition electronics



“Cold” Directional-Coupler BPMs

Technology

- High directivity required to disentangle B1/B2 signals
- Tungsten shielding: lower TID on Q2B magnet by ~15 %
- Amorphous carbon coating: Electron cloud effects decreased by 40x
- Active cooling with liquid He: To evacuate up to 6 W of head load



Status / Milestones

- BPM prototype production launched
- Started procurement of tungsten absorbers (with WP12) and cryogenic RF feedthroughs
 - Qualification of RF feedthroughs mid 2020
- In-kind contribution of BPM body manufacturing
 - Collaboration agreement with Russia finalized
- Coaxial SiO₂ RF cables
 - Market survey and procurement start for mid 2020
 - In combination with cables required for the collimator BPMs



“Button” BPMs embedded in collimators


- Buttons embedded in collimator jaws to speed up set up since 2013
- Uses high-precision DOROS BPM acquisition system
- Collimator jaw position now interlocked on BPM readings
- Challenging integration and component procurement: coaxial SiO₂ RF cables
- All HL-LHC collimators will be equipped with BPMs



Crab-Cavity diagnostics – EM Head-Tail monitor

SPS Head-Tail monitor

- Wideband BPM measuring intra-bunch beam position
- 180° RF hybrid + high-speed oscilloscope
- Used primarily for instability diagnostics
- SPS HT monitor used in 2018 for crab cavity diagnostics
- Requires $\pm 90^\circ$ phase advance and large beta functions
- For HL-LHC: insufficient resolution and bandwidth



Crab-Cavity diagnostics – Electro-optic BPM




Technology

- Birefringent crystals encoding the electric field of the beam onto a laser light (polarisation rotation)
- Ultrafast crystals used by telecoms, components commercially available

Status / Milestones

- Fully in-vacuum prototype installed in the SPS in 2016, modified 2017-2018
- First electro-optic measurements of a proton bunch
- Design on-going for an HL-LHC out-of-vacuum electro-optic BPM
- Functional prototype in 2021





Beam halo monitoring – coronagraph



Principle of operation

- Beam halo monitoring crucial for adequately adapting the HL-LHC machine protection systems
- Coronagraphs used to view the Sun's corona
- Real image is created by an objective lens
- A mask blocks the bright core
- To deal with light diffracted from the limited entrance aperture, a field lens together with a well-dimensioned stop are used
- Final performance defined by contrast




LHC coronagraph



Status / Milestones

- 1st prototype (v1) based on KEK photon factory optics installed together with other synchrotron light diagnostics
 - *First successful beam halo observation in 2016 using undulator-produced SR*
 - *Demonstrated contrast $\sim 10^{-4}$*
- 2nd, improved prototype (v2) to be installed by end of LS2 on one beam for testing in Run 3
 - *Higher magnification to achieve the 10^{-5} contrast design goal*
- The final HL version (LS3) will be on a dedicated synchrotron dipole radiation optical line




Beam Gas Curtain monitor - BGC



Technology

- Use case:
Hollow Electron Lens (HEL)
 - *Beam halo collimation*
 - *Proton and hollow electron beam must be concentric*
- 2D image of both beams on supersonic gas “screen”
- Beam Induced Fluorescence: minimally invasive and unaffected by a strong solenoid field
- Compatible with both, low and high energy beams
- Gases under study: N_2 , Ne, Ar



BGC prototype




Status / Milestones

- Prototype BGC built at Cockcroft Institute (UK)
- Three different gases tested with a 5 keV electron beam at 0.65 mA
- Fluorescence observed with all gases
- HL-LHC H **H. Zhang, Gas jet diagnostics for the hollow e-lens**
- current ~ 5 A – much higher photos flux
- Challenges: Low X-section with p at high energies
- Extensive simulation and engineering work put into gas curtain generation
- Installation foreseen in LS2

see also the presentation today afternoon, 14:00:


H. Zhang, Gas jet diagnostics for the hollow e-lens



Beam Gas Vertex monitor - BGV

Technology

- Beam-gas interaction vertex reconstruction under study as a non-invasive beam profile measurement
- Demonstrator installed in 2014 using neon at $5 \cdot 10^{-8}$ mbar and scintillating fibres from LHCb
- Demonstrated beam size measurements throughout the energy ramp
 - Demonstrated the required precision in a reasonable integration time (2% within 20s)
 - Still, need to demonstrate the absolute accuracy and profile measurement through vertexing.




HL-LHC BGV design



Status / Milestones

- BGV is a candidate instrument for HL-LHC beam size measurements
- Final design proposal by the end of 2020
- Performance target:
 - 5% resolution with a single bunch
 - 2% absolute accuracy with the whole beam
 - < 1 minute integration time
- Various improvements under study:
 - Addition of a third detector plane
 - Other detector technologies (silicon, gaseous)
 - Using a gas jet instead of large gas volume to reduce longitudinal acceptance region
- Optimal location to be identified: symmetric optical functions, large beam size, small aperture




LHC Beam Size Measurement Review, 1-2 Oct. 2019

- **HL-LHC requirements**
 - Beam size, beam profile (1D, 2D), non-Gaussian beams, beam halo
- **Run 2 experience and possible upgrades**
 - Wire-scanners, synchrotron light (BSRT), BGV demonstrator, quadrupolar BPMs, ionization profile monitor (BGI), gas jet diagnostics (BGC)
- **Main outcome**
 - Wire-scanners for calibration purposes continue to be essential
 - Identified BGV (current HL baseline) and BGI as most promising candidates to fulfill all HL-LHC beam profile measurement requirements
 - *BGI based on Timepix/Medipix technology demonstrated in the CERN-PS, but requires redesign and a new, compact 0.6T dipole magnet*

Luminosity monitoring - BRANQ

Technology


- Independent monitoring of the LHC luminosity
 - Not related to Atlas/CMS data
- LHC: ionisation chambers measuring the shower created by forward neutral debris
- HL-LHC: fused silica rods producing Cherenkov radiation under study
- Prototype installed and tested in the LHC
- Some rod darkening observed within the first 10 fb^{-1}
 - Only at lower wavelength $< 400 \text{ nm}$
 - stable beyond initial irradiation



Luminosity monitoring under varying X-ing angle

Challenges / Status

- Beams collided at an angle
- Different crossing planes for ATLAS and CMS experiments
- Luminosity monitor installed in the same orientation for both crossing planes
- In the horizontal X-ing case (IP1) not all rods irradiated with the same power
- Sensitivity to the crossing angle $\sim 10\%$ for a $15 \mu\text{rad}$ change



Progress of other WP13 Tasks

- **Upgrade of synchrotron light diagnostics**
 - D4 exit in LSS4 identified as source for new light extraction line
 - *Design of extraction tank & optics started*
- **Beam position system electronics**
 - New requirements for the HL-LHC final focus BPMs in IR1 & 5
 - *Will be used to prototype a full LHC BPM system renovation post LS3*
 - *Funded by R2E, CONS and HL-LHC*
- **Long Range Beam-Beam compensation**
 - Workshop following this meeting
 - 4 wire-in-jaw collimators successfully demonstrated compensation in Run 2
 - HL funding study for final technical design as part of WP13 for possible future option
- **Electron beam test stand**
 - To test components for a hollow electron lens
 - Installation ongoing
 - Accompanied by e-beam simulations (collaboration with BINP)

Summary

- LHC constructed with comprehensive suite of beam diagnostic devices
 - These play an important role in its safe & reliable operation
- HL-LHC will push the performance of LHC even further
 - Requires a deep understanding of beam related phenomena
 - Can only be delivered through its beam instrumentation
- Significant progress made on all tasks thanks to our many collaborators
 - Aachen University (Germany)
 - ARIES (EU)
 - BINP (Russia)
 - CERN EP Department
 - The Cockcroft Institute (UK)
 - EPFL (Switzerland)
 - FNAL (US)
 - GSI (Germany)
 - KEK (Japan)
 - LHCb (CERN)
 - Royal Holloway University of London (UK)
 - Wroclaw University (Poland)
 - University of Liverpool (UK)

Thank you!



大学共同利用機関法人
高エネルギー加速器研究機構



Wroclaw University
of Science and Technology

