


RFD Canada – Status and Transport Aspects

Bob Laxdal

TRIUMF Hi-Lumi Technical Lead

2019-04-08



June 25, 2018

“Great science knows no borders.” Minister Kirsty Duncan

Canadian Minister of Science and Sport Kirsty Duncan announces 10M\$ support for TRIUMF to build 5 Hi Lumi LHC RFD Crab Cavity Cryomodules

Working with the Canadian research community and industry, TRIUMF will lead the production of the cryomodules with a \$2 million in-kind contribution for a total project value of \$12 million.

Hi-Lumi FNAL Oct. 2019 - Laxdal



CERN-TRIUMF MOU – Addendum No. 3

An agreement has been drafted – soon to be signed.

TRIUMF representatives on the Steering Committee

Jon Bagger – Director

Oliver Kester – Project Leader

TRIUMF's Technical Coordinator

Robert Laxdal – SRF Department Head

CERN representatives on the Steering Committee

Frédéric Bordry – Director for Accelerators and Technology

Lucio Rossi – HL-LHC Project Leader

CERN's Technical Coordinators and Safety Correspondents

Rama Calaga – HL-LHC Work Package 4 Leader

Ofelia Capatina – HL-LHC Work Package 4 Deputy Leader

P095/A1

Addendum No. 3

to

THE 2009 PROTOCOL P095

to

THE 1996 CO-OPERATION AGREEMENT

between

**THE EUROPEAN ORGANIZATION FOR NUCLEAR
RESEARCH (CERN)**

and


TRIUMF (CANADA)

Concerning

**Collaboration on the High-Luminosity LHC
for the construction of the RFD Crab Cavities cryomodules**

RFD Cryomodule Project

- TRIUMF to work with CERN and UK colleagues to develop RFD cryomodule design, assembly tooling and fixtures, assembly procedures
- TRIUMF to receive dressed RFD resonators produced and qualified in AUP, to install the fundamental power coupler and to assemble each pair of RFDs into five hermetic strings
- TRIUMF to assemble hermetic strings into five cryomodules
- TRIUMF to qualify the cryomodules through testing at TRIUMF before packaging and shipping to CERN
- TRIUMF to work with CERN and UK to establish a suitable shipping method to retain the high performance of the module



The TRIUMF Team

Technical coordinator – [Bob Laxdal](#)

Deputy Coordinator – [Zhongyuan Yao](#)

Engineer – [Matt Brownell](#)

Designer – [Ben Matheson](#)


String assembly – [Bhalwinder Waraich](#),
[Ruminder Sekhon](#)

Cryomodule assembly – [Devon Lang](#),
[James Keir](#), Student

Cabling – [Sean Wang](#)

Technical support – alignment,
cryogenics, HLRF, machine shop


Administrative: [Procurement](#), [Finance](#)



CERN/TRIUMF – Hi Lumi technical meeting

June 26-28, 2019 Bob Laxdal (TRIUMF HiLumi Technical Coordinator), Ben Matheson (Designer) and Mat Brownell (Engineer) met with CERN technical personnel to discuss HiLumi cryomodule project


- Discussed deliverables and scope, CERN protocols, gained access to CERN drawing vault and EDMS (document server)
- Toured Crab cryo-module installation in SPS tunnel and SM18 CM assembly area



TRIUMF Review process – next steps

TRIUMF employs a project review protocol similar to the DOE Critical Decision process with four Gates:


- The project has passed Gate 0 Aug. 2018
- Gate 1 inputs
 - Design Notes covering Conceptual Design
 - Initial Project Plan containing: Level 1 WBS, Initial Budget and Resource Estimates.
 - Initial Hazard analysis and Risk Registry
- Gate 2 inputs
 - Project Plan containing full WBS and budget
 - Resource Loaded Schedule and detailed budget to WBS Level 3
 - Initial Technical Design documentation
- Gate 3 – readiness review for construction
 - Final design documents and specifications released



Project milestones - proposal

We want to link TRIUMF gate schedule with CERN technical milestones. In principle we would like to get to Gate 3 before standard procurements. The prototype TCM0 could be considered in a Gate 3A.

Project Milestone	Proposed date	Hi-Lumi input
Gate 1	Dec. 1, 2019	Conceptual design review, preliminary scope def'n
Gate 2	Feb. 1, 2020	Final scope def'n, detailed budget
Gate 3A TCM0	May 1, 2020 ?	TCM0 design review, released drawings and specifications
Gate 3B TCM1-4	July 1, 2021 ?	Final design review, released drawings and specifications



Gate 1 Project definition

- Define a collaboration agreement
- Draft scope of the Canadian contribution to HL-LHC-WP4 including fabrication, assembly and testing
- Project plan released – level 1 WBS, initial budget and resource estimates
- Conceptual design released
- Initial hazard analysis and risk registry

Gate 2 Project planning

- Define scope of the Canadian contribution to HL-LHC-WP4 including fabrication, assembly and testing
- Include RFD cryomodules and integration into WP4 master planning
- Define main interfaces and responsibility sharing between Canada and CERN
- Define acceptance criteria and compliance with engineering specifications.

Gate 3A Prototype design

- Prototype cryomodule technical design review complete, released drawings and specifications
- Gate 3A asks whether the project is ready for procurement
- Will define the launch of the TCM0 procurements

What is TCM0?



TCM0 is an early prototype of the RFD cryomodule to be built at TRIUMF

TCM0 would engage TRIUMF earlier and significantly reduce schedule risk once series cavities arrive

TCM0 would allow early preparation and qualification of tooling , processes, testing well before series production

Would require 2 (or even 1) dressed RFD cavities from AUP at the end of 2020 or early 2021


A dummy cavity could be used in one of the slots to replicate cavity geometry, interfaces and cryo-load (example ARIEL ACMuno)



Gate 3B – final series design

- Production cryomodule technical design review complete, released drawings and specifications
- Will define the launch of the TCM1-4 procurements
- How to resolve the schedule mismatch between the TRIUMF schedule and the testing at SM18 and in the SPS
 - We would like to launch final procurements starting July 1, 2021
 - RFD SM18 test is scheduled for completion Oct. 1, 2021
 - RFD SPS test will get results July 1, 2022
- Point for discussion

Proposed schedule in Oct. 2018



TCM0: Would engage TRIUMF earlier and significantly reduce schedule risk once series cavities arrive


TCM0+ - retro-fit for LHC as required

Latest schedule

12/09/2019


WP4- PSM 2019
5th review

Baseline: Dec -2018



LEGEND SPECIFICATIONS FABRICATION & ASSEMBLY INSTALLATION TEST SPARES MILESTONE: ◇ FC - Finance committee


Updated schedule in Oct. 2019



SM18 and SPS RFD tests are after the date TRIUMF would like to fix the CM design


Cavity Tests at TRIUMF

- Propose to receive and test (a subset of?) the cavities at TRIUMF in our large cryostat
 - Best would be to cold test as delivered without venting
 - can the first units be delivered with a test coupler?
- Subsequent test would be to assemble a single cavity with FPC and test the fully assembled unit
 - Would be the only opportunity for a full qualification before cryomodule assembly



Required inputs

- Solid works model of dressed cavity – will be used for planning cavity testing program after receipt of cavity from AUP at TRIUMF
- Discussion of timing of deliverables and configuration of dressed equipment from AUP
- Would need an rf source from CERN before cavity delivery




Goals for 2020

- Execute Gate 1, Gate 2 and Gate 3A at TRIUMF in consultation with CERN
 - Establish scope
 - Agree on detailed design for TCM0
 - Establish acceptance criteria for cavities at TRIUMF
 - Establish acceptance criteria for cryomodules at TRIUMF
- Launch procurement of TCM0, fixtures and tooling


VECC Injector Cryomodule Transport

Transport of VECC ICM2

- In 2008 TRIUMF signed an MOU for the construction of a second Injector Cryo Module (ICM2) to be sent to VECC.
- This module is a twin to ICM1 that is currently operational at TRIUMF
- ICM2 hosts one nine cell 1.3GHz cavity, two 50kW FPC, coaxial HOM dampers





Journey to Kolkata




Total travel to VECC includes;

- 530 km of road travel
- 20 hours of flight time
- 5 freight transfers
- Via YVR, PDX, HKD and CCU



Lessons Learned from LCLS-II




Tom Peterson – TTC 2019




- During shipment from FNAL to SLAC it was found that a number of bellows had cracked and vented the cavity string to atmosphere.
- It was found that vibration from road noise had driven a resonance and it had fatigued in the 3400 km (2130 mile) trip.


Transport Frame



Shipping Frame



Skeleton Support Frame



Complete Transport Frame


- After numerous simulations it was determined that ICM2 would be too fragile and sensitive to vibrations to transport as one complete device.
- The Yellow Frame is designed to provide support to prevent yielding of the internal components.
- The Yellow Frame is supported in the Blue Frame using ten wire rope springs to provide vibration and shock isolation.

Transport frames



The two frames – internal frame not yet painted

Lid and cold mass lowered into frame





Wire Rope Isolators

Springs are VibroDynamic FH60-3608-C2 wire rope isolators



Custom supports – ie Coupler bracket

- Brackets are fabricated from water jet cut and welded $\frac{1}{4}$ " steel plate.
- Support bar is 2x2 $\frac{1}{4}$ " steel L-angle
- Bracket connects to the coupler over the cover flange allowing attachment of existing aluminum supports.
- All bolted connections are slotted to allow adjustment.




Disassembling and Packing ICM2


- The ICM was disassembled, small components were documented then packed into 10 individual boxes, with a combined weight of 275 kg (600 lb)
- The vacuum tank was placed on a pallet and crated separately.
- The cold mass and top assembly were then installed in the yellow frame and critical components were attached to the frame.
- Photos were taking during the entire process to create a set of assembly instructions for the technicians at VECC to follow, to put ICM2 back together.

Proposed Procedure for VECC Injector Re-Assembly		
Document-174411	Release No. 1	Release Date.: 2019-09-12

11. Remove the Tuner/Cavity support cross bars (2 locations).



12. Remove 2.75" Conflat blank from coupler cold end cover.



20190912 102400 Template: Document-18187 Rel.7 Page 9 of 35


Vibration and Shock Monitoring



MIDE – SLAM STICK

3 axis accelerometer
8 GB storage
12.5 to 3200 Hz sample rate
22 hour internal battery

Three SLAM STICK® sensors are installed and two 7.2 Ah AGM batteries are installed keep the sensors charged for 15 days.



Two are installed on both yellow and blue frame, configured for high resolution vibration study sensors



One configured for low resolution shock/environmental watchdog w/ 40 days of memory

Vibration Testing and Final Crating



Results from a drop test that shows the attenuation of shock loads between outer (CH1) and inner frame (CH2)

This test showed a 90% reduction in a 3g external shock



ICM2 was then packed in three wooden crates

Shown loaded on an air-ride flat deck as it begins long journey to VECC

Summary

TRIUMF has secured funding to construct and deliver five RFD Crab Cavity cryomodules to the HiLumi LHC Project in Collaboration with CERN and HiLumi partners.

We would like to set the dates of near term TRIUMF project milestones, to finalize the scope, to discuss acceptance tests after receipt of cavities and after assembly of the modules.

TRIUMF has gained recent experience in transporting a cryomodule to India – now in transit.

