



High Order Corrector update

Marco Statera
on behalf of the LASA team
INFN Milano - LASA



9th HL-LHC Collaboration Meeting
Fermilab – Oct 15th 2019



OUTLINE

- Scope: the High Order Correctors magnets
- Overview on HO Correctors
- The prototypes
- The series production
- Next steps
- Conclusions

High Luminosity LHC

- **LHC** integrated luminosity 300 fb^{-1} by 2023
- **HL LHC**
 - upgrade interacting regions 2024/26
 - 3000 fb^{-1} integrated luminosity by 2038


LHC / HL-LHC Plan



CERN courtesy



THE LOW BETA SECTION and the High Order Correctors



73.6 m



IP



by P. Fessia

b3 b4 b5 b6
a3 a4 a5 a6 a2

half batch

SCOPE - High Order Correctors

- The INFN-LASA follows the design, construction and test of the 5 prototypes of the High Order (HO) corrector magnets for the HL interaction regions of HL-LHC. KE2291
- The INFN-LASA will follow the series production of the HO corrector magnets for the HL interaction regions of HL-LHC. KE3085

ADDENDUM No. 2 KE3085/TE/HL-LHC

to

FRAMEWORK COLLABORATION AGREEMENT KN3083

between

THE EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH (CERN)

and

Istituto Nazionale di Fisica Nucleare (the “Institute”)

concerning


Collaboration in design, procurement and testing of the high-order orbit corrector superconducting magnets in the framework of the High Luminosity upgrade for the LHC at CERN

30th Nov 2017

54 S.C. High Order
Corrector magnets



HO CORRECTOR MAGNETS ZOO



Tested 2019
MCQSXFP1b


NbTi SuperFerric design

Geometrical lengths:

200 mm - 265 mm


12P, S4P: 540 mm – 580 mm

MCSXFP1




Tested 2016
MCDXFP1


MCOXFP1



Tested 2017
MCTXFP1



Tested 2018




Tested 2018

Design

Construction & Test

- 5 protoptypes
- 54 series magnets

Round Coil Superconducting Magnet
MgB₂demonstrator



Tested 2019



SUPERFERRIC DESIGN

NbTi superconducting coils

- Racetrack
- Insulation by S2 glass reinforced material

Superferric design

- Compact and modular
- Strong contribution of the iron poles
- Field quality influenced by the shape of the poles



constraints

- Longitudinal dimension
- Quench protection
- Small dimension: 84kN series production (6 magnets)

magnet	Ic @ 4.2 K	Margin @4.2 K	Margin @1.9K
4P S	315.5 A	42.3 %	57.1 %
6P	225.5 A	53.4 %	>60 %
8P	230.2 A	54.4 %	>60 %
10P	255.7 A	58.9 %	>60 %
12P N	232.6 A	54.9 %	>60 %
12P S	230.2 A	54.4 %	>60 %


Quench protection

- No energy extraction (but 4P)
- 60% margin @ 1.9 K


MCQSXFP1

length	538 mm
integrated field @ I_n @ r50 mm	0.700 Tm
magnetic length	401.1 mm
energy @ I_{nom}	30.8 kJ
harmonics	$B_6 = -30 U$ at low current $B_6 = 30 U$ at I_{op} $B_{10} = -8 U \div -12 U$

- $I_{nom} = 174 A$ $I_u = 197 A$
- COILS
 - 754 windings
 - 815 m of Φ 0.7 mm NbTi




Connections on a PCB
board (Arlon N85)
Double V taps




EM DESIGN

- nominal current 174 A
- field integral 0.7 Tm
- ultimate current 197 A






modified ideal pole shape
(wire EDM laminations)



QUENCH protection
OPERA + QLASA
1.5 Ω dump resistor
ground in the middle
Max temperature 145 K
Max voltage 235 V

Assembly



Saes Rial Vacuum
Dec. 2018



First Cooldown and Energization

- Controlled cool down: <100 K/m
- Training up to nominal

- Electrical problem





Event n.13 **B4**


- Precursor
- Recovered transitions in different coils

Event n.7

- Voltage instability during the discharge
- Tiny effect on current




Event n.15



Damaged Coil

bridge





Hypothesis:



- Internal short originated in the quenched coil n.1
- Discharges between output wire and windings
- Inner layers not damaged

Numerical Model



- Numerical model implemented in LTSpice, Netlist forma (M. Prioli)
- Coil 1 split into two parts:
 - Coil 1A: **7 high-field layers** bypassed by a short-circuit
 - Coil 1B: 19 layers normally in series with the rest of the circuit
- Mutual inductance matrix (5 x 5) computed in Opera (S. Mariotto)
- Quench originated in the high-field zone (Coil 1A)
 - The resistance is not evenly distributed between coil 1A and coil 1B
 - Simulated distribution is 37% for coil 1A and 63% for coil 1B
- The **short resistance** is a variable
 - It is initially high ($\sim 10 \Omega$), then decreases due to a local welding ($\sim 0 \Omega$) then increases ($\sim 1 \Omega$)



Secondary Faults





Numerical Model: Results



Two New Coils

- all coils compliant
- the 2 new coils installed




Quality Control Improvements

- The first test of MQSXF1 proved that the QA procedures and the QC of the coils inter-turn and inter-layer insulation are fundamental in view of the series production
 - Insulation damages may be less severe than that in coil n. 1
- How to implement the early defect detection?
 - Ground insulation test
 - Resistance measurement
 - ➔ ■ PJ method (capacitor discharge)
 - ➔ ■ Ferromagnetic coupling


PJ Test

- Charged capacitor connected across the coil under test





- Surge tester
- $C=2\text{ nF}$, $V=5\text{ kV}$

- Oscilloscope
- Capacitor bank (up to 400 V) and control unit
- High voltage probe
- Coil



PJ test results

- Following the analysis, C was set to 20 nF
- One turn in short was reproduced





M. Prioli



- The short can be easily discerned, measurement are repeatable

Ferromagnetic coupling - setup

- Oscilloscope
- Signal generator
- 4 quadrants PC
 - Low AC voltage (36 V per coil)
- Pickup coil
- Ferromagnetic core
- 2 coils



M. Todero



M. Statera


Ferromagnetic Coupling - Measurements

- Optimal frequency 500 Hz

- Allows also to distinguish the origin of unbalance (number of turns or short)

- Optimal frequency 500 Hz

- Allows also to distinguish the origin of unbalance (number of turns or short)



M. Prioli

Second Assembly Assessment

Coil


- Geometry
- HV ground insulation (2,5 kV)
- Wire-wire insulation (2kV), turns

All coils are compliant
(spare coils tested up to 7 kV)



Magnet

- Laminations' profiles and slits
- Alignment of the assembly
- HV ground insulation of the magnet (up to 2 KV)




procedures validated

- second assembly
- coil replacement



Magnet Ground Insulation

resistance [$M\Omega$]



Power Test

- Most quenches in new coils
- Good stability after reaching 200 A ($> I_{ult}$ 197 A)
- Stable 1 h @ ultimate after thermal cycle




B1	B1
B3	B3
B5	B3
B3	B1
B1	B4
B3	B3
B1	B3
B3	B3
B4	B4
B1	B3
	B3

Test at INFN-LASA



Dinamic Inductance


Measured during current ramps



High reproducibility
Good agreement
with simulations

Single Point Field Measurement

- Low accuracy positioning
- Field quality measurement at LASA in 2019





Field calculated in case of the damaged coil

several ramps
two assembly
Lines: positioning error
Dots: calibration errors

Splice Resistance

- Splice resistance measurement
- dedicated channels in DAQ
- 3 measurement
- about 10 n Ω




D. Pedrini


M. prioli

Round Coil Superconducting Magnet

demonstrator




- Multipolar MgB₂ magnet
- Inner bore ϕ 150 mm
- Single MgB₂ coil
 - Diameter > 200 mm
 - Wire diameter 1 mm
 - T_c 39 K




G. Volpini et al. Eletromagnetic Study of a Round Coil Superferric Magnet, IEEE Tr. App. Sup, 26, 4 (2016)

single module




single coil



No quench training
The Coil is stable at the Ultimate Current (108% I_{op})
Maximum value of the current reached: >75% of the Short Sample Limit

Single coil and RCSM test results


- **Ultimate current reached** without any training
- **1 h stability** test successfully passed
- 3 different spontaneous quenches occurred at:
 - **243 A**, single coil
 - **236 A**, RCSM



Load line comparison

- Single coil: **73%** of load line
- RCSM: **78%** of load line


Compatible with wire degradation of 21.4% in the coil ends, during winding procedure



Differential inductance in RCSM

- **Eddy currents in superconductor:** excluded because the inductance increasing occurs at high current
- **Eddy currents on non-laminated ARMCO iron:** excluded because the same phenomenon can be seen during the single coil test and is excluded by OPERA simulation
- **Resistive region growing (current sharing regime):** excluded in the coil ends by measurement, not excluded in the winding
- Heat dissipation in **current leads** (?)

Differential inductance




Opera 3D simulation

Magnetic field

Hall probe signal taken from different current ramp-up and ramp-down

- **high repetibility** of the magnet with no degradation at high current level
- **Difference of about 20%** between the magnetic field measured and simulated:
 1. Presence of the air gap & holes: excluded by OPERA 3D simulation
 2. Hall probe calibration: ongoing test
 3. Hall probe positioning: excluded by OPERA 3D simulation
 4. B-H curve: excluded



SERIES PRODUCTION

- 17/9/2018 call for tender
- 15/1/2019 evaluation of quotations
- 28/2/2019 contract awarded by Giunta Esecutiva to Saes Rial Vacuum (SRV)
- 17/6/2019 contract signed
- 24/6/2019 kick off meeting
- 1/10/2019 production started (machining)

SCHEDULE

In May 2018 an “Engineering Change Request” has been requested by CERN, to increase magnetic (and geometric) length of 3 magnets and decrease the 4-pole skew

In Feb 2019 an electrical problem with the skew quadrupole

Milestones:

M1.1	Engineering Design of the series completed	July 2018
M1.2	First coil wound	May 2019
M1.3	First batch delivered to INFN-LASA for test (2 magnets per type)	November 2019
M1.4	Second batch delivered to INFN-LASA for test (2 magnets per type)	July 2020
M1.5	Third batch delivered to INFN-LASA for test (2 magnets per type)	March 2021

Deliverables:

D1.1	Award for the contract of the series construction	January 2019
D1.2	First tested batch delivered to CERN (2 magnets per type)	March 2020
D1.3	Second tested batch delivered to CERN (2 magnets per type)	November 2020
D1.4	Third tested batch delivered to CERN (2 magnets per type)	June 2021

Nov 2020
Jul 2020 (1a Mar 2020)
Dec 2020
Jun 2021


Feb 2019
signed Jun 2019

Oct 2020 (1a Jun 2020)
Mar 2021
Sep 2021

Schedule 2

- Engineering **done**
- Procurement: S2 insulated NbTi wire **not delivered** (Aug 2019)
- Machining **started**
- Winding and assembly not affected


Schedule 3



FIELD MEASUREMENTS AT LASA

- measure field quality of MQSXF1b at LASA
Nov-Dec 2019
 - New frame supporting the magnets **done**
 - Install field probe (not the final one) **done**
 - Cabling for series tests **ongoing**
 - Install skew quadrupole
- Finalize the field probe for the series **ongoing**
(L. Fiscarelli, S. Mariotto)
- Assembly of a new power converter 600 A
 - Dump resistance
 - IGBT polarity switch

ongoing



CONCLUSIONS

- High Order Correctors prototypes tested
 - 5 superferic and 1 Round Coil Superconducting Magnet
 - Tested second assembly procedure
 - Updated QC for early defect detection
- High Order Correctors series production started
 - Engineering done, procurement ongoing, machining started
- Delay of about 6 months with respect original plans -> scheduled 3 month at last delivery
 - First series magnet in 2019
- Field measurements at LASA in preparation
 - First measurement in 2019
 - Cabling for series magnets



Istituto Nazionale di Fisica Nucleare
Laboratorio Acceleratori e Superconduttività Applicata

LASA team

F. Alessandria, G. Bellomo, F. Broggi, S. Mariotto, A. Paccalini, A. Pasini, D. Pedrini, A. Leone, M. Quadrio, M. Prioli, M. Sorbi, M. Statera, M. Todero, C. Uva
CERN A. Musso, E. Todesco



SPARES

