



## Test Facility Status at FNAL

Guram Chlachidze  
Fermilab



9<sup>th</sup> HL-LHC Collaboration Meeting  
Fermilab, Oct. 14–16 2019



# Introduction to Magnet/Cavity Test Facility

- Magnet test facility (MTF) originates from the Main Ring period, when the first main accelerator was built at Fermilab
  - First conventional magnet tests started by the end of the 1960s
- Testing of the first superconducting accelerator magnets started in the late 1970s
  - MTF cryogenic plant in operation since 1978
- Vertical Magnet Test Facility (VMTF) - the main R&D stand for the SC magnets, in operation since 1996
  - LARP magnets – TQ, LQ, HQ, short MQXF model, and many other magnets were tested at VMTF
- Vertical Cavity Test Facility (VCTF) commissioned in 2007 to support the SC RF cavity R&D program at Fermilab
- Currently SC RF cavity and magnet test facilities share all the plant liquefaction capacity

# Magnet Test Facility (cont'd)



# Cryo-plant Improvements

- Various improvements are planned or already made to improve overall reliability of the cryo-plant
- Already implemented full stream purification system helps to control contamination level
- New liquefier will be procured soon, increasing total LHe make rate to 600 ltr./hour and total liquid storage volume to 14,000 ltr.
  - Current CTI-1500 liquefier with liquefaction rate up to 300 ltr./hour and 10,000 ltr. storage dewar for the LHe
  - New liquefier is expected to be fully operational in 2021
- Combination of higher liquefaction and LHe storage capacities will significantly increase throughput in magnet and SRF cavity testing
  - Practically no downtime due to cryo-plant maintenance



# More on Cryo-plant


- Five 30,000-Gal ( $\sim 114 \text{ m}^3$ ) buffer tanks are used for storage of helium gas



- One 30,000-Gal buffer tank is used for the helium gas recovery after high-current quenches at TS4/VMTF
  - Longer transfer line helps to warm up the GHe

# Horizontal Test Stand

- The Horizontal Test Stand (TS4) previously was used for testing the present LHC inner triplet quadrupoles at FNAL in 2001-2006
- Test stand upgrade currently in progress to accommodate new Q1/Q3 cryo-assembly design and meet new test requirements
  - Some of old components will be refurbished and re-used



Old LHC cryo-assembly at the horizontal test stand

# Power Systems

- Existing 30 kA power system will be used for Q1/Q3 cryo-assemblies horizontal test
  - 6 PEI-150 (150 kW) power supply units connected in parallel, each delivering 5 kA at 30 V
- New 20 kA rated flexible water-cooled power cables, connecting the solid bus bar to the top plate, were recently installed and tested in a shorted bus configuration
- External energy extraction system based on a solid-state dump switch
  - SCRs mounted in water cooled heatsinks
  - Dump resistor configurations from 2 to 120 m $\Omega$
- No issues are expected with continuous operation at currents up to 25-26 kA
  - 10-15 min or less of continuous operation at currents above 27 kA




# Power Systems (cont'd)

150 kW Power Energy Industries  
(PEI) PS module



Dump Resistor Cabinet






# HL-LHC AUP Magnet Tests


- Q1/Q3 cryo-assemblies with two MQXFA magnets inside will be tested at Fermilab's Horizontal test stand
- Currently project scope is a horizontal test of 12 cryo-assemblies (2 pre-series, 10 production and re-work)
  - MQXFA magnets to be trained at BNL
- 3 power leads at TS4 will allow independent powering of magnets in the cryo-assembly
  - Individual magnet training possible if necessary
  - Independent magnet protection with new CLIQ connection scheme
- Comprehensive magnetic measurements including magnet alignment and harmonics measurements are expected during horizontal tests at Fermilab

# Cryo-Mechanical Upgrades

- Various test stand components are under upgrade right now. The plan is to complete most of upgrades in Feb.-March 2020 followed by a zero-magnet test
- Overhead crane upgrade was required for lifting Q1/Q3 cryo-assemblies with two magnets
  - Most cost-efficient solution was to add one more 25 T crane
  - Two cranes in tandem provide a total lifting capacity of 50 T
- New adapter box allows connecting the existing Feed box with the new cryostat




# Adapter Box



# Adapter Box Status

- Adapter box assembly currently in progress.
  - Most of (long lead-time) parts/components arrived
  - Expected to be ready for installation at TS4 by the end of this year






# New location of Lambda plug

- Separation between the 4.5 K and 1.9 K areas moved from the Feed Box to the adapter box (interface between the FB and the cryo-assembly)
- We can test cryo-assemblies at high pressure, i.e. under conditions close to the operation at LHC
- Other obvious advantages
  - Reduced consumption of LHe
  - Fast quench recovery


Lambda plate (old location)

New location  
of lambda plug




# Lambda plug

- CERN developed lambda plug design was adopted for Stand 4
  - Lambda plug is made of Ultem 1000
- Lambda plug design at Fermilab is modified to accommodate 3 power leads
- Lambda plug prototype assembly is ready for cold testing in LN2
  - Leak rate check at 300 K and cold
  - ~280 psig pressure drop will be created by GHe supply
  - Several thermal cycles




# More Cryo-Mechanical Upgrades

- Quench recovery system design and analysis is complete, the required sizing is established
  - Eliminate unexpected and unnecessary venting of helium
  - Quench system was reviewed in Jan. 2019, assembly after the zero-magnet test
- New Return End box just delivered



- 3-point mounting support system is developed and fabricated
  - CERN designed anchor for axial support will help to restrain the cryo-assembly against the longitudinal forces

# Horizontal Test Stand layout



- The HFU and CLIQ racks are on wheels and are moved to the lead and return end close to the feed throughs. Power cables are out of feed throughs, reach the interface box, and then to HFU rack.
- A 4x4 wireway picks up all QD and other cables and convey them to the QD rack that is on mezzanine.
- Power solutions by test stand are illustrated in red.




# Quench Protection and Monitoring

- QPM Requirements and Specifications are developed
  - A three-tier design will be deployed: Tier 1 – primary QD, Tier 2 – secondary QD, and Tier 3 – System Monitoring and Data Management
- High reliability is achieved with two independent systems: Digital (primary) and Analog (secondary) quench detection
  - Validation time implemented
  - Current dependent thresholds applied to avoid voltage spike trips
- Coupling loss Induced Quench (CLIQ) system is included in the magnet protection along with the quench heaters
  - CLIQ fabrication in progress, delivery in Nov.-Dec. 2019
- Heater Firing Units (HFU) are provided by CERN
  - 4 units arrived, (12 + 2 spares) - to be delivered this year
  - FNAL QP requires additional features: crowbar function, load status, charge status and front panel indicators and manual controls

# Quench Detection System Status

- Full chassis of Analog and Digital quench detection modules are assembled
- AQD and DQD final tests in progress. Full integration tests of the AQD, DQD and Tier-III will be done in Nov.-Dec. 2019
- QPM final commissioning during the zero-magnet test in Mar. 2020

**AQD (left) and DQD chassis**



**DQD Module**




# Magnetic measurement systems

- Rotating coil and Single Stretched Wire Systems will be used for alignment, field strength and harmonics measurements
- Measurement system requirements and design specifications were developed in 2018




**New SSW system**

U.S. HL-LHC Accelerator Upgrade Project	<b>Magnetic Measurement Systems Requirements and Design Specifications</b>	US-HILumi-doc-818 Date: Jan. 10, 2018 Page 1 of 10
 <b>U.S. HL-LHC Accelerator Upgrade Project</b>  <b>Magnetic Measurement Systems Requirements and Design Specifications For Q1/Q3 Cryostat Assemblies Horizontal Test</b>		
Prepared by: Joe DiMarco Date: 1/10/2018	Organization FNAL	Contact <a href="mailto:dimarco@fnal.gov">dimarco@fnal.gov</a> (630) 840-2672
Reviewed by: Guram Chlachidze Date: 1/10/2018	Organization FNAL	Contact <a href="mailto:guram@fnal.gov">guram@fnal.gov</a> (630) 840-4622
Reviewed by: George Velez Date: 1/22/2018	Organization FNAL	Contact <a href="mailto:velez@fnal.gov">velez@fnal.gov</a> (630) 840-2303

- Single Stretched Wire (SSW) system is already assembled
  - Currently in commissioning
  - Similar systems are successfully used for LCLS-II, Mu2e, etc.

# Magnetic measurement systems (cont'd)

- Rotating coil system DAQ was successfully tested with MQXFS1 short model at VMTF
- Fermilab developed PCB measurement probes are used at BNL, LBNL and FNAL
  - Currently dual 110/220-mm and single 440-mm long probes are available.
  - Work on dual 110/110-mm probe in progress.





# Precise magnetic measurements at Stand 4

- For accurate measurements of the local magnetic center and field angles we need to know the measurement probe location and orientation inside the magnet with high precision
- Laser tracker will follow and measure 3 targets (reflectors) on a probe
  - Dedicated software developed for finding and measurement of targets
  - Tests currently in progress at magnet test facility

The screenshot displays the software interface for the laser tracker. It includes a control panel with buttons for 'Init', 'Disconnect', 'Spherical?', 'Tracker Status', 'PowerLock', and 'NotReady'. A 'Data File' field is set to 'ProbeShaft0m-12m.csv'. The 'Positioning System' section has 'Get Targets', 'Find.MeasureTargets', and 'Target Estimation' buttons. A 'Measurement History' table is visible, showing columns for H Est, V Est, D Est, H Meas, V Meas, D Meas, Timestamp, and Label. The table contains several rows of data, all labeled as 'Duplicate'. At the bottom, there are 'Notes', 'Start Measurement', and 'SaveToFile' buttons. A status bar at the bottom indicates 'File saved: 4/26/2019 4:45:27 PM'.

H Est	V Est	D Est	H Meas	V Meas	D Meas	Timestamp	Label
35.319725	88.959193	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:59 PM	Duplicate
35.711099	90.183803	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:09 PM	Duplicate
35.833482	89.857860	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:19 PM	Duplicate
35.932483	89.591492	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:29 PM	Duplicate
36.266354	90.111058	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:39 PM	Duplicate
36.294121	90.116032	10000.000000	0.000000	0.000000	0.000000	4/26/2019 4:53:49 PM	Duplicate



Probe with 3 targets inside the warm bore tube

J. Nogiec

# Process Controls Upgrade

- High level architecture and design has been finalized
- Old PLC cabinets were disconnected and moved out from the platform at Horizontal Test Stand
- Fully populated new (S7/400, Lakeshore and I/O) cabinets are installed, PLC networked
- Work on the PLC programming & integration with iFix in progress
- Terminations of the control instrumentation in Jan. 2020
- New system commissioning is expected in Jan-Feb 2020




**New PLC cabinets at TS4**

# Zero-magnet test

- Zero-magnet test – major milestone for Horizontal Test Stand upgrade
  - Most cryo-mechanical upgrades, power leads, lambda plug, controlled cool-down, as well as new QPM system will be commissioned

Test stand 3D model for zero-magnet test



# Summary

- Thanks to experienced and hardworking team Horizontal Test Stand upgrade is on track to meet very important milestone - zero-magnet test in March 2020
- Recent and planned cryo-plant upgrades will allow reliable cryogenic operation of the magnet test stand in parallel with the SRF cavity testing
- Overhead crane capacity at MTF now is adequate for lifting and handling Q1/Q3 cryo-assemblies
- Upgrade of various test stand components will be completed soon
  - Adapter box assembly in Nov.-Dec.
  - Lambda plug prototype cold test expected in a week or two
  - New transfer lines/warm piping installations in Nov.-Dec.
- Quench detection integration tests in Dec. 2019
- Preparations for pre-series cryo-assembly test will start immediately after zero-magnet test



# Backup Slides

# More on Cooling Capacity

- Full stream purification system helps to control contamination level of H<sub>2</sub>O, N<sub>2</sub> and O<sub>2</sub> increasing overall cryo-plant reliability
- New Helium compressor skids - 4 Kinney pumps in parallel used for TS4/VMTF and VCTF
  - Total pumping speed of 10 g/s at 12 torr (4.5 K operation) and 15 g/s at 20 torr (1.9 K operation)
- 10,000 Gal LN<sub>2</sub> dewar filled twice a week
  - Dry gas in warm bore
  - 1<sup>st</sup> stage cooling of the cold box
- Industrial Cooling Water (ICW) system feeds the low conductivity water (LCW) for cooling power supplies or conventional magnets